



Cheatham and Associates, P.A.
Consulting Engineers

May 3, 2010

ADDENDUM NO. 2

**HVAC RENOVATIONS – JAMES KENAN HIGH SCHOOL
DUPLIN COUNTY SCHOOLS
KENANSVILLE, NORTH CAROLINA
C&A Project No. 09.50**

I. NOTICE TO ALL BIDDERS:

The following items shall take precedence over the plans and specifications of the above named project and shall become part of the contract documents. Original items of the specifications and information indicated on the drawings not herein modified, amended, voided, or suspended shall remain in effect.

REMINDER: Contract will be single prime contract with all general and electrical work included in the mechanical contract.

II. BIDDING TIME, DATE, AND LOCATION:

- A. Bids will be received on Thursday, May 6, 2010 and will be opened at 3:00 pm local time.
- B. Opening of bids will be held at the **Conference Room, Duplin County Maintenance Building, 249 NC Highway 11 South, Kenansville, NC**

III. CHANGES TO SPECIFICATIONS:


- A. Project Manual Page 75, Section 01501 – Construction Facilities, Paragraph 1.02 Definitions, Item B-3: Delete Item B-3 and add: “The Contractor may use the toilet facilities in the Locker Rooms provided he maintain them in a clean condition. Failing to do so will require the Contractor to provide portable toilet facilities.”
- B. Soon after school is out for the summer, the Owner will remove the furniture from the classrooms and line it up against one side of the corridor wall. The Owner will store computers, tools, records, etc. in a locked area.

IV. CHANGES TO THE DRAWINGS:

- A. Drawing Sheets C-1 and C-2 show corridor ceiling to be removed and replaced with new ceilings. The Contractor shall have the option to leave the ceiling grid in place and remove necessary tiles as required to install his system. The Contractor may run his work parallel to the corridor in the classrooms and not lower the ceiling grid. Adjustments will be made to the ceiling diffusers to miss the steel structure. The new lights shall be installed as near to the shown location as possible to fit into the existing grid.
- B. Drawing Sheet C-2, Note “3” shall be changed to read: “Butt ceiling tile up to wall and run grid in a straight line from corner to corner.”

Prepared by,

Cheatham & Associates, P.A.


James H. Cheatham Jr., P.E.
JHCjr:dsb