

CONTRACT # N40085-10B-0426
PROJECT# 10M032CN
MACC # 10-0426
MAXIMO # 4270353

TITLE: BLDG 27 REPLACE TERRACOTTA SEWER LINE

ATTACHMENTS:

1. Site Map #1
2. Site Map #2

SCOPE OF WORK: The contractor shall provide all material, labor, equipment, and supervision required to accomplish the following:

General description Disconnect sewer lateral from existing Terracotta line and install new sewer line. See map for details and location.

Detailed requirements and specifications – The contractor shall:

1. Locate existing sewer pipe at bldg 27 and bldg 11.
2. Connect to existing clean outs at front and left side of bldg 27 and install approximately 312ft of 4" SCH 40 PVC pipe. See drawing for location and more information.
3. Contractor shall demo existing lift station at bldg 27 and deliver to building 1202. Call Mr. Dave Marshburn at 910-340-9349 to schedule equipment unloading.
4. Install approximately 170ft of 6" SCH 40 PVC pipe and connect to existing sewer main. Install 4" clean out at each 90 degree turn and every 100 feet. See map for location and more information.
5. Locate 4" sewer pipe at corner of bldg 11 and connect 4" pipe (approximately 40ft) to new 6" sewer pipe. See drawing for location.
6. Contractor shall make sure that the line is properly graded to gravity flow to main.
7. Contractor shall abandon old terracotta pipe in place and cap off.
8. All grounds, sidewalks and roads disturbed by the contractor shall be repaired. Disturbed grounds shall be covered with top soil or gravel as appropriate, raked, and seeded. All ground repairs shall create a smooth uniform surface for future mowing operations. Gravel size and type shall match existing.

SUBMITTALS: None

SPECIAL SCHEDULING AND ACCESS:

1. The contractor shall coordinate work schedule and access to work with POC James Rohr (910) 451-3806.

SPECIAL CONDITIONS:

1. The contractor shall provide, maintain, empty 3 each porta-potties while heads are unavailable for tenant use. The portable heads shall be removed within 48 hours after heads become available for tenant use.
2. The contractor is responsible for scheduling underground utility locating prior to any digging. The contractor shall bear all costs incurred as the result of damage to any functional underground object or utility (ex: power lines, water lines, sewer lines, telephone, television cables, fiber Optus, etc.)

HAZARDOUS MATERIALS: None Identified

ENVIRONMENTAL: None