

TEST FIRE DAMPERS, BUILDING NH 100 NAVAL HOSPITAL CAMP LEJEUNE, NC

- 1. GENERAL INTENTION.** It is the declared and acknowledged intention of this solicitation to obtain the supervision, expertise, labor, materials, and equipment to test fire dampers in building NH100, Naval Hospital, Camp Lejeune, NC.
- 2. LOCATION.** The work location is the Naval Hospital, 100 Brewster Boulevard, Camp Lejeune, North Carolina.
- 3. DETAILED REQUIREMENTS.** The Contractor shall:
 - a. Take such steps as may be reasonably necessary to ascertain the nature and location of the work and general local conditions that could affect the work or the cost thereof and should perform an inspection of each repair item, taking their own measurements and developing their own material requirements in accordance with the specifications. Failure to do so will not relieve the contractor from the responsibility of estimating properly the difficulty or cost of successfully performing the work. Adhere to all specified information within these pages. Shall meet or exceed the manufacturer's specifications and adhere to guidelines as follows:
 - b. Prior to testing coordinate and schedule with the hospital staff and heads of each department along with the communications center to facilitate the execution of the required work.
 - c. Prior to work, protect all finishes and surfaces from damage. Remove, mask, or otherwise protect hardware, hardware accessories, machined surfaces, lighting fixtures, public and private property, and other such items not to be demolished. Following completion of demolition and repair, workmen skilled in the trades involved shall reinstall removed items. Restore and repair any surfaces damaged during testing to its original condition.
 - d. Investigate and test approximately 241 fire dampers in building NH-100. (Drawings will be provided by the Naval Hospital's Facilities Maintenance Department) Testing shall determine and document if the dampers meet NFPA standards. All inspections and testing need to be documented indicating the location of the damper, date of inspection, name of inspector and deficiencies discovered. The contractor shall provide a design and solution, with an estimated cost to correct any failed dampers discovered during testing.
- 4. SPECIAL REQUIREMENTS. The Contractor shall:**
 - a. Commence work under this contract within thirty (30) days after award, and prosecute the work diligently.
 - b. Make adjustments to work scheduling and execution as a result of working with an active medical facility and conduct the specific work as described to individual sections of the building as laid out or blocked off by the Officer in Charge.
 - c. Complete the work within thirty (30) calendar days after commencement.

