


## NTS

3. LIMIT CONSTRUCTION ACTIVITIES TO DESIGNATED AREAS OF WORK.
2. THE BUILDING/ FACILITY WILL REMAIN IN USE/ OCCUPIED DURING CONSTRUCTION.
3. PROVIDE THE OWNER A MINIMUM 48 HOUR NOTICE AND OBTAIN APPROVAL FOR ACTIVITIES THAT COULD INTERRUPT OR IMPACT THE USE OR OPERATION OF THE EXISTING BUILDINGS/ FACILITIES.
4. THE CONTRACTOR, SUBCONTRACTORS AND THEIR EMPLOYEES SHALL ABIDE BY ALL BADGING, SECURITY, AND CONDUCT REQUIREMENTS REQUIRED BY THE OWNER.
5. MAINTAIN CORRIDORS AND PATHS OF EGRESS AT ALL TIMES. DO NOT BLOCK EXITS, STAIRS, RAMPS, ETC.
6. BUILDING FIRE ALARM AND OTHER LIFE SAFETY SYSTEMS SHALL REMAIN OPERATIONAL. PROTECT SYSTEMS AND DEVICES FROM DAMAGE.
7. CONTRACTOR SHALL DOCUMENT EXISTING CONDITIONS.
8. CONTRACTOR SHALL PROTECT ALL EXISTING STRUCTURES, FINISHES, PARTITIONS, BUILDING SYSTEMS AND OTHER ELEMENTS THAT REMAIN FROM DAMAGE.
9. CONTRACTOR IS RESPONSIBLE FOR ANY AND ALL DAMAGE TO EXISTING BUILDING, STRUCTURE, FINISHES, PARTITIONS, BUILDING SYSTEMS AND OTHER ELEMENTS TO REMAIN.
10. ALL AREAS OF CONSTRUCTION SHALL BE SECURED SO AS TO LIMIT ACCESS BY UNAUTHORIZED PERSONS.
11. ALL FACILITIES WHERE CONSTRUCTION OCCURS SHALL BE SECURED DAILY UPON THE COMPLETION OF THE WORK DAY. SECURITY METHODS & EMERGENCY ACCESS SHALL BE APPROVED BY THE OWNER.
12. SEE GENERAL NOTES ON G601
13. SEE PLUMBING, MECHANICAL, AND ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.
14. SEE NYCOM DRAWINGS FOR CASEWORK AND EQUIPMENT INFORMATION.
15. SEE A601 FOR WALL TYPE, WINDOW ELEVATIONS, DOOR SCHEDULES AND DETAILS.
16. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING INSTALLATION OF BLOCKING WITH LABORATORY CASEWORK SUPPLIER.
17. CONTRACTOR SHALL OBTAIN SAFETY CLEARANCE FROM UNIVERSITY'S ENVIRONMENT, HEALTHY, & SAFETY DEPARTMENT PRIOR REMOVAL AND DECONTAMINATION OF ANY LAB HOODS AND BIO & CHEMICAL SAFETY CABINETS.



1 FLOOR PLAN  
A101 SCALE: 1/4" = 1'-0"

# A101

COPYRIGHT © 2017