

# EMMA B. TRASK MIDDLE SCHOOL RENOVATIONS

Addendum #1 April 12, 2019





www.barnhillcontracting.com

New Hanover County Schools Trask Middle School Renovation Wilmington, NC

#### **ADDENDUM #1**

April 12, 2019

To: ALL BIDDERS OF RECORD:

This addendum forms a part of the Contract Documents and modifies the original Project Bid Manual Dated March 31, 2019 and Drawings and Specifications dated March 27, 2019. Acknowledge of receipt of this Addendum in the space provided on the Bid Form is mandatory. Failure to do so may subject the Bidder to disqualification.

#### **General Information**

- 1. Reminder: The last date for questions to be addressed via addendum is April 17, 2019.
- 2. Please note that the civil drawings are laid out on 24x36" drawing sheets, but the rest of the drawings are 30x42". The Architect has printed their sets such that the civil drawings are 24x36 print size on a 30x42 sheet.
  - a. Please ensure that when looking at the electronic files of the civil drawings, they are at the correct scale.
- 3. Provided as an attachment to this addendum is the finish schedule for the 8 Classroom Modular unit. This is provided as reference for those Bid Packages which have work related to setting up of the units.
- 4. Bid Forms will be mailed out to Prequalified Bidders, the week of 4/15. All bidders should receive by Friday 4/19/19.
- 5. Attached is the updated Bidding RFI Log with attached responses. Please review all, as the responses apply to the associated Bid Packages.
- 6. Substitution Request #003 and #004 are provided in the attachments.(Requests #001 & 002 still under review).

#### **Project Bid Manual**

Please make the following corrections to SOW items in the respective Bid Package Scopes of Work – Section 3.

- 1. BP100- General Trades
  - ADD SOW Item 8 This contractor will be responsible for removal of the chain link gate hinge post at the corner of Danny Pence Drive and reinstall following the mobile unit setup. (Trailer is wider than the gate



www.barnhillcontracting.com

opening) This activity will occur a second time when the units are removed from the site at the time of project completion.

- 2. BP220 Abatement and Demo
  - ADD SOW Item 30 Exclude demo note 14 on AD 1.0. this will be completed by BP 390.
  - ADD SOW Item 31 Clarification on scope: Reference demo delineation plan, NOTE: areas of "new work" and "complete" demo (highlighted) this contractor will be responsible for all demo. Wall to wall and to the ceiling. BP 1600 will be responsible for making safe all electrical, and flag all conduit that remains as HOT. BP 1540 will make safe and flag all remaining plumbing. EXCLUDE ALL HVAC DUCT DEMO this will be the responsibility of BP 1550.
- 3. BP250 Turn Key Sitework
  - ADD SOW Item 49 Provide surveyed layout for the mobile unit setup. CAD file to be provided by CM.
  - ADD SOW Item 50 All site demo inside the courtyard included.
  - ADD SOW Item 51 This contractor will be responsible for asphalt patch at CM trailer where water connection is made. Assume 100' x 2'.
- 4. BP790 Caulking and Sealants
  - ADD SOW Item 21 All exterior caulk joints are to cut out and replaced as part of this scope of work
- 5. BP 960 Resilient Carpet and Base
  - ADD SOW Item 30 It should be noted that in the majority of VCT replacement areas abatement by others will occur. Preparation for new flooring install should be accounted for.
  - ADD SOW Item 31 Clarification on scope: Reference demo delineation plan, NOTE: 100% of the existing VCT is being replaced, areas outside of those highlighted in the demo delineation plan will be the responsibility of this bid package to demo and replace, all normal associated floor prep included. This phased work will occur over the course of the school year. This will be coordinated with the CM and NHCSS schedule. NOTE: All VCT called out in the highlight portion of the demo delineation plan is the responsibility of BP 220 to remove via abatement.
- 6. BP 980 Acoustical Ceilings
  - ADD SOW Item 25 Clarification on scope: Reference demo delineation plan, NOTE: 100% of the ceiling grid and tile is being replaced, areas outside of those highlighted in the demo delineation plan will be the responsibility of this bid package to demo and replace. This phased work will occur over the course of the school year. This will be coordinated with BP 1600, BP 925, and BP 400. Coordinate with CM.



www.barnhillcontracting.com

#### 7. BP 990 – Painting

- ADD SOW Item 18 If locker room alternate is not taken, this
  contractor will be responsible for minor touchup around interior
  signage during replacement.
- ADD SOW Item 19 Clarification on scope: Reference demo delineation plan, NOTE: 100% of the school being repainted, areas outside of those highlighted in the demo delineation plan will be the responsibility of this bid package for all wall prep prior to final paint, including but not limited to adhesion testing, patching of existing holes, removal of plastic moly anchors and screws, etc.etc. to provide a finished product. This phased work will occur over the course of the school year. This will be coordinated with the CM and NHCSS.

#### 8. BP1010 - Identifying Devices

 ADD – SOW Item 12 - This package will remove and replace the interior signage inside the locker room, as part of the base bid.
 Alternate pricing will be in the event of quantity changes etc. Painting or patching by others.

#### 9. BP 1540 - Plumbing

 ADD – SOW Item 45 - Scope clarification: CM Trailer water hookup will either be by underground water main located in the parking lot near the trailer, or from building main located in the storage room by the kitchen back door. Either way trenching thru existing asphalt will be required.

#### 10. BP 1550 - Turn Key HVAC

ADD – SOW Item 42 - ALL DEMO of DUCT will be by this contractor.
 11. BP 1600 – Turn Key Electrical

- ADD SOW Item 56 Clarification on CM trailer power hook up location, there is a DEP junction box located less than 100' from the trailer location shown on the logistics plan, simple 4x4 and meter box only needed, with all load side wiring.
- ADD SOW Item 57 Clarification on scope: Reference demo delineation plan, NOTE: with 100% of the ceiling grid and tile being replaced, areas outside of those highlighted in the demo delineation plan this contractor will be responsible to coordinate with BP 980 for all demo/replacement of new lighting and ceiling mounted device install. This phased work will occur over the course of the school year. This will be coordinated also with BP 925, and BP 400. Coordinate with CM.
- ADD SOW Item 58 Reference demo delineation plan, in areas of complete demo, this contractor will make safe for BP 220 and flag all remaining hot conduit. All conduit called to be removed by BP 220 will



www.barnhillcontracting.com

be cut back to the furthest Jbox and flagged where the circuit becomes hot again.

#### **Attachments**

- 1. Pre-bid Conference Meeting Minutes dated April 10, 2019 with attachments.
- 2. "First String Space Modular Buildings Finish Schedule"
- 3. Bidding RFI Log with Attached Responses; RFIs 01, 02, 03, 04, 05, 07, & 08.
- 4. Trask Middle School Demo Delineation Plan Sketch
- 5. Substitution Request #003 Hiny Hiders
- 6. Substitution Request #004 Tufftec Bench (Disapproved)

#### End of Addendum #1

# TRASK MIDDLE SCHOOL RENOVATIONS PRE-BID MEETING



April 10, 2019







### Meeting Logistics

- Greetings & Thanks for Attending
- Restroom facilities
- Meeting Sign-In Sheet
- Turn off cell phones
- All Prime Bidding by Pre-Qualification Only
- Meeting Duration NTE 90-Minutes w/ Site Walk
- Will Take Questions / Raise Hand to be acknowledged
- Meeting Minutes & Attendee Listing to be issued via Addendum

# Meeting Purpose

- A Forum for Explanation of Project Requirements & Expectations
- Receive Subcontractor Feedback
- Explain & Understand Project Responsibilities
- Address Unclear Issues, Items and/or Concerns
- Opportunity to Build New Business Relationships
- Identify Those Who Voluntarily Want to Participate/Follow Project Procedures

# Meeting Agenda

- Project Team Introductions
- Project Overview/Description & Project Goals
- Project Documents & Key/Critical Dates
- Bidder Instructions & MWBE Project Participation
- Bid Day Activities & Scope Review/Confirmation Meeting
- Project Logistics, Work Rules & Safety
- Schedule & Schedule Compliance
- Project Administrative & Construction Engineering Requirements
- Quality Control, First Summer Items & Work Scope Summaries
- Closing Comments & Questions
- Preferred Brand Alternates

### Project Team Introduction

- Owner: New Hanover County Public Schools
   Owner Project Representative: Kimberly Gordon
- Architect Sawyer Sherwood and Associates
- Civil/Landscape Engineer CLH Design
- Structural Engineer Woods Engineering
- PME Engineers Cheatham and Associates
- Design Professional(s) Project Representative(s):
  - Doug Sherwood Sawyer Sherwood and Associates

### **Project Team Introduction**

Construction Manager at Risk: Barnhill Contracting Company

Construction Manager at Risk Project Representative(s):

Barry Harden, Vice President of Operations

Brad Martin, Project Executive

Matt Cave, Project Superintendent

Ruben Auvert, Project Engineer

Pre-Bid Communications

Directed to/through Construction Manager/Barnhill Contracting Company

# Project Overview/Description

- Project Location/Address:
  - □ Trask Middle School 2900 North College Road, Wilmington, NC 28405



# Project Overview/Description

#### Project Overview Narrative:

The project consists of renovations to the 92,365 square feet single story existing Middle School. Renovations to the following existing areas: Administration areas with new entry vestibule, Media Center, Class Rooms, bathroom & locker room renovations, courtyard and Exterior Walls/Windows. Building interiors are to consist of CMU, drywall, acoustical ceilings, VCT flooring, porcelain tile and bleacher replacement. The new classroom renovation portion of the project will consist of light demolition, acoustical ceilings, solid surface casework, painting, flooring, and building specialties. The existing restroom renovations will consist of the demolition and reinstall of existing toilet fixtures, specialties and finishes. A new clerestory will be added above classrooms. The roofing for entire school will consist of a low slope PVC roof overlay with roof drains and scuppers. Plumbing, HVAC and Electrical replacements will be made.

### Project Overview/Description

- Address Project Unique Issues:
  - First Summer Abatement & Temp Flooring Activities (refer to Logistics & Partial Phasing Plan; Section One Bid Manual)
    - Short Procurement Period
  - Coordination with Mobile Classrooms
  - Thinking Creatively on starting work
  - ACTIVE CAMPUS!!!!
- Anticipated Construction Duration (Months): 13 (July 2020)
- □ One Bid Date Two Bid Times (9:00 AM & 1:00 PM)
- Expectations of Project Participants:
  - Safety, Integrity, Quality, On-Schedule, Timely Paperwork Processing, Teamwork, Good Neighbor Policy, etc.

### **Project Goals**

- Each Project Participate Intimately Familiar w/ Project Details
- Be Accountable to Do Your Job On Time
- Deliver High Quality Work
- Contribute to a High Productive Workplace
- Manage Construction Process Fairness, Firmness & Honesty
- Managing Safe Site/Workplace No Lost Time Accidents
- Deliver required MWBE Project Participation
- Engage in Project Communication/Coordination w/o Having to be Asked To
- Be "Good Neighbors" to Existing Surroundings and Active School
- All Disputes Resolved at Field Level

### **Project Documents**

- All Project Participants Held Accountable to Project Documents to Include:
  - Drawings dated: 3/27/19
  - Specifications dated: 3/27/19
  - Bid Manual dated: 3/31/19
  - All Addendums: TBD
- Project Participants Have Responsibility to Review ALL Project Documents
  - Do not be Limited to Specific Work Scope
  - Coordination of Work with Work of Others
- Document Availability Plan Rooms & Printing:
  - Barnhill Contracting Company Online Planroom, Barnhill Contracting Company Raleigh & Wilmington Office, Duncan Parnell Wilmington, NC
  - Addendums (as needed) Issued by CM

# **Key/Critical Dates**

□ Last Day for Questions 4/17/19 @ 12:00 PM

Last Addenda Issuance Date
 4/18/19

Bid Day One - Morning Specified Packages Only
 Date & Time 4/25/19 @ 9:00 AM – 12:00 PM

Bid Day One - Afternoon Specified Packages
 Date & Time 4/25/19 @ 1:00 PM – 4:00 PM

Scope Review Meeting Timeframe 4/26/16 – 5/8/19

Anticipated Construction Start
 6/17/19

Anticipated Substantial Completion 7/31/20

Anticipated Closeout Complete
 8/20/20

#### Definitions

Project Documents include Drawings, Specifications, Bid Manual and All Addendums

#### Bidder Representations

- Bidder has reviewed all Project Documents
  - All Drawings
  - All Specifications
  - Entire Bid Manual
  - All Addendums
- Bidder has visited/is familiar with project site
- Bidder has reviewed all geotechnical information
- By submitting Bid, bidder agrees project documents are biddable and buildable for stated price

#### Interpretation or Corrections

- Advise CM of any discrepancy, omission, error or inconsistency no later than 10-days prior to Bid Day
- All Bidder questions to be in writing
- All questions received will be responded to via addendum and shared with all Bidders
- CM is relying on Bidders ability to provide complete & comprehensive bid

#### Substitutions

- Must be received 15-days prior to Bid Day
- Must complete CM "Substitution Request Form"
- Bidder responsible for any/all domino impacts of approved substitution

### Preparation & Submission of Bid

- All Bid Submission Questions to: Barnhill Contracting Company
  - Brad Martin, Project Executive PRIMARY CONTACT
    - bmartin@barnhillcontracting.com
    - (919)795-6919 (Cell)
  - Matt Cave, Project Superintendent
    - mcave@barnhillcontracting.com
    - (252)885-2448 (Cell)

- No modifications of any kind to Bid Form permitted
- Bid Form signed by Company Officer
- Bid Price to include anything and everything required to complete work
- Bid Price to include anything and everything required to comply with project documents
- Provide unit prices as requested
- Acknowledge receipt of addendums issued
- No exclusions, qualifications and/or clarifications on/with Bid Form is permitted
- Fill out all blanks on Proposal Form

- Bid Bonds
  - Any packages over \$300,000.00 MUST include a Bid Bond.
- Payment and Performance Bonds
  - All packages MUST include a P&P Bond Cost (Over \$100K Only)
  - Bid forms will include an alternate section to be filled out for the P&P Bond Cost

- Post Bid 72-Hour Submission Items
  - Affidavit C with MWBE Firms
  - Affidavit D MWBE Good Faith effort
  - Tiered Subcontractor Listing
- Contract Award
  - CM & Owner will determine the most responsive, responsible, lowest bid Responsive – Bid Form completed correctly
    - Responsible price adequately reflects entire scope, project requirement compliance
    - Lowest Bid lowest cost to the Owner
  - CM will issue Notice of Intent to Award to all Selected Bidders
  - Selected Bidders 10-workdays to execute Subcontract
    - Review Contract prior to Bid
    - No contract modifications permitted after Bid

### MWBE Project Participation

- MWBE Project Participation Goal 10% MINIMUM
- All Bidders Review MWBE Minimum Compliance Guidelines
- MWBE Prime Bidders Required to Meet Goal via Tiered Subcontract Relationships
- Be Prepared to "Show Your Work" Good Faith Effort
  - Affidavits Required
- CM/Owner expects/requires Active MWBE Project
   Participation CM Monthly Monitoring during Project
- Opportunity to Increase Business Relationships with New Firms
- Issue CM MWBE Listing
- Encourage Certification SWUC Program
  - http://www.doa.nc.gov/hub

### Bid Day Activities

- Prequalified Prime Bidders
- 2<sup>nd</sup> & 3<sup>rd</sup> tier Bidders No Prequalification Requirement
- Required NHCS Forms to be completed: Sexual Offender Registry Check Certification
- All Bids Received Must be Sealed Envelope
- Submit Bids to: Sealed Bids hand delivered to New Hanover County Schools Large Conference Room, located 6410 Carolina Beach Road Wilmington, NC 28412 or sealed bids delivered before 5:00 PM on 4/24/19 to the Wilmington office of Barnhill Contracting Company, 272 North Front Street, Suite 420 Wilmington, NC 28401.
- Bids Opened & Read Aloud: New Hanover County Schools Large Conference Room, located at 6410 Carolina Beach Road Wilmington, NC 28412.
- Bid Day Apparent Low Bidders Subject to Scope Review Confirmation
- Bid Tabulation Will be Available w/in 48-hours of Bid Day upon Request
- Bid Day Bid Evaluations & Scope Review Confirmations Kept in Strict Confidence


### Scope Review/Confirmation Meeting

- Scope Review Meeting to Include Bidder Estimator & Proposed Field Personnel
- Bring Estimate Notes, Take-off, etc. for Review Purposes/Discuss Project Details
- Meetings Held at Barnhill's Building Division Wilmington Office Located at 272 North Front Street, Suite 420 Wilmington NC
  - Face-to-face
  - Teleconference
- CM to Notify Bidders w/in 72 hours of Bid Day to Attend Scope Reviews
- Scope Review Meeting Duration NTE 90-Minutes

### Project Logistics/Work Rules

- Work Hours: 7:00 AM to 5:30 PM M-F and Weekends as required
- Project Safety Orientations & Safety Plan
- Weekly Meeting Attendance
- Daily Field Reporting
- Daily Cleanup & Housekeeping
- Communications & Coordination
- Owner Furnished Items: Misc. Toilet Accessories
- Site Security: No Night Watchman or Security Provided by Owner/CM
- Protection of In-Place Work

# Trask Middle School Logistics Plan



### Schedule

### Tentative Milestone Dates:

NTP/Intent to Award	06/05/19
NTP for Construction	06/17/19
First Day of School (19-20)	08/27/19
Last Day of School (19-20)	06/11/20
Substantial Completion	07/31/20
Final Completion (Including Closeout)	08/20/20

### Schedule

- Bid Default Schedule
- Depicts CM's 1-sided View of Project Sequences & Durations
  - All Subcontracts Tied to Bid Default Schedule
  - Used to Manage Construction Until Construction Schedule Approved
  - Schedule is Based on Standard Hours/Day, 5 Day/Week.
- Construction Schedule
  - CM Facilitate Schedule Sessions
  - Subcontractor Field Supervision Participation Mandatory
  - Cultivate Subcontractor Specific work Scope Details Input
  - Combine All Detail Received into Logical CPM Schedule
  - Create "Approved" Construction Schedule Which All Will Support

### Schedule

- Schedule Updating & Compliance Management
  - Construction Schedule Reviewed & Updated Weekly
  - Review & Coordinated at Weekly Project Meeting
  - Responsible Party Held Accountable to Schedule Delay & Domino Impacts
  - CM to Direct Overtime Work As Necessary to Meet Schedule
  - Project Will Be On Schedule Every Monday Morning
- Schedule Sequence
  - School → Site → Building Activity Detail
- CM to Utilize Primavera (P7) Scheduling Software

### Project Administrative Requirements

- Weekly Coordination Meetings are Mandatory Time to be established by CM
- Daily Field Reports are Mandatory Turn in by 12:00 pm the following day
- Attend OAC Meetings as requested
- Weekly Safety Meeting documentation will be required from each subcontractor
- Safety Orientation will be conducted prior to any contractor starting work on site
- ID Stickers provided by Barnhill Contracting Company as Required.
- All administrative paperwork is required to have 10 workday turnaround

### Construction Engineering Requirements

- All submittals to be sent to the Construction Manager no later than 30 days from issuance of contract. Submittal to be turned around in 20 days. Critical Submittals should be noted as critical for quicker turnaround. All Domino Effects due to delayed Key Submittals will be the responsibility of the Subcontractor.
- Each Contractor is required to conduct a thorough review of submittals for accuracy and completeness prior to submittal to the Construction Manager
- Submittals not submitted in the correct format or incomplete will be returned without review and resubmittal required

### Construction Engineering Requirements

- Open Issues will be resolved by Construction Manager within 30 days.
- Closeout documents should be submitted as early in the project as possible for each respective scope of work.
- Warranties will be submitted separate from other closeout documents and will start upon date of substantial completion. Construction Manager to confirm date of Substantial completion prior to issuance of any warranties.

### **Quality Control**

- CM Responsible for QC Management NO Negotiation of In-Place Quality
- Subcontractors Responsible for In-Place QC
- All Mock-Up Requirements Separate from In-Place Work
  - Project Will Require Mock up Panels for review per the specifications.
- Be Prepared for:
  - Pre-installation Meetings for ALL Work
  - Benchmark Field Checks & Evaluations
  - Quality Non-Conformance Notices
  - Repairs & Re-Work No Avenue for Additional Compensation

# **Quality Control**

- Provide Protection of Completed Work
- Respect Complete Work of Others
- CM Will Manage QC Non-Conformance Issues Log / Review at Weekly Project Meeting
  - Issues Log emailed to Subcontractors on daily basis
  - Immediate Follow-up & Corrections Required by Responsible Party
  - Direct involvement by Subcontractors

# First Summer Specific Items

- Phased Abatement & Demo
- Temporary and Permanent Flooring




- BP001 General Guidelines (ALL BIDDERS TO REVIEW)
- Mobile units are submitted as a separate permit with the County includes work by the following:
  - BP100, BP105, BP250, BP290, BP800, BP925, BP960, BP980, BP990, BP1005, BP1540, BP1600
- BP100 General Trades Includes forklift, daily cleanup, locker relocation, misc items
- BP105 Final Cleaning Multiple mobilizations, all required project final cleaning (interior/exterior), removal of floor protection.
- BP220 Demolition & Abatement All required selective demolition and abatement; work will be phased.
- BP250 Turnkey Sitework & Utilities All grading, utilities, concrete paving & sidewalks, asphalt.
- BP290 Landscaping All plantings and seeding as indicated, including pavers in Courtyard.

- BP390 Turnkey Concrete Rebar caps & footing chairs, concrete materials, flatwork, reinforcing steel, footings, all demo of existing concrete included.
- BP400 Turnkey Masonry Interior CMU walls with light exterior brickwork.
- BP500 Turnkey Steel Structural and Misc Steel.
- BP620 Millwork New Casework and Countertops, Reception Desk.
- BP740 Roofing Complete roofing overlayment.
- BP742 Metal Wall Panels All metal wall panels.
- BP790 Caulking & Waterproofing Brick sealer, closed cell sprayfoam, caulking of any item requiring backer rod.
- BP800 Turnkey Doors/Frames/Hardware Rated Door replacement, HM doors/frames, hardware, building software integration, phased installation.
- BP840 Storefronts/Glass/Glazing Replacement Windows & Aluminum Doors, all demo and caulking related to this scope of work.


- BP925 Metal Studs/Drywall/Insulation All new GWB assemblies and wood blocking in metal partitions, one superintendent for duration of project, fire stopping.
- BP930 Ceramic Tile All new tile installation, demo of existing, Crack isolation membrane, floor patching & prep, protect finished work, Terrazzo Scope.
- **BP960 Resilient/Carpet/Base** Substrate prep, floor patching/buffing, testing of sub floor, flooring, entrance mat.
- BP 980 Acoustical Ceiling Systems Lay-in ceiling systems, acoustical wall panels, complete replacement of existing lay-in ceiling.
- BP990 Painting Paint related caulking, any special coatings, complete re-painting of existing building, exterior required painting.
- BP1005 Specialties, Accessories, Div. 10 Wire guards, mirrors, toilet partitions, accessories, appliances, etc.
- BP1010 Identifying Devices All interior/exterior building signage/lettering
- BP1240 Telescoping Bleachers Bleacher replacement and Wall Pads.

- BP1540 Plumbing Gas piping, limited BIM Coordination, housekeeping pads, Hook up Trailers, Toilet Room Renovations.
- BP1550 HVAC Systems Unit Replacement, HVAC Controls, Test and Balance, limited BIM Coordination, place HVAC systems into service asap.
- BP1600 Electrical Temporary power & lighting, place Electrical systems into service asap, motor starters & disconnects, limited BIM Coordination, Switchgear Replacement, complete lighting replacement, Hook up Trailers.



## Preferred Brand Alternates

- No. G-1 Preferred Hardware:
  - Hinges (Ives), Cylinders (Yale), Mortise Locks (Yale), Closers (LCN), Exit Devices (Von Duprin), Key Keeper (Knox Valut), Electronic locksets (Schlage)
- No. M-1 Preferred DDC Controls:
  - DDC system by Johnson Controls, Inc;
- No. E-1 Preferred Intercom System:
  - Intercom System by Aiphone Corporation.



## Comments and Questions From PREBID CONFERENCE

Questions from the pre bid meeting:

- 1. Is the SwitchGear Replacement targeted for the 1st summer?
  - ANS: No. With limited procurement time switchgear replacement will happen 2nd summer or an extended break during school year. Similar thing was done on the Laney HS reno, so we have a baseline plan to assist the Electrician with.
- 2. Are Sexual Offender Registry Checks required for everybody onsite?
  - ANS: Yes, form can be found in Section 7 of the Bid Manual. Would need to be provided prior to starting construction.



Trask Middle School Renovations

New Hanover County Schools Wilmington, North Carolina

Pre-Bid Meeting - April 10, 2019 - 4:00pm

COMPANY	PHONE #	EMAIL
T.A. WOODS	452-7900	AYOUNG TAWOODS, COM
Eastern Environmental	910-329-1/29	DB92461@AOL. COM
Curtis Construction	252-523-1078	estinating Pourtisce. com
DIVISION 9+NC	910-392-6882	CPALMEZ @ DIVGING, COM
Division 9 Inc	910-990-9017	Thungan @ Div 9 Inc, con
NHCS FRAC	910.228.0315	Kimbuly, gordon 8 nhcs. net
5293	910.762.0852	dag @ 5293.com
1		
	Eastern Environmental Contis Construction DIVISION 9 + NC	T.D. WOODS  Enstern Environmental 910-329-1129  Cartis Construction 252-523-1078  DIVISION 9 INC 910-392-6582  DIVISION 9 INC 910-990-9017  NHCS FRIC 910.762.0857



Trask Middle School Renovations New Hanover County Schools Wilmington, North Carolina

Pre-Bid Meeting - April 10, 2019 - 4:00pm

SI	0	MI	B.I	C	ш	Е	С,	۳

SIGN-IN SHEET		9/7	575 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
NAME	COMPANY	PHONE #	EMAIL
44 Duane Pearse Take Bownen	muter construction	919-375-1135	(80 Fing Bids @Muster construction com
45 DONNIE Antry	Humphrey MECharical	910-650-6781	dautry @humphreymechanical.com
46 Andy Luce	Hamlin Roofing	919 772 8780	aluce chamlincos. com
47 Brian Smith	LJ Electrical	asa sao 759 a	brian, Smith @ 1 janstructionine con
48 TOM ElliOIT	NORTH STATE STEEL	910.262-6823	TGII; OTTO WONTHSTAT & STEEL . COM
49 Landon Williams	NEO Corporation	919-482-6973	Williams aneocorporation. com
50 DARIO PAWGO	DRIESim Phap	910-362-48	8 and emplumbing pakin & gmail. com
51 Jereny Tuckel	PWI	910-524-2777	Tucker opraision walls. com
52 George Stokes	ENV. HOLDINGS PO	201-481-1479	9 Stokes & shall com
53 Agron Lawrence	BFPE	910) 431-1038	9 Stokes & Shall com Alawrence BEFFE.com
54 Tim Barnes	Nationwide Electrical Se	rices 919-736-265	5 tim@nationwide-electric.com
55 JACOB SMITH	Elfino DEMOLITION	(843)839-1380	JUSMITH @ BHINO DEMOLITION-COL
56			
57	and the state of t		The state of the s
58			(A) 新华。 (图4) 15
59			
60			1651
61			
62	The second second	-12	
63			



Trask Middle School Renovations

New Hanover County Schools Wilmington, North Carolina

Pre-Bid Meeting - April 10, 2019 - 4:00pm

SCOON Walky SANTIAGO FRANCO BRAD MARTIN	Atlanta Flooring MANNING MASONA	919 - 417 - 3049 252 - 814 - 4918	jubley @atlantaflowing design com Santiago. manning mason y@gmail bmartine barnhill contracting can
MATT CAVE	BCC	719-175-6917	pmartin & barnhill contracting . can
RYBEN AUVERT	BCC	919-2114-1740	mave e
RYDERY MAREE	pcc .	111-397-6380	raugert e
	the second second		
	7		8
			2
	\$ \$		2-
			15 2 2
	1 1 2 2 1 2 1 2 1 2 1 2 1 2 1 2 1 2 1 2		187
1000		1 14	
		- 5	E 7
	7		5
			- 1
	3 3.61	The state of the s	

Page 5 of 5

#### First String Space Modular Buildings (Purchased thru Mobile Modular) – August 2018.

4-Classroom FSSI 6332 A-E (Myrtle Grove to Murray 2019)

6-Classroom FSSI 6333 A-G (Myrtle Grove to Trask 2019)

8-Classroom FSSI 6334 A-I (Roland-Grise)

#### **Finish Schedule**

Floor covering – Armstrong VCT – Fortress white 51839

Cove base - NAFCO, Tarkett, Brown CB-37-2, 4" vinyl base, .080"

Walls – Impact resistant gyp board – Continental Building Products.

FRP – Kalwall Corp. – Almond

Interior paint – Sherwin Williams – Summer White SW7557

Ceiling – Armstrong, School zone fine fissured square lay in, White, #1713, 2 x2 x ¾.

Prelude XL, 15/16" exposed tee grid. 7300, XL7348, XL7328 and 7800

Toilet partitions – Accurate, Phenolic color thru, floor anchored, overhead braced, Hazelnut 4450C

Roof – Firestone – UltraPly TPO membrane

Exterior siding/trim – Timberlake vinyl siding by Kaycan Ltd., Pebblestone on walls, trim is Flagstone.



#### Trask Middle School Renovations - Bidding RFI LOG

CLOSED OPEN

		I					
RFI#	Requested By:	Title	Description	Date to Architect/ Engineer	Date Returned by Architect	Date Sent to Bidders	<u>Status/Response</u>
001	BCC	Locker Room Gas Lines	Will the gas piping be installed within the locker room regardless if alternate G-2 is taken or not?	4/3/2019	4/3/2019	Addendum #1	Yes, gas piping shall be installed as indicated on the plans, regardless of which alternates are taken. If a roof top unit is not installed due to an alternate not being taken, gas piping shall be valued can capped above roof for future installation.
002	всс	Signage	1. Specification 10 1400 SIGNAGE details "Emergency Evacuation Maps" in the 1.1 C. summary section. This is not found elsewhere in the spec section or in the drawings. Please clarify if any EVAC maps / map holders are required as a part of the BP1010 Scope. If so, please provide a quantity, specifications, and drawings (including size and construction) of the holder and clarification on who is responsible for the content, design, and/or 2. Specification of the holder and clarification on who is responsible for the content, design, and/or 2. Specification of the SIGNAGE detail "interior Directional sign" as part of the BP1010 Signa" as part of the BP1010 Signa size involved as part of the BP1010 Signa. Signage is required as part of the BP1010 Signage is required as part of the BP1010 Signage is required as part of the BP1010 Signage is required as grant of the BP1010 Signage is required as displayed in the Signage is required signage in the Signage is required as signage is the Signage is required as signage is the Signage is signage in signage	4/3/2019	4/3/2019	Addendum#1	Section 11 11400, Part 1 General, 1.1 Section Includes Delete item B. Interior directional and informational signs. Delete item C. Enregency evacuation signs. Add Item E. Maximum occupancy signs, (3 pair, 6 fotal) Section 11 11400, Part 2 Signage Applications, B. Room and Door Signs, 4. Sign Height a. Signs with room numbers only: 2 inches. Shall be used for Mechanical Rooms (M1), Electrical Rooms (E1), Data/ Communication Rooms (11) b. Signs with room names or other additional information: 6 inches. Shall be used for all classroom spaces. Section 11 1400, Part 2 Signage Applications, B. Room and Door Signs, 5. Office Doors Shall be used for all classroom spaces. Section 11 1400, Part 2 Signage Applications, B. Room and Door Signs, 5. Office Doors Shall be the same as the 6 inch sign except onth room name and provide window Signage is to including the Athletic Support Spaces as part of the base bid.
003	BCC	Painting	Will the locker room be painted regardless if the Alternate G-2 is taken?	4/3/2019	4/3/2019	Addendum #1	No, if the alternate is not taken then no painting is required in the locker rooms.
004	BCC	Need for Impact Glazing	In the Aluminum Window and Doors specification there is no mention of this job requiring any impact glazing. Can you confirm this is correct please.	4/4/2019	4/4/2019	Addendum #1	Impact glazing is not specified because it is not required.
005	BCC	Exterior Brick Sealant	Please advise if the existing caulk sealants are to be cutout and replaced prior to the exterior brick cleaning and sealant. The brick sealants are for masonry only.	4/4/2019	4/8/2019	Addendum #1	Existing brick sealant joints are to be cut out and replaced. This scope consist of roughly 23 locations in the low wall conditions (+/- 10' long each) and 3 locations in the high wall gym condition (+/- 22' long each).
006	BCC	New Meter Size	Based on 4.9. 19 email from Cheatham it is suspected that we will need to install a new 3" meter at trask to supply the fatures. Please advise the following: Will there need to ne a new service top installed back to the CFPUA main? Will a new C 5.0 sheet be issued to show replacement of existing meter.	4/10/2019			The state control and a second set as a region that spirit constant (1). As seen control
007	BCC	Fiber Requirements	On print E7.3 Detail A there is a note to re-route the fiber optic cable. Please can you provide the following information?     a. Quantity of fiber strands     b. Is the fiber optic cable single mode or multimode (OM1, OM3 or OM3)?	4/10/2019	4/12/2019	Addendum #1	From the records we have, we believe this to be 12 strand single mode fiber. See photo below.
008	всс	Division 10 questions	1. Inpro's Endurant Toilet Partitions are Solid Surface material. Please Advise if the Intention is for Solid Surface or Solid Please (eIDPE) Total Partitions—per spec section 102113.  Solid Please (eIDPE) Total Partitions—per spec section 102113.  Spec Section 10110 Total Please Advise correct Sartlard Najabin basis of design, as a Grab Bar product number Please advise correct Sartlard Najabin sels-of-design.  Spec Section 101101 Dy Erase Walls in Media Center are not clear, is the intention to have (3) Dry crease panels 45 vide to cover 120° length in Group Sulfy Dy Erase walls will be 80° high. Confirm please.  4. Additional Tackboard noted in Media Center. Please advise size.	4/10/2019	4/11/2019	Addendum #1	1. Totel partitions are to be HDPE tested in accordance with NFPA 286. It ingre does not make this type of partition system, then they should be removed from the specification as we would still be left with 3 approved manufacturers. 2. Please modify Specification Section 10 2800, 2.4 Commercial Totel Accessories, E. 1. Product: 8254 Series by Botrick. 3. Yos, the intention in the Media Center Group Study, Area is to use (3) 48 by 96 any erase ponels butted joints with a frame around the perimeter of the the 3. This may require cutting 1 panel to properly if on the walt. Enter result should appear as a continuous 128% section of writable wall surface. 4. Please revise Specification Section 10 1101, Part 3 Execution, 3.4 Schedule, B. Media Center to include: 3, 2004 - Media Center: One 48 x 48 tockboard.
009	BCC						
010 011	BCC BCC						
012	BCC						
013 014	BCC BCC						
	DUU		I .				The state of the s

BARNHILL CONTRACTING COMPANY	REQUEST	FOR INFORMATION	RFI Number
Project: Trask Middle School Ren	No: <u>1102018</u>	From: Barnhill	
Location: Locker room renovat	tion	Contract For:	
Request Date: 4.3.19		Subcontract For: N/A	
Response Needed By:		To: Doug Sherwood	
Subject: Locker Room gas line	es	Attn:	
Project Implications: Cost  Reference: Drawing Number:		Specification	n:
Information Needed:  Will the gas piping be in not.	nstalled within the loo	cker room regardless If alternate G-2	is taken or
1/2°   1/	LAUNDRY BOOK BOOK BOOK BOOK BOOK BOOK BOOK BOO		
Submitted by: Matt Cave		Date: <u>4.3.19</u>	
Response: Proceed with	th recommendation	X Proceed with the following ins	structions:
	it is not installed d	l on the plans, regardless of which ue to an alternate not being taken, f for future installation.	

Casey Gilman, PE LEED AP

Date: 4/3/19

COMPANY	REQUEST F	OR INFORMATION	RFI Number RFI #0002
Project: Trask Middle School Ren	n No: <u>1102018</u>	From: <u>Barnhill</u>	
Location: Entire school		Contract For:	
Request Date: 4.3.19	;	Subcontract For: N/A	
Response Needed By:	-	To: Doug Sherwood	
Subject: Signage		Attn:	
Information Needed:  1. Specification 10 1400 SIGN. found elsewhere in the spect as part of the BP1010 Scope. construction) of the holder as printing/installation of any reconstruction. No sizes, drawings, Interior Directional and Informatical American Informatical Informa	section or in the drawings. P. If so, please provide a quand clarification on who is resequired inserts.  AGE details "Interior Direct construction, or quantity are mational Signage is requireding size and construction) of AGE details "Room and Doserts, Conference and Meeting rawing 6/A6.0 only details arify which signs types are to	vacuation Maps" in the 1.1 C. summary see Please clarify if any EVAC maps / map hol ntity, specifications, and drawings (includes sponsible for the content, design, and/or cional and Informational Signs" as part of the detailed for bidding purposes. Please clared as part of the BP1010 Scope. If so, plea	ction. This is no liders are required ing size and the 2.2 C. rify if any use provide a des signs for om Signage in and a Service red signs for
of the Alternate.			
Contractor Recommendation:	:	Date: 4.3.19	
Contractor Recommendation:  Submitted by:Matt Cave	th recommendation	Date: <u>4.3.19</u>	
Contractor Recommendation:  Submitted by: Matt Cave  Response: Proceed wire  Section 11 11400, Part 1 General Delete item B. Interior of Delete item C. Emerge	th recommendation  al, 1.1 Section Includes directional and informat	Proceed with the following ins	

Shall be used for all classroom spaces.

cc: BCC Project w/File

Section 11 1400, Part 2 Signage Applications, B. Room and Door Signs, 5. Office Doors

Shall be the same as the 6 inch sign except omit room name and provide window

Signage is to including the Athletic Support Spaces as part of the base bid. Date: 4/3/19 Doug Sherwood, AIA Architect/Engineer's Signature

Response Needed By: To: To: Doug Sh	erwood  only Specification	
Request Date: 4.3.19  Response Needed By:	erwood  only Specification	
Response Needed By: To: To: Doug Sh Subject: Attn:	erwood  only Specification	
Subject: Painting Attn: Attn: Project Implications: Cost   Time  Information C	only Specification	
Project Implications: Cost ☐ Time ☐ Information C	nly Specification	
	Specification	n·
Reference: Drawing Number: Detail Number: NA		n·
Information Needed:  1. Will the locker room be painted regardless if the alternate G-2 is taken?  Contractor Recommendation:  Submitted by: Matt Cave	Date: 4.2.10	
Response: Proceed with recommendation Proceed v	Date: 4.3.19	
No, if the alternate is not taken then no paid the locker rooms.  Doug Sherwood, AIA architect/Engineer's Signature	nting is requi	

BARNHILL CONTRACTING	DECLIEST	EOD INFORMATION	RFI Number: RFI #0004
COMPANY	REQUEST	FOR INFORMATION	KFI #0004
Project: Trask Middle School Rei	n No: 1102018	From: <u>Barnhill</u>	
Location: Building		Contract For:	
Request Date: 4.4.19		Subcontract For: N/A	
Response Needed By:		To: Doug Sherwood	
Subject: Need for impact glaz	ing	Attn:	
Can you confirm this is corr	Detail N and doors specifications th ect please.	Specification	
Contractor Recommendation	:		
Submitted by: Matt Cave		Date: <u>4.4.19</u>	
Response: Proceed w	ith recommendation	Proceed with the following in	nstructions:
Impact glazing is not specified	d because it is not req		
	Doug Sherwood	, AIA Date: 4	/5/19

Architect/Engineer's Signature

cc: BCC Project w/File

BARNHILL CONTRACTING COMPANY	REQUEST	FOR INFORM	IATION	RFI Number: RFI #0005
Project: Trask Middle School Ren	No: <u>1102018</u>	From: <u>Barnhill</u>		
Location: Building		Contract For:		
Request Date: 4.4.19		Subcontract For: N	I/A	
Response Needed By:		To: Doug Sherwo	ood	
Subject: Exterior brick sealant		Attn:		
Project Implications: Cost  Reference: Drawing Number: Information Needed:  1. Please advise if the existing and sealant. The brick sealant		lumber: NA	Specification Volume/Sectior prior to the exterio	
Contractor Recommendation:  Submitted by: Matt Cave	:	Da	te: <u>4.4.19</u>	
Response: Proceed wi	th recommendation	☐ Proceed with t	he following ins	tructions:
Existing brick sealant joints a in the low wall conditions (+, (+, 22' long each).			_	
	Doug Sherwood			

Architect/Engineer's Signature

cc: BCC Project w/File

BARNHILL CONTRACTING COMPANY	REQUEST	FOR INFORMATION	RFI Number: RFI #0007			
Project: Trask Middle School Ren	No: <u>1102018</u>	From: <u>Barnhill</u>				
Location: Building electrical		Contract For:				
Request Date: 4.10.19		Subcontract For: N/A				
6Response Needed By:		To: Doug Sherwood				
Subject: Fiber Requirements		Attn:				
following information?  a. Quantity of fiber  b. Is the fiber optic	Detail Nere is a note to re-route strands cable single mode or n	Specification				
Contractor Recommendation	:					
Submitted by: Matt Cave		Date: <u>4.10.19</u>				
Response: Proceed wi	th recommendation	Proceed with the following ins	structions:			
CHEATHAM RESPONSE:  From the records we have we	e believe this to be 12	strand single mode fiber. See photo	n helow			

elow.

April 11, 2019 Mark A. Ciarrocca



cc: BCC Project w/File

Architect/Engineer's Signature

BARNHILL CONTRACTING COMPANY	REQUEST	FOR INFORMATION	RFI Number: RFI #0008
Project: Trask Middle School Ren	No: <u>1102018</u>	From: Barnhill	
Location: Building accessories	<u>.</u>	Contract For:	
Request Date: 4.10.19	_	Subcontract For: N/A	
6Response Needed By:		To: Doug Sherwood	
Subject: Division 10 questions		Attn:	
Project Implications: Cost  Reference: Drawing Number:		Information Only Specification Number: NA Volume/Section	ո։
Surface or Solid Plastic (F 2. Toilet Accessory Spec Sec product number. Please ac 3. Spec Section 101101 Dry	HDPE) Toilet Partitions ction 102800 call for S dvise correct Sanitary N Erase Walls in Media over 12'0" length in G	Center are not clear. Is the intention to h roup Study? Dry Erase walls will be 8'0'	as a Grab Bar ave (3) Dry
Contractor Recommendation:			
Submitted by: Matt Cave		Date: <u>4.10.19</u>	
Response: Proceed with	th recommendation	X Proceed with the following ins	structions:
<ul> <li>type of partition system, the left with 3 approved manu</li> <li>Please modify Specification Series by Bobrick.</li> <li>Yes, the intention in the Me butted joints with a frame of the system.</li> </ul>	en they should be rei facturers. n Section 10 2800, 2.4 dia Center Group Stu around the perimetel	dance with NFPA 286. If Inpro does not moved from the specification as we want of the Accessories, E, 1.  Udy Area is to use (3) 48 by 96 dry erast of the the 3. This may require cutting areas a continuous 12'x8' section of writing the Accessories of the the 3.	would still be Product: B254 se panels g 1 panel to

Doug Sherwood, AIA

Architect/Engineer's Signature

cc: BCC Project w/File

Date: 4/11/19

# Trask Middle School Demo Delineation Plan Addendum #1



#### SUBSTITUTION REQUEST (During the Bidding/Negotiating Stage) Substitution Request Trask Middle School (Renovations) (16-718974) SubReq-03161 Project: Number: WILMINGTON, NC Courtney Damore, Scranton Products From: Debrielle Boone, Barnhill Contracting 04/03/2019 To: Date: dboone@barnhillcontracting.com, (919) 781-7210 A/E Project Number: Plastic Toilet Compartments Contract For: New Hanover County Board of Education Re: Plastic Toilet Compartments Manufacturers Specification Title: Description: Section: 10 2113.19 Page: 1 Article/Paragraph: 2.1 Hiny Hiders Solid Plastic Proposed Substitution: Scranton Products Address: scrantonproducts.com 570-348-0997 Manufacturer: Phone: Scranton Hiny Hiders Solid Plastic Trade Name: Model No.: N/A Attached data includes product description, specifications, drawings, photographs, and performance and test data adequate for evaluation of the request; applicable portions of the data are clearly identified. Attached data also includes a description of changes to the Contract Documents that the proposed substitution will require for its proper installation. The Undersigned certifies: · Proposed substitution has been fully investigated and determined to be equal or superior in all respects to specified product. • Same warranty will be furnished for proposed substitution as for specified product. Same maintenance service and source of replacement parts, as applicable, is available. Proposed substitution will have no adverse effect on other trades and will not affect or delay progress schedule. Proposed substitution does not affect dimensions and functional clearances. Submitted by: Courtney Damore Courtney Damore Signed by: Scranton Products Firm: 801 E. Corey Street Address: Scranton, Pennsylvania 18504 Telephone: (570) 348-0997 ext. 8032, courtney.damore@azekco.com A/E's REVIEW AND ACTION Substitution approved - Make submittals in accordance with Specification Substitution Procedures. Substitution approved as noted - Make submittals in accordance with Specification Substitution Procedures. Substitution rejected - Use specified materials.

Substitution Request received too late - Use specified materials.

Product Data

Samples

Tests

Reports

Drawings

Signed by: Doug Sherwood, AIA

Supporting Data Attached:

#### **SUBSTITUTION REQUEST**

(During the Bidding/Negotiating Stage)

				(Dailing the Didding, Negetiating Grage)
Project:	Trask Middle School (Renovations) (16-718974) WILMINGTON, NC		Substitution Request  Number:	SubReq-03162  Courtney Damore, Scranton Products
			From:	
То:	Debrielle Boone, Barnhill Contracting		Date:	04/03/2019
	dboone@barnhillcontracting.com, (919) 781-7210		A/E Project Number:	
Re:	Lockers		Contract For:	New Hanover County Board of Education
Specification	on Title: Lo	ckers	Description:	Manufacturers
Section:	10 5100	Page: _1	Article/Paragraph	n: 2.1
Proposed :	Substitution:	Tufftec Bench		
Manufacturer:		Scranton Products	Address: scrantonproducts.com	Phone: 570-348-0997
Trade Name:		Scranton Tufftec Bench	/tudioss. <u>estation-productions</u>	Model No.: N/A
Attached data includes product description, specifications, draw		drawings photographs and perform		
		tions of the data are clearly iden		iance and lest data adequate for evaluation of
Attached d installation		s a description of changes to the	e Contract Documents that the propo	osed substitution will require for its proper
	rsigned certifie			
• Pro	oposed substitu oposed substitu	tion will have no adverse effect of tion does not affect dimensions a	ment parts, as applicable, is available on other trades and will not affect or cand functional clearances.	
Submitted	by: Courtney Da	amore		
Signed by:	Courtney Da	amore		
Firm:	Scranton Pr	oducts		
Address:	801 E. Core	y Street		
	Scranton, P	ennsylvania 18504		
Telephone	<u>(570)</u> 348-0	997 ext. 8032, courtney.damore	@azekco.com	
A/E' s RE\	/IEW AND ACT	ION		
☐ Substi	tution approved	- Make submittals in accordance	e with Specification Substitution Prod	cedures.
☐ Substi	tution approved	as noted - Make submittals in a	ccordance with Specification Substitu	ution Procedures.
X Substi	tution rejected -	Use specified materials.		
☐ Substi	tution Request	received too late - Use specified	materials.	
Signed by	: Doug St	nerwood, AIA		Date: 4/12/1
Supporting Attached:	j Data	□ Drawings □ Produ	ict Data	☐ Tests ☐ Reports ☐
While r	not data v	vas provided for revi	ew a quick online revie	ew revealed that these are
HDPE k	penches.	Laminated maple a	re specified. This does	not meet the specificaion.