



## Trade Partner Scope of Work

### Exhibit A

### **BP- 02A Selective Demo**

#### North Brunswick High School Addition and Renovations

---

A. The subcontractor shall perform all work and shall furnish all layout, supervision, materials, labor, scaffolding, tools, equipment, supplies, services, rigging, craning and hoisting of all materials and equipment and all other things necessary or reasonably incidental for the construction and completion of their work as portrayed in the enclosed enumerated contract documents and specification sections as referenced below:

Supplemental Instructions to Bidders dated April 17, 2020

S&ME Geotechnical Exploration Report dated August 21, 2019

#### Associated Specifications:

Division 00 Procurement and Contracting Requirement

Division 01 General Requirements

#### 02 41 19 SELECTIVE DEMOLITION

#### B. Subcontractor's work specifically includes:

1. All bidders to note project includes all plans and specifications for the Two-Story Classroom Addition, ROTC Building, Cafeteria Expansion, and Classroom 413 Renovations.
2. Multiple mobilizations will be required to facilitate work
3. Demo includes all architectural, structural, work as shown on plans and specs. For example (but not limited to): VCT Tile, Ceiling Tile, windows, doors, masonry, concrete (site concrete by others), block work for new duct work, new openings, etc.
  - a. MEP Demolition to be by the MEP bid packages, however, close coordination with MEP subcontractors will be required.
  - b. Selective Demo subcontractor and MEP trades are required to walk project prior to demo start (on each phase) to mark items to be removed and where demo should start/begin. This walk through will be recorded (itemized list) and marked on set of drawings to be agreed upon by all trades.
4. All items shown to be salvaged shall be protected and delivered to BCS Staff as directed. BCS Has first right of refusal.
5. All shoring and scaffolding provided and installed by subcontractor
6. Dumpsters will be provided by CM@R
7. Dust control to be installed and provided by subcontractor. In existing classrooms, Flooring protection to be installed by BP-02A.
8. In addition, also include twenty (20) man hours of additional work by this contractor to be utilized at the discretion of the CMAR via written request for other purposes.



9. Include Temporary shoring of adjacent walls, ceiling, & soffits where required during Brick demo.
10. See site logistics plan for additional notes regarding site demo included by others.
11. BP-02A to provide any and all required equipment and scaffold required for selective demo.
12. Tie-in to existing 2 story building will require holiday, weekend and/or night work in order to complete scope of work during school breaks – see schedule for details.
13. Tie-ins to existing 2 story building and cafeteria will require close coordination with other subcontractors, multiple mobilizations will be required for the phased demo of existing masonry and the support of the existing block/brick. Mason required to cut grout and install of Lintel and C-Channel detail. Demo subcontractor to remove existing block and brick after detail approval/inspection. Steel Lintel, channel and bolts to be provided by Steel subcontractor (BP-05A). Pay close attention to structural documents for shoring requirements and for order of operation.
14. At new ductwork openings in existing blockwork, Metal Subcontractor (BP-05A) to provide lintels, and Demo contractor to cut in and install loose lintels prior to demo of new opening size. See Structural Drawings
15. Metal Roof demo to be by roofing contractor BP-07C.

C. Subcontractor Specific Requirements:

- The following is a general outline of items specifically included, but not limited to, under this agreement:

- A. Submittals must be uploaded onto WMJ Sharepoint site for review. To gain access to Sharepoint site please contact the Construction Manager within 5 days of receiving the contract. All submittals are expected to be received no later than 20 days of receiving the contract unless discussed and approved by the Construction Manager.
- B. Delivery Requirements: As coordinated by Subcontractor with WMJ on site Superintendent. Subcontractor is responsible to coordinate delivers with vendors. The construction manager will not provide equipment to unload subcontractor materials. Please keep in mind the school will be in session during normal school hours and all deliveries must be scheduled. NO DELIVERIES WILL BE ACCEPTED BETWEEN THE HOURS OF 7:00AM AND 8:00AM and 2:00 and 3:30PM MONDAY THROUGH FRIDAY (this excludes deliveries on small company pickup trucks and/or small box trucks as approved by project superintendent). Saturday deliveries will be accepted only on the approval of the project Superintendent.
- C. Subcontractor is responsible for scheduling, coordinating, preparing and documenting all testing, inspections, and punch-list with the Owner, Architect, Engineer, Owner's Commissioning Agent, inspection agencies, and required local authority(s) having jurisdiction. All pre-testing and testing requirements needed to achieve temporary and permanent certificate of occupancy and the construction schedule is included.
- D. It is the responsibility of this Subcontractor to anticipate inspection delays in the installation durations and sequence such work ahead of others as not to impose delays in the schedule.
- E. Any and all requirements for mockups for approval of assemblies on this project are fully included.



- F. In addition to the requirements of the specifications, Subcontractor will supply Shop Drawings that include all dimensions, mounting details, and/or pad layout, weight, color, power requirements, ventilation requirements, and all special attachments and mounting details as applicable to their own scope.
  - G. This Subcontractor should provide protection for ANY new and existing installations as part of this Project. If protection provided by others is not sufficient to support/protect the work as part of this scope, this Subcontractor shall provide additional protection as may be required to fully protect that equipment or installation.
  - H. All damage to paint primers or applied factory finishes damaged during install shall be repaired by this Subcontractor.
  - I. Final cleaning of all equipment prior to Final Project Completion including removal of shipping stickers, etc. This shall apply to all existing installations as well as new installations
- D. Allowances:
- a. The Subcontractor is to include the following allowances in their base bid amount. These allowances will include all overhead and profit and will be identified on a separate line item in the payment application schedule of values. The Construction Manager is solely responsible for determining what work will be charged against these allowances and all said work must be authorized in writing by the Project Manager or Superintendent prior to commencing. Subcontractor will submit daily work slips for verification and actual costs against this allowance will be reconciled at the completion of the project. Any work performed by Subcontractor that was not previously authorized by the CM will not be reimbursed.
- E. Unit Prices
- a. Unit prices quoted and accepted shall apply throughout the duration of the contract and are inclusive of all overhead costs, insurance, bonding and profit. If necessary, Subcontractor agrees to provide labor and/or materials and/or equipment to perform the following work on a unit price basis for the unit prices stated below. Should additional Unit Prices be necessary, these will be agreed upon and included here after the completion of the post-bid scope review meeting
- F. Alternates:
- a. The subcontractor is directed to reference the big form for applicable project alternate prices to be included with the Subcontractor's Bid. Alternate Prices shall include all cost associated with the changes, omissions, additions or other adjustments to the work of the Bid Package as described in the alternate, or are reasonably inferable therefrom. Alternate Prices shall include all cost of overhead, profit, and bond premiums associated with the work of the Alternate whether additive or deductive. Claims for extras resulting from changes caused by the acceptance or rejection of any alternate will not be allowed. The Drawings, Specifications, Project Manual, Addendum(s), and other Contract Documents shall be considered appropriately modified by either the acceptance or rejection of the various Alternatives. The Construction Manager and Owner expressly reserve the right to accept or reject any, or all, Alternate Prices and in any sequence. Acceptance or rejection of



any alternate does not relieve the Bidder of timely completion of the Work within the time periods indicated.