

**ADDENDUM I**

Date of Addendum: December 22, 2020

Project Name: New Hanover County Government Center

**PROJECT INFORMATION**

- A. Owner: New Hanover County
- B. Developer: Cape Fear FD Stonewater
- C. Architect: LS3P.
- D. Architect Project Number: 7702-190810

**NOTICE TO BIDDERS**

- A. This Addendum serves to clarify, revise, and supersede information in the Project Manual, Drawings, and previously issued Addenda. Portions of the Addendum affecting the Contract Documents will be incorporated into the Contract by enumeration of the Addendum in the Owner/Contractor Agreement.
- B. The Bidder shall acknowledge receipt of this Addendum in the appropriate space on the Bid Form.
- C. Attachments within this Addendum include, but may not be limited to, modifications as noted.

**ATTACHMENTS**

- A. This Addendum includes the following attached Sheets:
  - 1. General:
    - a. Sheet G-001, reissued.
    - b. Sheet G-002, new
  - 2. Architectural:
    - a. Sheets A-101, A-101A, A-101B, A-101C, A-102A, A-102B, A-102C, A-103, A-103A, A-103B, A-104A, A-104B, A-121A, A-121B, A-121C, A-122A, A-122B, A-122C, A-123A, A-123B, A-124A, A-124B, A-201, A-202, A-301, A-355, A-405, A-514, A-551, A-601, A-611, A-612, A-700, A-801, A-802, A-803, and A-804, reissued.
    - b. Sheet A-701, new
  - 3. Plumbing:
    - a. Sheets P-101A, P-101B, P-101C, P-102B, P-102C, P-103B, P-104A, P-104B, P-201C, P-202C, P-203A, P-204A, P-301, P-302 and P-303, reissued.
  - 4. Mechanical:
    - a. Sheets M-101A, M-101B, M-101C, M-102A, M-102B, M-102C, M-103A, M-103B, M-104A, M-104B, M-301, M-402, M-502, M-503, M-504, M-602, M-603, M-701, M-702, reissued.
  - 5. Fire Protection:
    - a. Sheets FP-001, FP-002, FP-101C, FP-102B, FP-103B and FP-104B, reissued.

6. Electrical:
  - a. Sheets E-001, E-002, E-100, E-101A, E-101B, E-101C, E-102B, E-102C, E-103B, E-104A, E-104B, E-111, E-112, E-113, E-114, E-201A, E-201B, E-201C, E-202A, E-202B, E-202C, E-203A, E-203B, E-204A, E-204B, E-205, E-301, E-302, E-501, E-502, E-503, E-504, E-505, E-506, E-507, E-508, E-509, E-510, E-511, E-512, E-604 and E-607, reissued.
7. Fire Alarm:
  - a. Sheets FA-102B, FA-102C, FA-103A and FA-105, reissued.
8. Telecom:
  - a. Sheets T-001, T-100, T-101C, T-102B, T-102C, T-103B, T-104B, T-401, T-402, T-403 and T-501, reissued.
9. Security:
  - a. Sheets SC-001, SC-101C, SC-102A, SC-102C, SC-103A, SC-103B and SC-104A, reissued.
10. Audio Visual:
  - a. Sheets AV-000, AV-101A, AV-101B, AV-101C, AV-102B, AV-102C, AV-103B and AV-121, reissued.

## **REVISIONS TO DIVISION 01 - GENERAL REQUIREMENTS**

### Item I-1. Tenant Improvements, Section 011000, Article 1.5:

1. Revise article header to read "Owner-Furnished Products".
2. Add Paragraph C as follows:
  - B. Owner-Furnished/Contractor-Installed (OFCI) Products:
    1. Toilet seat cover dispensers.

## **REVISIONS TO DIVISIONS 02 - 49 SPECIFICATION SECTIONS**

### Item I-2. Tenant Improvements, Section 093013:

1. Article 2.3 A.1: Revise to read as follows:
  1. Basis of Design: Subject to compliance with requirements, provide basis of design indicated or comparable products by one of the following:
    - a. Del Conca USA; Tudor Stone, Item No. 70TUDGRA2M (Basis of Design)
    - b. Ceramiche - Piemme, Purestone, Color - Girgio
    - c. Crossville; Sands by Edimax
2. Article 2.3 B.1: Revise to read as follows:
  1. Basis of Design: Subject to compliance with requirements, provide basis of design indicated or comparable products by one of the following:
    - a. Del Conca USA; Tudor Stone, Item No. 70TUDGRA1224 (Basis of Design)
    - b. Ceramiche - Piemme, Purestone, Color - Girgio
    - c. Crossville; Sands by Edimax
3. Article 2.3 C.1: Revise to read as follows:
  1. Basis of Design: Subject to compliance with requirements, provide basis of design indicated or comparable products by one of the following:

- a. Atlas Concorde; Marine, Item No. 15SHOMAR1224 and 15SHOMAR2448 (Basis of Design)
- b. Florida Tile; Sequence, Color - Drift
- c. Best Tile

**Item I-3.** Tenant Improvements, Section 093023, Article 2.3 A.1: Revise to read as follows:

1. Basis of Design: Subject to compliance with requirements, provide basis of design indicated or comparable products by one of the following:
  - a. Best Tile; Shimmer (Basis of Design)
  - b. Somer Tile
  - c. Tilebar

**Item I-4.** Tenant Improvements, Section 222500, Article 1.1 C: Add Item 1 as follows:

1. All horizontal primary and secondary piping to be insulated.

**Item I-5.** Tenant Improvements, Section 224400, Article 3.4 B: Revise as follows to add ball valves.

- B. Globe or Ball Valves:
  1. Provide globe or ball valves in each water supply connection to sinks, water coolers, and any fixture provided by others, except where globe type stop valves are furnished with fixtures.

**Item I-6.** Tenant Improvements, Section 237000: Revise as follows:

1. Article 1.3 C: Revise first sentence to read "The first 20' of rectangular supply and return ductwork outside the HVAC room and of supply air duct within the risers from the rooftop units shall be constructed of 16 gauge..."
2. Article 3.4 A: Revise to read "Line 10' downstream of terminal boxes ductwork, at all locations, with duct fibrous lining."
3. Article 3.4 B: Add "If the box has an electric heating coil, install lined ductwork 10' downstream after 30" from electrical heating coil."

## **REVISIONS TO DRAWING SHEETS**

**Item I-7.** Sheet G-001: Replace with revised sheet, included.

1. Deleted Appendix B - Moved to Sheet G-002.
2. Added civil and structural drawing list.

**Item I-8.** Add Sheet G-002, included. Moved Appendix B to new sheet.

**Item I-9.** Sheet A-101: Replace with revised sheet, included. Added gate dimension notes.

**Item I-10.** Sheets A-101A, A-101B, A-101C, A-102A, A-102B, A-102C, A-103A, A-103B, A-104B: Replace with revised sheet, included. Added fire extinguisher cabinets.

**Item I-11.** Sheet A-103: Replace with revised sheet, included. Changed window types: SF18 on 3<sup>rd</sup> Level and SF19 on 4<sup>th</sup> Level.

**Item I-12.** Sheet A-104A: Replace with revised sheet, included.

1. Added new wall furring at SF19.
2. Added fire extinguisher cabinets.

Item I-13. Sheets A-121A, A-121B, A-121C, A-122A, A-122B, A-122C, A-123A, A-123B, A-124A, A-124B: Replace with revised sheets, included. Added Detail Section Cuts.

Item I-14. Sheet A-201: Replace with revised sheet, included. Changed window type (SF19).

Item I-15. Sheet A-202: Replace with revised sheet, included. Changed window type (SF18).

Item I-16. Sheets A-301 and A-355: Replace with revised sheets, included. Added concrete curb at lobby curtain walls.

Item I-17. Sheet A-405: Replace with revised sheet, included. Added gate dimension notes.

Item I-18. Sheet A-514: Replace with revised sheet, included. Added detail of concrete curb at lobby curtain wall.

Item I-19. Sheet A-551: Replace with revised sheet, included. Added new ceiling details (see updated RCPs for detail locations).

Item I-20. Sheet A-601: Replace with revised sheet, included.

1. Added 45 min. rating to Doors 126B and 148.
2. Updated frame finish to dark bronze on Doors 131, 132, 133, 134, 135, 280, 281, and 287.
3. Removed access control from Doors 101K, 106B, 107, 202, 207, S4, 302, and 402.
4. Added access control to Doors 125, 126A, 126B, 268, S3, S3B, S2A, and S2B.
5. Added impact glazing comment at exterior EOC/911/Hub doors with lites.

Item I-21. Sheet A-611: Replace with revised sheet, included. Revised lobby curtain walls with concrete curb.

Item I-22. Sheet A-612: Replace with revised sheet, included. Added window types: SF18 on 3<sup>rd</sup> Level and SF19 on 4<sup>th</sup> Level.

Item I-23. Sheet A-700: Replace with revised sheet, included.

1. Updated WWP-1.
2. Added PNT-8 (HUB/Mini HUB).
3. Added PNT-10 (Clinic).

Item I-24. Add Sheet A-701, included.

Item I-25. Sheet A-801: Replace with revised sheet, included.

1. Added Conc-1 and Conc-2 hatch to floor finish legend.
2. Updated HVAC room finish to show traffic coating (Conc-2).
3. Changed Corridor 158 flooring from CPT-1 to LVT-1.
4. Added accent wall outside Mini HUB 221 (PNT-3).
5. Updated floor pattern in Training 136, 137, and 139.

Item I-26. Sheet A-802: Replace with revised sheet, included. Changed Elec. 202 flooring from VCT-1 to sealed concrete (Conc-1).

Item I-27. Sheet A-803: Replace with revised sheet, included.

1. Changed Elec. 302 flooring from VCT-1 to sealed concrete (Conc-1).
2. Changed flooring in Rooms 322, 323, 324, 325, 326, 328, 329, 330, 331, 332 from CPT-2 to CPT-4.

Item I-28. Sheet A-804: Replace with revised sheet, included.

1. Changed Elec. 402 flooring from VCT-1 to sealed concrete (Conc-1).

2. Changed flooring in Rooms 422, 423, 424, 425, 427, 428, 429, 430, 431, 443, 444, 445 from CPT-2 to CPT-4.
3. Changed Open Office 474 flooring from CPT-2 to CPT-5.

Item I-29. Sheet P-101A: Replace with revised sheets, included. Added notation.

Item I-30. Sheet P-101B: Replace with revised sheets, included.

1. Change Shown on Revised Sheet:
  - a. Added notation.
2. Changes Not Shown on Revised Sheet:
  - a. Janitor 148: Add mop sink and associated hot and cold water service.
  - b. Corridor 147B (at millwork outside of Fitness 140): Add water connection box (F9) for undercounter ice machine.

Item I-31. Sheet P-101C: Replace with revised sheet, included.

1. Change Shown on Revised Sheet:
  - a. Added partial plan call outs.
2. Changes Not Shown on Revised Sheet:
  - a. HUB Kitchen 152: Add water connection boxes (F9) for two undercounter ice machines.
  - b. Kitchen 171: Add water line for undercounter ice machine.

Item I-32. Sheet P-102B: Replace with revised sheet, included.

1. Change Shown on Revised Sheet:
  - a. Added notation.
  - b. Updated distribution piping.
2. Change Not Shown on Revised Sheet:
  - a. Mini Hub 221: Add water connection box (F9) for undercounter ice machine.

Item I-33. Sheet P-102C: Replace with revised sheet, included.

1. Removed notation.
2. Added partial plan call out.

Item I-34. Sheet P-103B: Replace with revised sheet, included.

1. Change Shown on Revised Sheet:
  - a. Updated distribution piping.
2. Change Not Shown on Revised Sheet:
  - a. Mini Hub 321: Add water connection box (F9) for undercounter ice machine.

Item I-35. Sheet P-104A: Replace with revised sheet, included.

1. Added piping to TLT440.
2. Added partial plan call out.

Item I-36. Sheet P-104B: Replace with revised sheet, included.

1. Change Shown on Revised Sheet:
  - a. Updated distribution piping.

2. Change Not Shown on Revised Sheet:
  - a. Mini Hub 421: Add water connection box (F9) for undercounter ice machine.

Item I-37. Sheet P-201B:

1. Janitor 148: Add waste for mop sink.
2. Corridor 147B (at millwork outside of Fitness 140): Add floor drain for undercounter ice machine.

Item I-38. Sheets P-201C: Replace with revised sheet, included.

1. Change Shown on Revised Sheet:
  - a. Added partial plan call out.
2. Changes Not Shown on Revised Sheet:
  - a. HUB Kitchen 152: Add floor drains for two undercounter ice machines.
  - b. Kitchen 171: Add floor drain for undercounter ice machine.

Item I-39. Sheet P-202B, Mini Hub 221: Add floor drain for undercounter ice machine.

Item I-40. Sheet P-202C: Replace with revised sheet, included. Added partial plan call out.

Item I-41. Sheet P-203A: Replace with revised sheet, included.

1. Added waste piping for restrooms on Level 4.
2. Added notation.

Item I-42. Sheet P-203B, Mini Hub 321: Add floor drain for undercounter ice machine.

Item I-43. Sheet P-204A: Replace with revised sheet, included.

1. Added piping to TLT440
2. Added notation
3. Added partial plan call out

Item I-44. Sheet P-204B, Mini Hub 421: Add floor drain for undercounter ice machine.

Item I-45. Sheet P-301: Replace with revised sheet, included. Edited partial plans.

Item I-46. Sheets P-302 and P-303: Replace with revised sheets, included. Added partial plans.

Item I-47. Sheet M-101A: Replace with revised sheet, included.

1. Reworked ductwork over register of Deeds 121B.
2. Relocated terminal units.

Item I-48. Sheet M-101B: Replace with revised sheet, included.

1. Changed diffusers in Storage 144 Storage, and 143 Media from S-CF to S-SR.
2. Relocated terminal unit S120 from 143 Media to 142 Production.
3. Replaced return grill with transfer duct in 143 Media.
4. Modeled duct lining on return and supply.
5. Increased return ductwork size.
6. Relocated terminal units.

Item I-49. Sheet M-101C: Replace with revised sheet, included.

1. Relocated terminal units.

2. Reworked ductwork over bathrooms.
3. Modeled outside air control damper.
4. Modeled relief air control damper and airflow measuring system over Storage 176.
5. Added S-LD type diffusers plan north of Hub 153.
6. Modeled duct lining on supply and return.
7. Changed restroom terminal units to have electric reheat.

Item I-50. Sheet M-102A: Replace with revised sheet, included.

1. Reworked ductwork over Office 243.
2. Added fire damper downstream of S250.
3. Added terminal unit for elevator lobby.
4. Modeled duct lining on return.

Item I-51. Sheet M-102B: Replace with revised sheet, included.

1. Added diffuser to Storage 265.
2. Changed terminal units S231, S230, S229, S228, S238, and S239 to have electric reheat.

Item I-52. Sheet M-102C: Replace with revised sheet, included.

1. Reworked ductwork over EOC and Hub.
2. Changed bathroom terminal units to have electric reheat.
3. Added two terminal units to serve Hub.
4. Removed fan powered terminal unit from hub mezzanine.
5. Modeled relief air control damper and airflow measuring system.

Item I-53. Sheet M-103A: Replace with revised sheet, included.

1. Modeled duct lining on return.
2. Reworked ductwork plan north on drawing.
3. Added plenum returns.

Item I-54. Sheet M-103B: Replace with revised sheet, included.

1. Changed terminal units S320, S319, S318, S317 and S328 to have electric reheat.
2. Added plenum returns.

Item I-55. Sheet M-104A: Replace with revised sheet, included. Office 440 changed to TLT 440. Removed plenum return and added exhaust diffuser.

Item I-56. Sheet M-104B: Replace with revised sheet, included. Modeled duct lining on return.

Item I-57. Sheet M-301: Replace with revised sheet, included.

1. FS damper relocated to be at floor.
2. Modeled control dampers for the AHU and ERU.
3. Modeled heat trace control panel.
4. Added sound attenuator for AHU-1-1.

Item I-58. Sheet M-402: Replace with revised sheet, included.

1. Modeled duct lining on supply and return.
2. Added sound attenuator for RTU-R-3

Item I-59. Sheet M-502: Replace with revised sheet, included. Added a note to the finned turb radiation schedule for the color to be bronze.

Item I-60. Sheet M-503: Replace with revised sheet, included.

1. Added two terminal units to Level 1
2. Revised schedule notes.

Item I-61. Sheet M-504: Replace with revised sheet, included.

1. Added one terminal unit to Level 4.
2. Revised schedule notes.

Item I-62. Sheet M-602: Replace with revised sheet, included. Added pipe isolation detail.

Item I-63. Sheet M-603: Replace with revised sheet, included. Updated AHU detail.

Item I-64. Sheet M-701: Replace with revised sheet, included. Air flow measuring system removed from schematic and added to each fan inlet.

Item I-65. Sheet M-702: Replace with revised sheet, included. Airflow measuring system added to each fan inlet.

Item I-66. Sheet FP-001: Replace with revised sheet, included. Riser diagram corrected to include valves.

Item I-67. Sheet FP-002: Replace with revised sheet, included. Clarified FDC detail.

Item I-68. Sheet FP-101C: Replace with revised sheet, included. Removed tradework crossing matchlines.

Item I-69. Sheets FP-102B, FP-103B and FP-104B: Replace with revised sheets, included. Shifted notes for clarity.

Item I-70. Sheet E-001: Replace with revised sheet, included. Clarified electrical legend.

Item I-71. Sheet E-002: Replace with revised sheet, included.

1. Updated luminaire schedule.
2. Added: R1, S3, TH1, TR1. Removed: J2.

Item I-72. Sheet E-100: Replace with revised sheet, included. Added power connections for site lighting.

Item I-73. Sheet E-101A: Replace with revised sheet, included. Changed water fountain power connection.

Item I-74. Sheet E-101B: Replace with revised sheet, included.

1. Changed water fountain power connection.
2. Removed power for digital signage.
3. Reworked power plan in Media room and added power for Media lighting.
4. Added duplex receptacle and lighting control panel in ELEC. 141.
5. Added power connections for Fresco touchpads.

Item I-75. Sheet E-101C: Replace with revised sheet, included.

1. Changed water fountain power connection.
2. Added garbage disposal receptacle and switch to HUB KITCHEN 152 and KITCHEN 171.

Item I-76. Sheet E-102B: Replace with revised sheet, included.

1. Changed water fountain power connection.
2. Added receptacles to MINI HUB 221 Island.
3. Deleted floor box in MINI HUB 221.
4. Re-arranged receptacle circuits, adding new circuits to balance loads.



Item I-77. Sheet E-102C: Replace with revised sheet, included.

1. Added raised floor power system components (floor boxes, bus track, etc.) and connections. Deleted connections to floor boxes now fed from raised floor system bus track.
2. Deleted power for OFFICE 271.

Item I-78. Sheet E-103B: Replace with revised sheet, included.

1. Changed water fountain power connection.
2. Added receptacles to MINI HUB 321 Island.
3. Re-arranged receptacle circuits, adding new circuits to balance loads.

Item I-79. Sheet E-104A: Replace with revised sheet, included. Added receptacle and power connections to new TLT 440.

Item I-80. Sheet E-104B: Replace with revised sheet, included.

1. Changed water fountain power connection.
2. Added receptacles to MINI HUB 421 Island.
3. Re-arranged receptacle circuits, adding new circuits to balance loads.

Item I-81. Sheets E-111, E-112, E-113 and E-114: Replace with revised sheets, included. Updated terminal unit electrical loads, connection types and connection locations.

Item I-82. Sheet E-201A: Replace with revised sheet, included.

1. Added under-counter toe lighting.
2. Reworked lighting zoning.

Item I-83. Sheet E-201B: Replace with revised sheet, included.

1. Added track lighting and touchpad controller to Training 136 and 137, Conference 139, and Lobby B 120B.
2. Reworked lighting in Media 143. Added pipe grid.
3. Reworked lighting zoning.

Item I-84. Sheets E-201C, E-202A, E-202B, E-202C, E-203A, E-203B, E-204A, and E-204B: Replace with revised sheets, included. Reworked lighting zoning.

Item I-85. Sheet E-205: Replace with revised sheet, included. Added façade lighting circuiting notes.

Item I-86. Sheet E-301: Replace with revised sheet, included.

1. Added special receptacle for AT&T rack in COMM 208.
2. Added hardwired connections for (2) in-row server rack coolers in SERVER 206.
3. Added hardwired connection to heat trace/control panel in HVAC 109.

Item I-87. Sheet E-302: Replace with revised sheet, included. Clarified enlarged plan layouts.

Item I-88. Sheet E-501: Replace with revised sheet, included.

1. Added schedule for panel LCP1B-T
2. Clarified schedules.

Item I-89. Sheets E-502 and E-503: Replace with revised sheets, included. Updated terminal unit electrical loads and connection types in connection schedules.

Item I-90. Sheets E-504, E-505, E-506, E-507, E-508, E-509, E-510, E-511 and E-512: Replace with revised sheets, included. Updated panel schedules.

Item I-91. Sheet E-604: Replace with revised sheet, included. Clarified Overhead Power Distribution Busway detail.

Item I-92. Sheet E-607: Replace with revised sheet, included. Clarified lighting control details.

Item I-93. Sheet FA-102B: Replace with revised sheet, included. Added wattage and candela ratings.

Item I-94. Sheet FA-102C: Replace with revised sheet, included. Added strobe to reception area.

Item I-95. Sheet FA-103A: Replace with revised sheet, included. Added wattage and candela ratings.

Item I-96. Sheet FA-105: Replace with revised sheet, included. Clarified enclosures for roof devices.

Item I-97. Sheet T-001: Replace with revised sheet, included. Added raised floor box symbol.

Item I-98. Sheet T-100: Replace with revised sheet, included. Removed underground conduits to tower. Conduits are being installed by tower company.

Item I-99. Sheet T-101C: Replace with revised sheet, included. Updated North-west camera view and cable tray detail.

Item I-100. Sheet T-102B: Replace with revised sheet, included. Added informacast speakers to bathroom, 236-237 and corridor.

Item I-101. Sheet T-102C: Replace with revised sheet, included. Removed overhead telecom equipment and updated layout to match raised floor in the EOC. Updated keynotes.

Item I-102. Sheet T-103B: Replace with revised sheet, included. Added data drops in maintenance office and updated elevator room tags.

Item I-103. Sheet T-104B: Replace with revised sheet, included. Added informacast speaker to Corridor 420 and updated elevator room tags.

Item I-104. Sheet T-401: Replace with revised sheet, included.

1. Updated server to match vendor layout.
2. Added telecommunication grounding bar.
3. Added AT&T cabinet keynote.

Item I-105. Sheets T-402 and T-403: Replace with revised sheets, included. Added measure accordingly and updated keynotes.

Item I-106. Sheet T-501: Replace with revised sheet, included. Updated Detail 3 to match AV/electrical.

Item I-107. Sheet SC-001: Replace with revised sheet, included. Detail 2, updated local door alarm and RTE motion detector information.

Item I-108. Sheet SC-101C: Replace with revised sheet, included. Remove egress detail from Corridor 158.

Item I-109. Sheet SC-102A: Replace with revised sheet, included. Remove electrical elevation callout details.

Item I-110. Sheet SC-102C: Replace with revised sheet, included.

1. Added door tag south stair next to Room JCC 287.
2. Moved Door 268, deleted annotation details.

Item I-111. Sheets SC-103A and SC-103B: Replace with revised sheets, included. Remove AV elevation callout.

Item I-112. Sheet SC-104A: Replace with revised sheet, included. Remove electrical elevation callout.

Item I-113. Sheet AV-000: Replace with revised sheet, included.

1. Changed Floorbox and Poke Through symbols to match symbols with Electrical/Telecom.
2. Removed Wall Mounted Speaker symbol which is not needed on this project.
3. Rearranged some Symbols list and revised notes to match with new requirements.

Item I-114. Sheet AV-101A: Replace with revised sheet, included. Moved W1 backbox below the TV1 backbox.

Item I-115. Sheet AV-101B: Replace with revised sheet, included.

1. Removed Cable Tray and sleeves info and moved into the telecom set.
2. Added W2 mic input backboxes across multiple rooms to accommodate Press Feeds.
3. SP (Scheduling panels) shown are currently mounted on the glass next to the entry door, more details on mounting is shown on the AV Details sheets for further coordination.

Item I-116. Sheet AV-101C: Replace with revised sheet, included. Moved W1 backbox below the TV2 backbox.

Item I-117. Sheet AV-101D: Delete sheet in its entirety. Ceiling speakers in lobby areas will be part of the telecom system.

Item I-118. Sheet AV-102B: Replace with revised sheet, included.

1. SP (Scheduling panels) shown are currently mounted on the glass next to the entry door, more details on mounting is shown on the AV Details sheets for further coordination.
2. Removed Poke through from Room 227.

Item I-119. Sheet AV-102C: Replace with revised sheet, included.

1. Currently shown Floor Poke Through beneath the Table in EOC 279 are removed as this is a new raised floor.
2. New cable pathway is shown as the floor has been changed to raised floor, see telecom set for details.

Item I-120. Sheet AV-103B: Replace with revised sheet, included.

1. SP (Scheduling panels) shown are currently mounted on the glass next to the entry door, more details on mounting is shown on the AV Details sheets for further coordination.
2. Added W1 back boxes below TV1 in plan review 369.

Item I-121. Sheet AV-121: Replace with revised sheet, included. Added RCP to show ceiling speakers in the EOC and side rooms.

END OF ADDENDUM 1