LEGEND- REFLECTED CEILING PLAN

- ACT-1 24"x24" LAY-IN ACOUSTIC CEILING TILE
- ACT-2 24"x48" LAY-IN ACOUSTIC CEILING TILE
- ACT-3 48"x96" LAY-IN ACOUSTIC CEILING W/ INTEGRATED LIGHTING AND HVAC
- ACT-4 48"x96" LAY-IN ACOUSTIC CEILING W/ INTEGRATED LIGHTING AND HVAC
- ACT-5 48"x96" LAY-IN ACOUSTIC CEILING W/ INTEGRATED LIGHTING AND HVAC
- 3'-0"X3'-0" PIPE GRID SYSTEM STRUCTURE ABOVE EXPOSED & PNT BLACK
- WPP-1 WOOD SOFFIT
- GYPSUM BOARD
- EXPOSED STRUCTURE - NO CEILING
- EXPOSED STRUCTURE - DRYFALL PAINTED ABOVE
- 2 X 2 LED RECESSED TROFFER
- 2 X 4 LED RECESSED TROFFER
- 4" SQUARE RECESSED LED LIGHTS
- RECESSED LED STRIP LIGHT, LENGTH VARIES
- DECORATIVE PENDANT
- CONTINUOUS LINEAR SUSPENSION INDIRECT/ DIRECT LED, LENGTH VARIES
- 1'x4' LED SUSPENDED LINEAR UTILITY FIXTURE
- LED PENDANT, MULTI HEIGHT/ SHAPE/ DIAMETER; TBD
- WAC LIGHTING WALL SCONCE; EXACT FIXTURE TBD
- RETURN AIR DIFFUSER
- EXHAUST FAN
- SUPPLY AIR DIFFUSER
- LINEAR AIR DIFFUSER
- 555'-5 5/5" AFF — HEIGHT ABOVE FINSHES FLOOR 9'-0" U.N.O.
- LIGHT COVE

TRUE NORTH | PROJECT NORTH

A1 / A-123A	RCP- PARTIAL- LEVEL 3 - AREA A	1/8" = 1'-0"	RCP LEGEND	1/8" = 1'-0"

CAPE FEAR FD STONEWATER

LS3P

101 NORTH THIRD STREET, SUITE 500
WILMINGTON, NORTH CAROLINA 28401
TEL. 910.790.9901 FAX. 910.790.3111
WWW.LS3P.COM

LS3P ASSOCIATES LTD. CERT. NO. 50417 WILMINGTON, NORTH CAROLINA

NOT FOR CONSTRUCTION

NHC Goverment Center 7702-190810

NEW HANOVER COUNTY GOVERNMENT CENTER

GOVERNMENT CENTER DRIVE
WILMINGTON, NC 28403

LS3P PROJECT: 7702-190810

Δ	DATE	DESCRIPTION
A	2020.08.18	TI- SCHEMATIC DESIGN
B	2020.10.16	TI- DESIGN DEVELOPMENT
C	2020.11.20	TI GMP SET
D	2020.12.16	GMP SET
E	2020.12.22	ADDENDUM #1

KEY PLAN:



SHEET NAME:
REFLECTED CEILING PLAN- LEVEL 3 AREA A

ORIG SUBMISSION: 2020.12.16
CURRENT: 2020.12.22
ADDENDUM #1

SHEET:
A-123A

GMP SET

12/22/2020 2:12:51 PM