INTERIOR FINISH LEGEND

ALL MATERIALS ARE BASIS OF DESIGN, SEE SPECIFICATIONS FOR APPROVED EQUALS.

FINISH CODE	MANUFACTURER	PRODUCT NAME	PRODUCT NUMBER	COLOR	SIZE / WIDTH	DESCRIPTION	REMARKS
FLOOR BASE							
B-1	TARKETT/JOHNSONITE	BASEWORKS	TSB-63-4	BURNT UMBER	4" H	THERMOSET RUBBER COVE BASE	-
B-2	TARKETT/JOHNSONITE	MILLWORK	MW-63-F	BURNT UMBER	4 1/4" H X 1/4" THICK	PROFILE RUBBER BASE	MITER ALL CORNERS
B-3	BEST TILE	BAMBUSA		GRIGIO	2.5" x 24"	PORCELAIN TILE - BULLNOSE	GR-2 - TO EXTEND UP IN BASE, BASE TO SET ON TOP OF TR-5/ 1/A705, 1/8" GROUT JOINT
B-4	STONHARD	STONTEC TRF		SMOKEY MOUNTAIN		EPOXY FLOOR SYSTEM	FLASH COVE BASE, COVE BACK STRIP & METAL TOP CAP TR-8, 1/A705
B-5	TRINITY	WHITE WATER		WAVE	3" x 24", 8MM	PORCELAIN TILE - BULLNOSE	GR-1 - TO EXTEND UP IN BASE, BASE TO SET ON TOP OF TR-5 / 1/A705
B-6	BEST TILE	LINK	--	TIE	6" x 12", 9MM, MATTE	PORCELAIN TILE COVE BASE	GR-1 EXTEND UP IN BASE, BASE TO ALIGN WITH FLOOR TILE.
B-7	STONHARD	STONCLAD GS/STONKOTE GS4/ STONSEAL ST6	--	PEWTER	1/4" THICK	EPOXY URETHANE MORTAR SYSTEM, GRIT 3	ALTERNATE 6, FOR APPARATUS ROOM A - 201 & ROOM B 209, FLASH COVE BASE,COVE BACK STRIP & METAL TOP CAP, 1/A705
FLOORING							
CPT-1	MANNINGTON	OUTLINE	15217	BOROUGH	24" X 24"	CARPET - TILE	BRICK, SEE FINISH PLAN
CPT-2	J&J FLOORING GROUP	RUNWAY II WALK-OFF 7267	1421	FRESH FACE	24" X 24"	CARPET - WALK OFF TILE	BRICK, SEE FINISH PLAN
CPT-3	STATIC SMART PLUS/JULIE INDUSTRIES	COLONIAL	-	PENN	24" X 24"	STATIC DISSIPATIVE CARPET - TILE	QUARTER TURNED, ALIGN CARPET TILE WITH RAISED FLOOR PANEL
LV-1	J&J FLOORING GROUP	LEGEND V5010	1057	TALE	18" x 36", 5MM, 20 MIL	LUXURY VINYL - PLANK	GLUE DOWN RESILIENT PLANK, BRICK PATTERN
LV-2	SHAW	SOLITUDE 0648V	48599	FRENCH GRAY	6" x 48", 5MM, 20 MIL	LUXURY VINYL - PLANK	GLUE DOWN RESILIENT PLANK, STAGGERED PATTERN
LV-3	PATCRAFT	WOODEN WARP I484V	00580	BOBBIN	9" x 36", 3MM	WOVEN LUXURY VINYL - PLANK	STAGGERED, EXOGUARD FINISH, GLUE DOWN
LV-4	PATCRAFT	WOODEN WARP I484V	00775	JAQUARD	9" x 36", 3MM	WOVEN LUXURY VINYL - PLANK	STAGGERED, EXOGUARD FINISH, GLUE DOWN
PT-1	BEST TILE	LINK	--	TIE	24" x 24", 9MM, MATTE	PORCELAIN TILE, RECTIFIED	GR-1, 3/16" GROUT JOINT
PT-2	BEST TILE	LINK	--	TIE	2" x 2", 9MM, MATTE	PORCELAIN TILE, MOSAIC	GR-1, 3/16" GROUT JOINT
PT-3	TRINITY	WHITE WATER	-	WAVE	12" x 24", 8MM	PORCELAIN TILE	GR-1, 3/16" GROUT JOINT
EPF-1	STONHARD	STONTEC TRF	-	SMOKEY MOUNTAIN	-	EPOXY FLOOR SYSTEM, GRIT 2	
EPF-2	STONHARD	STONCLAD GS/STONKOTE GS4/ STONSEAL ST6	-	PEWTER	1/4" THICK	EPOXY URETHANE MORTAR SYSTEM, GRIT 3	ALTERNATE 6, FOR APPARATUS ROOM A - 201 & ROOM B 209
SC-1	LATICRETE	-	-	CLEAR	-	SEALED CONCRETE	
SC-2	LATICRETE	L & M SEAL HARD/ HARDENER/DENSIFIER	BOTTOM LAYER- CLEAR/ TOP LAYER COLOR	CLEAR/GRAY/CLEAR TOP COAT		SEALED CONCRETE - HARDENER/DENSIFIER/ SEALER	SUBMIT ALL COLORS FOR ARCHITECT TO SELECT. SEE A703 FOR AREA COLOR DESIGNATIONS.
SC-3	LATICRETE	L & M SEAL HARD/ HARDENER/DENSIFIER	BOTTOM LAYER- CLEAR/ TOP LAYER COLOR	CLEAR/ SAFETY YELLOW/CLEAR TOP COAT		SEALED CONCRETE - HARDENER/DENSIFIER/ SEALER	SUBMIT ALL COLORS FOR ARCHITECT TO SELECT. SEE A703 FOR AREA COLOR DESIGNATIONS.
SDT-1	STATICSMART	SUMMIT SERIES	C6061/2	GREY LOCK	12" x 12"	ELECTRIC STATIC DISSIPATIVE VINYL TILE	ALIGN JOINTS W/RAISED FLOOR PANELS
VCT-1	ARMSTRONG	STANDARD EXCELON IMPERIAL TEXTURE	51861	SOFT WARM GRAY	12" x 12" x 1/8"/3.2MM	VINYL COMPOSITE TILE	-
WALLS							
EPW-1	STONHARD	STONGLAZE	VSR	ASH GRAY		EPOXY WALL SYSTEM	
P-1	SHERWIN WILLIAM	TRIM PAINT	SW7069	IRON ORE	SEMI-GLOSS	TRIM PAINT	
P-2	SHERWIN WILLIAM	STANDARD PAINT	SW7064	PASSIVE	EG SHEL	STANDARD WALL PAINT	-
P-3	SHERWIN WILLIAM	ACCENT PAINT	SW6962	DAZZLE	EG SHEL	ACCENT WALL & CEILING PAINT	SEE FINISH SCHEDULE FOR EPOXY LOCATIONS
P-4	SHERWIN WILLIAM	ACCENT PAINT	SW7652	MINERAL DEPOSIT	EG SHEL	ACCENT WALL & CEILING PAINT	SEE FINISH SCHEDULE FOR EPOXY LOCATIONS CEILING PAINT & SOFFIT TO BE FLAT PAINT FINISH
P-5	SHERWIN WILLIAM	ACCENT PAINT	SW7018	DOVETAIL	EG SHEL	ACCENT WALL & CEILING PAINT	SEE FINISH SCHEDULE FOR EPOXY LOCATIONS CEILING PAINT & SOFFIT TO BE FLAT PAINT FINISH
P-6	SHERWIN WILLIAM	ACCENT PAINT	SW7057	WEB GRAY	FLAT	ACCENT WALL & CEILING PAINT	SEE FINISH SCHEDULE FOR EPOXY LOCATIONS CEILING PAINT & SOFFIT TO BE FLAT PAINT FINISH
P-7	SHERWIN WILLIAM	ACCENT PAINT	SW7757	HIGH REFLECTIVE WHITE	FLAT	ACCENT WALL & CEILING PAINT	SEE FINISH SCHEDULE FOR EPOXY LOCATIONS CEILING PAINT & SOFFIT TO BE FLAT PAINT FINISH
P-8	SHERWIN WILLIAM	STANDARD PAINT	SW6993	BLACK OF NIGHT	FLAT	ACCENT WALL & CEILING PAINT	
P-9	SHERWIN WILLIAM	STANDARD PAINT	-	TO MATCH LIGHT GRAY K-13	FLAT	ACCENT WALL & CEILING PAINT	-
SSF-2	INPRO	BIOPRISM WALL CLADDING	P9011	BRIGHT WHITE	1/4" THICK PANEL, SMOOTH	SOLID SURFACE PANELS, DECONTAMINATION SHOWER STALL	SHOWER AREA, HARD SEAM WAVY EDGE, CAULK SEAM, TOP & BOTTOM CAP
WT-1	BEST TILE	BAMBUSA	-	GRIGIO	12" x 24", 10 MM	PORCELAIN TILE, FASCIA TEXTURE, RECTIFIED	GR-2, 1/8" GROUT JOINT, SEE FINISH PLANS & TOILET ELEVATIONS
WT-2	FLORIDA TILE	EMOTIVE	TBD	ENVY - SILK	4" x 9" TRAPEZOID	GLAZED CERAMIC TILE	GR-2, 1/8" GROUT JOINT, SEE FINISH PLANS, TOILET & CASEWORK ELEVATIONS
WP-1	ALTRO	WHITE ROCK	W103/W104	STANDARD WHITE	8' / 10' HIGH X 4' W		-
SURFACES							
PL-1	WILSONART	PLASTIC LAMINATE	6698-58	PALOMA POLAR	MATTE FINISH	COUNTER TOPS, BACK AND SIDE SPLASH	-
PL-2	FORMICA	PLASTIC LAMINATE	8848-PG	BLACKENED LENGO	SOFT GRAIN FINISH	UPPER AND LOWER VERTICAL CABINETS	-
QTZ-1	SILESTONE	QUARTZ	-	MERANGO	3CM	COUNTERTOPS	TOILETS
QTZ-2	SILESTONE	QUARTZ		KENSHO	3CM	COUNTERTOPS	KITCHENS, BREAK ROOM
SSF-1	FORMICA	SOLID SURFACE	781	LUNA CONCRETE	1/2" THICK	COUNTERTOPS, BACK,SIDE SPLASH, WINDOW SILLS	LAUNDRY
MISCELLANEOUS							
AWP-1	WHISPER WALL	WHISPER TRACK	BAILEY 2299	BELMONT SILVER 7010	3'-0" - 10'-0" A.F.F.	SITE FABRICATED ACOUSTICAL PANELS, 1" TRACK, SQUARE EDGE PROFILES	ALTERNATE 9. FOR E.O.C/MULTIPURPOSE ROOM 058
CG-1	CONSTRUCTION SPECIALTIES	SM-20AN	927	FOLKSTONE	3" X 4'	90 DEGREE, SURFACE MOUNTED, RADIUS, BULLNOSE CORNER GUARD	MATCH ADJACENT WALL, SEE FINISH PLANS FOR LOCATIONS, 3/A705
CG-2	CONSTRUCTION SPECIALTIES	SM-20MN	927	FOLKSTONE	3" X 4'	ODD ANGLE, SURFACE MOUNTED, RADIUS, BULLNOSE CORNER GUARD	MATCH ADJACENT WALL, SEE FINISH PLANS FOR LOCATIONS, 4/A705
CR-1			-	ST-1		-	SEE FINISH PLAN LOCATIONS AND ROOM FINISH SCHEDULE
CRT-1	SOURCE ONE/MOMENTUM	CAUSEWAY	TBD	SUMMER SHOWER	72"W/100% POLY. FR	CURTAIN - (SHOWER)	-
D-1	MASONITE/ASPIRO	PREFINISHED DOOR W/STAIN	WHITE MAPLE	COCOA BEAN	PLAIN SLICED	PREFINISHED WOOD DOOR, STAINED	
FRP-1	CRANE COMPOSITES	FRP PANELS SANITARY WALL PANELS, GLASBORD "FX"	85	WHITE	0.090' THICK, 4'X8'	CLASS A, WITH MATCHING CAULK VERTICAL SEAMS AND TOP, BOTTOM EDGE TRIMS	AT ALL JANITOR SINKS, INSTALL HORIZONTALLY, UNLESS CALLED OUT IN REMARKS OR ON FINISH PLANS
GR-1	TEC	ACCUCOLOR EFX	927	LIGHT PEWTER		FLOOR GROUT - EPOXY	-
GR-2	TEC	INCOLOR ADV. PERFORMANCE	939	MIST	-	WALL GROUT	-
LCK-1	PENCO	LOCKERS	054	CANVAS	-	-	-
MB-1	-	MARKER BOARD	-	-	-	-	-
N-1	TARKETT	NOSING - VIVCD-XX	63	BURNT UMBER	-	-	NOSING FOR PLATFORM
TB-1	-	TACK BOARD	-	-	-	-	-
TP-1	SCRANTON	TOILET PARTITION	-	CHARCOAL GREY	-	HDPE	-
TR-1	TARKETT	METALEDGE 001	178	IRONSTONE	-	TRANSITION STRIP - CARPET TO RESILIENT FLOORING	1/A705
TR-2	TARKETT	EDGE GUARD	63	BURNT UMBER	EG-63-H	TRANSITION STRIP - CARPET TO CONCRETE	1/A705
TR-3	SCHLUTER	SCHIENE	-	STAINLESS	-	TRANSITION - CARPET TO TILE, TILE TO TILE	1/A705
TR-4	SCHLUTER	RENO-U	-	STAINLESS	-	TRANSITION - TILE TO RESILENT-CONCRETE	1/A705
TR-5	SCHLUTER	DILEX-AHK	-	ANNODIZED ALUMINUM	-	TRANSITION - COVE FLOOR TO WALL TILE	1/A705
TR-6	SCHLUTER	QUADEC-K	-	SATIN ANNODIZED ALUMINUM - AE	-	TRANSITION -CORNER SQUARE EDGE	1/A705
TR-7	SCHLUTER	JOLLY	-	SATIN NICKEL ANNODIZED ALUMINUM - AT	-	TRANSITION - EDGE OF WALL TILE	1/A705
TR-8	SCHLUTER	SCHIENE		STAINLESS		TRANSITION - TOP OF FLASHCOVE BASE	1/A705
TR-9	TARKETT	SLIM LINE TRANSITION	63	BURNT UMBER	SLT-63-B	TRANSITION STRIP - LV TILE TO VCT TILE	1/A705
TR-10	SCHLUTER	DILEX-AHKA		STAINLESS		TRANSITION - COVE FLOOR TO WALL TILE	1/A705
WC-1	HUNTER DOUGLAS	ALUMINUM	METALLIC/BRUSHED	BRUSHED ALUMINUM	1" MINIBLINDS	WINDOWCOVERING - BLINDS	

INTERIOR FINISH GENERAL NOTES

1. TBD = TO BE DETERMINED.
2. REFERENCE INTERIOR ELEVATIONS, SECTIONS, DETAILS AND REFLECTED CEILING PLAN FOR ADDITIONAL INFORMATION (SEE COVER SHEET DRAWING INDEX AND/OR SHEET SERIES A700'S, A800'S & A900'S).
3. VERIFY LOCATION OF CONTROL JOINTS IN ROOMS RECEIVING TILE FLOORS. SEE WRITTEN SPECIFICATIONS DIVISION 9.
4. REFERENCE FINISHES ON INTERIOR ROOM FINISH SCHEDULE AND MILLORK ELEVATIONS.
5. ALL INTERIOR WALL & CEILING FINISHES SHALL COMPLY WITH **NCSBC CHAPTER 8, SECTION 803, TABLE 803.11**.
   INTERIOR FINISHES COMPLY WITH **NCSBC TABLE 803.11**
   SPRINKLERED:
   A. INTERIOR EXIT STAIRWAYS, RAMPS AND EXIT PASSAGEWAYS: **CLASS B**
   B. CORRIDORS & ENCLOSURES FOR EXIT ACCESS STAIRWAYS AND RAMPS: **CLASS C**
   C. ROOM AND ENCLOSED SPACES **CLASS C**
   D. WALL TEXTILES: CLASS **A** FLAME SPREAD
6. INTERIOR FLOOR FINISHES COMPLY WITH **NCSBC SECTION 804.**
7. ALL INTERIOR FINISHES IN TOILET AND BATHROOMS SHALL COMPLY WITH **NCSBC CHAPTER 12, SECTION 1210.2, 1210.2.1 THROUGH 1210.2.4.**

ROOM FINISH SCHEDULE

RM NO.	NAME	FLOOR	BASE	DOOR FRAME/ MISC. TRIM	DOOR	WALLS: STAND. WALL	WALLS: ACCENT WALL	WALLS: CHAIR RAIL ABOVE	WALLS: CHAIR RAIL BELOW	MILLWORK: COUNTER TOP	MILLWORK: CABINET FRONT	MILLWORK: CABINET BASE	COMMENTS	RM NO.
	PATIO	-	-	-	-	-								
001	LOBBY	PT-3	B-5	P-1	D-1/ALUM	P-2	P-4			QTZ-1			SEE FINISH PLAN FOR ACCENT WALL LOCATION, SEE WALL SECTIONS 2/A401 & 6/A406	001
002	STORAGE	VCT-1	B-1	P-1	D-1	P-2								002
003	PUBLIC TOILET	PT-1	TR-5	P-1	D-1	WT-1							TILE INSTALLED FULL HEIGHT ON WALLS, SEE A500'S TOILET ELEVATIONS	003
004	CORR.	CPT-1	B-1	P-1	D-1	P-2							LV-4 AS ALTERNATE 8	004
005	WORK ALCOVE	CPT-1	B-1	P-1	D-1	P-2				PL-1	PL-2	PL-2	SEE A900'S CASEWORK ELEVATIONS	005
006	ADMIN ASST	CPT-1	B-1	P-1	D-1	P-2								006
008	E.M.DIRECTOR	CPT-1	B-1	P-1	D-1	P-2								008
009	EMS OPERATIONS CHIEF	CPT-1	B-1	P-1	D-1	P-2								009
010	STORAGE	VCT-1	B-1	P-1	D-1	P-2								010
011	CONFERENCE	CPT-1	B-2	P-1	D-1	P-2				PL-1	PL-2	PL-2	SEE A900'S CASEWORK ELEVATIONS	011
012	ADMIN ASST	CPT-1	B-1	P-1	D-1	P-2				QTZ-1			QTZ-1 FOR WINDOW SILL AT LOBBY 001, SEE WALL SECTIONS 2/A401 & 6/A406	012
013	E.M. OPERATIONS	CPT-1	B-1	P-1	D-1	P-2								013
014	FIRE MARSHAL PLAN REVIEW	CPT-1	B-1	P-1	D-1	P-2								014
015	DEPUTY FIRE MARSHAL	CPT-1	B-1	P-1	D-1	P-2								015
016	CORRIDOR	CPT-1	B-1	P-1	D-1	P-2							LV-4 AS ALTERNATE 8	016
017	MEDICAL DIRECTOR	CPT-1	B-1	P-1	D-1	P-2								017
018	CORR.	CPT-1	B-1	P-1	D-1	P-2								018
019	TRAINING OFFICER	CPT-1	B-1	P-1	D-1	P-2								019
020	TRAINING	CPT-1	B-1	P-1	D-1	P-2	P-3			PL-1	PL-2	PL-2	SEE A900'S CASEWORK ELEVATIONS	020
021	SCENARIO TRAINING	VCT-1	B-1	P-1	D-1	P-2								021
022	A.V. CTRL I.T.	VCT-1	B-1	P-1	D-1	P-2								022
023	SCENARIO A.V. CTRL	CPT-1	B-1	P-1	D-1	P-2				PL-1	PL-2	PL-2	SEE A900'S CASEWORK ELEVATIONS	023
024	CORRIDOR	CPT-2	B-1	P-1	D-1	P-2								024
025	SECURE VESTIBULE	CPT-2	B-1	P-1	D-1/P-1	P-2								025
026	LAUNDRY	LV-1	B-1	P-1	D-1	P-2	FRP-1			SSF-1	PL-2	PL-2	SEE A900'S CASEWORK ELEVATIONS, INSTALL FRP HORIZONTALLY ABOVE BASE	026
027	CORRIDOR	CPT-1	B-1	P-1	D-1	P-2							LV-4 AS ALTERNATE 8	027
028	LOCKER ROOM ALCOVE	CPT-1	B-1	P-1	D-1	P-2							LV-4 AS ALTERNATE 8	028
029	WOMEN'S TOILETS	PT-1/PT-2	TR-5, B-3	P-1	D-1	WT-1/P-2*	WT-2			QTZ-1			*EPOXY PAINT, TP-1, WT-1 FULL HEIGHT WET WALL @ TOILETS, SEE FINISH PLAN, ABOVE COUNTER WT-2 BEHIND MIRRORS	029
030	WOMEN'S LOCKERS	PT-1	TR-5, B-3	P-1	D-1	P-4							LCK-1	030
031	WOMEN'S SHOWERS	PT-1/PT-2	TR-5 (3/A700) (TR-10) B-3		-	WT-1/P-2*							3/A700 *EPOXY PAINT, SEE A500'S TOILET ELEVATIONS, CRT-1, TR-10 IN SHOWER,FIRST ROW OF WT-1 4" CONTINUE WT-1 TO CEILING	031
032	MEN'S TOILETS	PT-1/PT-2	TR-5, B-3	P-1	D-1	WT-1/P-2*	WT-2			QTZ-1			*EPOXY PAINT, TP-1, WT-1 FULL HEIGHT WET WALL @ TOILETS, SEE FINISH PLAN, ABOVE COUNTER WT-2 BEHIND MIRRORS	032
033	MEN'S LOCKERS	PT-1	TR-5, B-3	P-1	D-1	P-4								033
034	MEN'S SHOWERS	PT-1/PT-2	TR-5 (3/A700) (TR-10) B-3	-	-	WT-1/P-2*	WT-1						3/A700 *EPOXY PAINT, SEE A500'S TOILET ELEVATIONS, CRT-1, TR-10 IN SHOWER,FIRST ROW OF WT-1 4" CONTINUE WT-1 TO CEILING	034
035	FIRE MARSHAL RECORDS STORAGE	VCT-1	B-1	P-1	D-1	P-2								035
036	DEPUTY FIRE MARSHAL	CPT-1	B-1	P-1	D-1	P-2								036
037	FIRE MARSHAL EVIDENCE STORAGE	VCT-1	B-1	P-1	D-1	P-2								037
038	FIRE MARSHALL/ASST E.M. DIRECTOR	CPT-1	B-1	P-1	D-1	P-2								038
039	E.M. PLANNING	CPT-1	B-1	P-1	D-1	P-2								039
040	WORK ROOM	CPT-1	B-1	P-1	-	P-2				PL-1	PL-2	PL-2	LV-4 AS ALTERNATE 8, SEE A900'S CASEWORK ELEVATIONS	040
041	CORR.	CPT-1	B-1	P-1	D-1	P-2							LV-4 AS ALTERNATE 8	041
042	INFORMATION TECHNOLOGY	SDT-1	B-1	P-1	D-1	P-2								042
043	E.M.SAFETY	CPT-1	B-1	P-1	D-1	P-2								043
044	ELEC.	SC-1	B-1	P-1	D-1	P-2								044
045	MECHANICAL	SC-1	B-1	P-1	D-1	P-2								045
046	CONFERENCE	CPT-1	B-1	P-1	D-1	P-3								046
047	E.M.FINANCE/ LOGISTICS	CPT-1	B-1	P-1	D-1	P-2								047
048	E.M. LIASON	CPT-1	B-1	P-1	D-1	P-2								048
049	AMATEUR RADIO	CPT-1	B-1	P-1	D-1	P-2								049
050	CORRIDOR	CPT-1	B-1	P-1	D-1	P-2							LV-4 AS ALTERNATE 8	050
051	GENERAL STORAGE	VCT-1	B-1	P-1	D-1	P-2								051
052	DRY GOODS STORAGE	VCT-1	B-1	P-1	D-1	P-2								052
053	KITCHEN/BREAKROOM	LV-1	B-1	P-1	D-1/ALUM	P-2	P-4,WT-2			QTZ-2	PL-2	PL-2	WT-2 BACKSPLASH, SEE A900'S CASEWORK ELEVATIONS	053
054	VENDING	CPT-1	B-1	-	-	P-2							LV-4 AS ALTERNATE 8	054
055	STAFF LOBBY	PT-3	B-5	P-1	D-1/ALUM	P-2	P-5						SEE FINISH PLAN FOR ACCENT WALLS	055
056	CORRIDOR	CPT-1	B-1	P-1	D-1	P-2							LV-4 AS ALTERNATE 8	056
057	E.M. EQUIP STORAGE	VCT-1	B-1	P-1	D-1/P-1	P-2								057
058	E.O.C./MULTI-PURPOSE	CPT-1	B-2	P-1	D-1	P-2	P-6	AWP-1		PL-1	PL-2	PL-2	SEE A900'S CASEWORK ELEVATIONS, CPT-3 AS ALTERNATE 6, AWP-1 AS ALTERNATE 9	058
059	E.O.C/ STORAGE	CPT-1	B-1	P-1	D-1	P-2							CPT-3 AS ALTERNATE 6	059
060	DAYROOM	LV-3	B-1	P-1	D-1	P-2	P-3,5			PL-1	PL-2		N-1 AT PLATFORM, SEE 900'S CASEWORK ELEVATIONS	060
061	JANITOR	PT-1	B-6	P-1	D-1	P-2*	FRP-1						*EPOXY PAINT, INSTALL FULL SHEET OF FRP-1 VERTICALLY- 2'-0" EITHER SIDE OF SINK	061
062	CORRIDOR	CPT-1	B-1	P-1	D-1	P-2								062
063	REPORT WRITING	CPT-1	B-1	P-1	D-1	P-2				PL-1	PL-2	PL-2	SEE A900'S CASEWORK ELEVATIONS	063
064	SECURE VESTIBULE	CPT-2	B-1	P-1	D-1/P-1	P-2								064
065	CORR.	CPT-1	B-1	P-1	D-1	P-2								065
066	BEDROOM	CPT-1	B-1	P-1	D-1	P-2								066
067	BEDROOM	CPT-1	B-1	P-1	D-1	P-2								067
068	BEDROOM	CPT-1	B-1	P-1	D-1	P-2								068
069	BEDROOM	CPT-1	B-1	P-1	D-1	P-2								069
070	BEDROOM	CPT-1	B-1	P-1	D-1	P-2								070
071	BEDROOM	CPT-1	B-1	P-1	D-1	P-2								071
072	SHIFT SUP. BEDROOM	CPT-1	B-1	P-1	D-1	P-2								072
073	BEDROOM	CPT-1	B-1	P-1	D-1	P-2								073
074	SHIFT SUPERVISOR	CPT-1	B-1	P-1	D-1	P-2								074
075	BEDROOM	CPT-1	B-1	P-1	D-1	P-2								075
101	SECURE VEST.	CPT-2	B-1	P-1	D-1/P-1	P-2								101
102	CORR.	CPT-1	B-1	P-1	D-1	P-2								102
103	COPIER	CPT-1	B-1	P-1	D-1	P-2								103
104	DEPUTY 911 DIRECTOR	CPT-1	B-1	P-1	D-1	P-2								104
105	911 DIRECTOR	CPT-1	B-1	P-1	D-1	P-2								105
106	CORR.	LV-2	B-1	P-1	ALUM	P-2								106
107	CONFERENCE/SHIFT BRIEFING ROOM	CPT-3	B-1	P-1	D-1	P-2	P-3,5			PL-1	PL-2	PL-2	SEE A900'S CASEWORK ELEVATIONS	107
108	ADDRESSING/QA ASSISTANT	CPT-1	B-1	P-1	D-1	P-2								108
109	CORRIDOR	CPT-1	B-1	P-1	D-1	P-2								109
110	ACCESSIBLE UNISEX SHOWER/TOILET	PT-1/PT-2	TR-5 (3/A700) (TR-10) B-3	P-1	D-1	WT-1				QTZ-1			3/A700 FIRST ROW OF WT-1 TO BE 4" THEN WT-1 FULL HEIGHT, SEE A500'S TOILET ELEVATIONS, CRT-1, TR-10 IN SHOWERS, SSF-1 ON TOP OF BUILTIN BENCH	110
111	UNISEX SHOWER/TOILET	PT-1/PT-2	TR-5 (3/A700) (TR-10) B-3	P-1	D-1	WT-1				QTZ-1			FIRST ROW OF WT-1 TO BE 4" THEN WT-1 FULL HEIGHT, SEE A500'S TOILET ELEVATIONS, CRT-1, TR-10 IN SHOWERS,	111
112	CORR.	LV-2	B-1	P-1	D-1	P-2								112
113	LOCKER ROOM	LV-2	B-1	P-1	-	P-2							LCK-1	113
114	911 DISPATCHING ROOM	CPT-3	B-1	P-1	D-1	P-2								114
115	SHIFT SUPERVISORS OFFICE	CPT-3	B-1	P-1	D-1	P-2								115
116	FILE ROOM	CPT-3	B-1	P-1	D-1	P-2								116
117	CORR.	LV-2	B-1	P-1	D-1	P-2								117
118	911 DISPATCHING TRAINING ROOM	CPT-3	B-1	P-1	D-1	P-2								118
119	PRIVATE ROOM	CPT-1	B-1	P-1	D-1	P-2								119
120	BACK-UP MGR OFFICE	CPT-1	B-1	P-1	D-1	P-2								120
121	JANITOR/STORAGE	PT-1	B-6	P-1	D-1	P-2*	FRP-1						*EPOXY PAINT, INSTALL FULL SHEET OF FRP-1 VERTICALLY- 2'-0" EITHER SIDE OF SINK	121
122	BUNK ROOM A	CPT-1	B-1	P-1	D-1	P-2								122
123	BUNK ROOM B	CPT-1	B-1	P-1	D-1	P-2								123
124	BREAK ROOM	LV-1	B-1	P-1	D-1	P-2	P-4,WT-2			QTZ-2	PL-2	PL-2	WT-2 BACKSPLASH, SEE A900'S CASEWORK ELEVATIONS, SEE FINISH PLAN FOR LOCATION OF ACCENT WALL	124
125	CORR.	CPT-1	B-1	P-1	D-1	P-2								125
126	SECURE VEST.	CPT-2	B-1	P-1	D-1/P-1	P-2								126
127	ELECTRICAL ROOM	SC-1	B-1	P-1	P-1	P-2								127
128	GENERAL STORAGE	VCT-1	B-1	P-1	P-1	P-2								128
129	MECHANICAL ROOM	SDT-1	B-1	P-1	P-1	P-2								129
130	IT/DEMARK ROOM	SDT-1	B-1	P-1	P-1	P-2								130
132	CORR.	CPT-1	B-1	P-1	P-1	P-2								132
133	CORRIDOR	CPT-1	B-1	P-1	D-1	P-2				PL-1	PL-2	PL-2	SEE A900'S CASEWORK ELEVATIONS	133
134	FIRE PROTECTION	SC-1	B-1	P-1	D-1	P-2								134
201	APPARATUS ROOM A	SC-2,SC-3	B-1	P-1	P-1	P-2							EPF-2 & B-7 AS ALTERNATE 6	201
202	WASH STORAGE	SC-1	B-1	P-1	P-1	P-2*	FRP-1						*EPOXY PAINT, INSTALL FULL SHEET OF FRP-1 VERTICALLY- 2'-0" EITHER SIDE OF SINK	202
203	DECONTAMINATION ROOM	EPF-1	B-4, TR-9	P-1	P-1	P-2*	FRP-1						*EPOXY PAINT, FRP-1 SEE A500'S TOILET ELEVATIONS FOR INSTALLATION DIRECTION	203
204	DECON BATH	EPF-1	B-4, TR-9	P-1	P-1	EPW-1	SSF-2						SSF-2 IN SHOWER STALL, SEE A500'S TOILET ELEVATIONS FOR INSTALLATION DIRECTION, CRT-1	204
205	READY STOCK	SC-1	B-1	P-1	P-1	P-2								205
206	EMS WAREHOUSE	SC-1	B-1	P-1	P-1	P-2								206
207	COVERED RESTOCKING BAYS	-	-	P-1	P-1	-								207
208	CORRIDOR	SC-1	B-1	P-1	P-1	P-2								208
209	APPARATUS ROOM B	SC-2,SC-3	B-1	P-1	P-1	P-2							EPF-2 & B-7 AS ALTERNATE 6	209

INTERIOR FINISH CODES

ACT	ACOUSTICAL CEILING TILE	QT	QUARRY
AWC	ACOUSTICAL WALL CARPET	QTZ