GENERAL NOTES:

1. CONTRACTOR SHALL COORDINATE ALL THRESHOLDS, TRANSITIONS, AND FLOOR FINISH HEIGHTS WITH THE HEIGHT OF DOOR BOTTOMS TO PROVIDE NOT LESS THAN 1/8" OR MORE THAN 3/8" CLEARANCE. EXCEPT DOORS TO BE UNDERCUT FOR MECHANICAL EXHAUST PURPOSES SHALL HAVE 3/4" CLEARANCE.
2. ALL HOLLOW METAL DOOR FRAMES SHALL CONFORM TO TOLERANCES PER SDI-117 AND SDI-250 FOR SQUARENESS, PLUMBNESS, ALIGNMENT, AND TWIST. ALL FRAMES SHALL BE VERTICALLY PLUMB TO WITHIN 1/16"

DOOR SCHEDULE REMARKS:

A	PROVIDE PANIC DEVICE
B	PROVIDE ALUMINUM THRESHOLD
C	NOT USED
D	PROVIDE J-BOX AND CONDUIT FOR CARD READER
E	PROVIDE J-BOX AND CONDUIT FOR CARD READER WITH KEYPAD
F	UNEVEN DOOR PAIR
G	PROVIDE DOOR POSITION SWITCH
H	SLIDING GLASS DOOR - ONE PANEL OPERABLE
J	PROVIDE EXIT DEVICE KIT - SEE DETAIL 02/A002
K	LEVEL III BULLET RESISTING DOOR AND FRAME

GLAZING SCHEDULE:

G-1	1/4" TEMPERED FLOAT GLASS
G-2	FIRE-RATED AND SAFETY-RATED GLASS
G-3	1" TEMPERED INSULATING LOW-E GLASS
G-4	FACTORY STANDARD TEMPERED GLASS WITH INTERNAL BLIND SYSTEM
G-5	LEVEL III BULLET RESISTING GLASS CLAD POLYCARBONATE

ABBREVIATIONS:

ALUM	ALUMINUM STOREFRONT/CURTAIN WALL
BR	BULLET RESISTANT
HM	HOLLOW METAL
IHM	INSULATED HOLLOW METAL
ISTL	INSULATED STEEL
GL	GLASS
SCW	SOLID CORE WOOD
STL	STEEL
G-	GLASS TYPE
H-	DOOR HEAD TYPE
J-	DOOR JAMB TYPE
PR	PAIR

GENERAL NOTES

SCALE: NTS 4

FRAME TYPES

SCALE: 1/4" = 1'-0" 3

DOOR TYPES

SCALE: 1/4" = 1'-0" 2

DOOR, FRAME, AND HARDWARE SCHEDULE

DOOR NUMBER	ROOM NAME	DOOR SIZE WIDTH	DOOR SIZE HEIGHT	DOOR SIZE THICK	DOOR TYPE	DOOR MAT	DOOR GLAZ	HDW SET	FRAME MAT	FRAME TYPE	FRAME GLAZ	FRAME SILL	FRAME JAMB	FRAME HEAD	REMARKS	FIRE LABEL
001	LOBBY	3'-6"	7'-0"	1 3/4"	1	ALUM	G-3	1.0	ALUM	A/A601	G-3	YES	J1	H1	A,B,E	
002	STORAGE	3'-0"	7'-0"	1 3/4"	3	SCW		30.0	HM	A			J2	H2		
003	PUBLIC TOILET	3'-0"	7'-0"	1 3/4"	3	SCW		18.0	HM	A			J2	H2		
004	CORRIDOR	3'-0"	7'-0"	1 3/4"	4	HM	G-5	5.0	HM	A			J2	H2	A,D,K	
005	WORK ALCOVE	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	22.0	HM	A			J2	H2		
006	ADMINISTRATIVE ASSISTANT	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
008	E.M. DIRECTOR	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
009	E.M.S. OPERATIONS CHIEF	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
010	STORAGE	3'-0"	7'-0"	1 3/4"	3	SCW		29.0	HM	A			J2	H2		
011A	CONFERENCE	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	23.0	HM	A			J2	H2		
011B	CONFERENCE	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	22.0	HM	A			J2	H2		
012	ADMINISTRATIVE ASSISTANT	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
013	E.M. OPERATONS	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
014	DEPUTY FIRE MARSHAL	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
015	FIRE MARSHALL PLAN REVIEW	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	22.0	HM	A			J2	H2		
017	MEDICAL DIRECTOR	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
018	CORRIDOR	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	5.0	HM	A			J2	H2	A,D	
019	TRAINING OFFICER	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
020A	TRAINING	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	10.0	HM	A			J2	H2	A	
020B	TRAINING	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	10.0	HM	A			J2	H2	A	
021	SCENARIO TRAINING	3'-0"	7'-0"	1 3/4"	3	SCW		22.0	HM	A			J2	H2		
022	A.V. CONTROL I.T.	PR 3'-0"	7'-0"	1 3/4"	3	SCW		32.0	HM	D			J2	H2		
023	SCENARIO A.V. CONTROL	3'-0"	7'-0"	1 3/4"	3	SCW		23.0	HM	A			J2	H2		
024A	CORRIDOR	3'-0"	7'-0"	1 3/4"	4	SCW	G-2	9.0	HM	A			J2	H2	A	1/3 HR
024B	CORRIDOR	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	5.0	HM	A			J2	H2	A,D	
025A	SECURE VESTIBULE	3'-0"	7'-0"	1 3/4"	3	SCW		5.0	HM	A			J2	H2	A,D	
025B	SECURE VESTIBULE	3'-0"	7'-0"	1 3/4"	2	IHM		3.0	HM	B		YES	J4	H4	A,B,D	1 1/2 HR
026	LAUNDRY	3'-0"	7'-0"	1 3/4"	3	SCW		25.0	HM	A			J2	H2		1/3 HR
029	WOMEN'S TOILETS	3'-0"	7'-0"	1 3/4"	3	SCW		15.0	HM	A			J2	H2		
030	WOMEN'S LOCKERS	3'-0"	7'-0"	1 3/4"	3	SCW		15.0	HM	A			J2	H2		
032	MEN'S TOILETS	3'-0"	7'-0"	1 3/4"	3	SCW		15.0	HM	A			J2	H2		
033	MEN'S LOCKERS	3'-0"	7'-0"	1 3/4"	3	SCW		15.0	HM	A			J2	H2		
035	FIRE MARSHAL RECORDS STOR.	3'-0"	7'-0"	1 3/4"	3	SCW		31.0	HM	A			J2	H2		
036	DEPUTY FIRE MARSHAL	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
037	FIRE MARSHAL EVIDENCE STOR.	3'-0"	7'-0"	1 3/4"	3	SCW		30.0	HM	A			J2	H2		
038	FIRE MARSHAL/ASST E.M. DIRECTOR	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
039	E.M. PLANNING	3'-0"	7'-0"	1 3/4"	3	SCW		22.0	HM	A			J2	H2		
041	CORRIDOR	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	5.0	HM	A			J2	H2	A,D	
042	INFORMATION TECHNOLOGY	3'-0"	7'-0"	1 3/4"	3	SCW		30.0	HM	A			J2	H2		
043	E.M. SAFETY	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
044	ELECTRICAL	3'-6"	7'-0"	1 3/4"	3	SCW		30.0	HM	A			J2	H2		
045	MECHANICAL	3'-6"	7'-0"	1 3/4"	3	SCW		30.0	HM	A			J2	H2		
046A	CONFERENCE	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	22.0	HM	A			J2	H2		
046B	CONFERENCE	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	12.0	HM	A			J2	H2	D	
047	E.M. FINANCE/LOGISTICS	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
048	E.M. LIASON	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
049	AMATEUR RADIO	3'-0"	7'-0"	1 3/4"	3	SCW		25.0	HM	A			J2	H2		
050	CORRIDOR	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	5.0	HM	A			J2	H2	A,D	
051	GENERAL STORAGE	3'-0"	7'-0"	1 3/4"	3	SCW		30.0	HM	A			J2	H2		
052	DRY GOODS STORAGE	3'-0"	7'-0"	1 3/4"	3	SCW		22.0	HM	A			J2	H2		
053A	KITCHEN/BREAK ROOM	3'-6"	7'-0"	1 3/4"	4	SCW		26.0	HM	A			J2	H2		
053B	KITCHEN/BREAK ROOM	3'-6"	7'-0"	1 3/4"	1	ALUM	G-3	1.0	ALUM	G/A601	G-3	YES	J1	H1	A,B,D	
055A	STAFF LOBBY	3'-0"	7'-0"	1 3/4"	3	SCW		11.0	HM	A			J3	H3	A,D	
055B	STAFF LOBBY	3'-6"	7'-0"	1 3/4"	1	ALUM	G-3	1.0	ALUM	F/A601	G-3	YES	J1	H1	A,B,D	
057A	E.M. EQUIPMENT STORAGE	3'-6"	7'-0"	1 3/4"	3	SCW		30.0	HM	A			J2	H2		
057B	E.M. EQUIPMENT STORAGE	PR 3'-0"	7'-0"	1 3/4"	2	IHM		33.0	HM	E		YES	J3	H3	B,G	
058A	E.O.C./MULTI-PURPOSE	3'-6"	7'-0"	1 3/4"	4	SCW	G-1	10.0	HM	A			J2	H2	A	
058B	E.O.C./MULTI-PURPOSE	3'-6"	7'-0"	1 3/4"	4	SCW	G-1	10.0	HM	A			J2	H2	A	
059	E.O.C. STORAGE	PR 3'-0"	7'-0"	1 3/4"	3	SCW		32.0	HM	D			J2	H2		
060A	DAYROOM	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	25.0	HM	A			J2	H2		
060B	DAYROOM	3'-0"	7'-0"	1 3/4"	3	SCW		13.0	HM	A			J2	H2	D	1/3 HR
061	JANITOR	3'-0"	7'-0"	1 3/4"	3	SCW		30.0	HM	A			J2	H2		
062A	CORRIDOR	3'-0"	7'-0"	1 3/4"	4	SCW	G-2	9.0	HM	A			J2	H2	A	1/3 HR
062B	CORRIDOR	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	5.0	HM	A			J2	H2	A,D	
063	REPORT WRITING	3'-0"	7'-0"	1 3/4"	3	SCW		21.0	HM	A			J2	H2		1/3 HR
064A	SECURE VESTIBULE	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	5.0	HM	A			J2	H2	A,D	
064B	SECURE VESTIBULE	3'-0"	7'-0"	1 3/4"	2	IHM		3.0	HM	B		YES	J4	H4	A,B,D	1 1/2 HR
066	BEDROOM	3'-0"	7'-0"	1 3/4"	3	SCW		17.0	HM	A			J2	H2		
067	BEDROOM	3'-0"	7'-0"	1 3/4"	3	SCW		17.0	HM	A			J2	H2		
068	BEDROOM	3'-0"	7'-0"	1 3/4"	3	SCW		17.0	HM	A			J2	H2		
069	BEDROOM	3'-0"	7'-0"	1 3/4"	3	SCW		17.0	HM	A			J2	H2		
070	BEDROOM	3'-0"	7'-0"	1 3/4"	3	SCW		17.0	HM	A			J2	H2		
071	BEDROOM	3'-0"	7'-0"	1 3/4"	3	SCW		17.0	HM	A			J2	H2		
072	SHIFT SUPERVISOR'S BEDROOM	3'-0"	7'-0"	1 3/4"	3	SCW		17.0	HM	A			J2	H2		
073	BEDROOM	3'-0"	7'-0"	1 3/4"	3	SCW		17.0	HM	A			J2	H2		
074A	SHIFT SUPERVISOR	3'-0"	7'-0"	1 3/4"	3	SCW		21.0	HM	A			J2	H2		1/3 HR
074B	SHIFT SUPERVISOR	3'-0"	7'-0"	1 3/4"	3	SCW		21.0	HM	A			J2	H2		
075	BEDROOM	3'-0"	7'-0"	1 3/4"	3	SCW		17.0	HM	A			J2	H2		
101	SECURE VESTIBULE	3'-0"	7'-0"	1 3/4"	2	HM		11.0	HM	B			J5	H5	A,D	1 HR
102	CORRIDOR	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	5.0	HM	A			J2	H2	A,D	
104	DEPUTY 911 DIRECTOR	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
105	911 DIRECTOR	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
106	CORRIDOR	3'-0"	7'-0"	1 3/4"	1	ALUM	G-1	12.0	ALUM	J/A601	G-1		J1	H1	D	
107A	CONFERENCE/SHIFT BRIEFING RM.	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	12.0	HM	A			J2	H2	D	
107B	CONFERENCE/SHIFT BRIEFING RM.	6'-0"	7'-0"	1 1/4"	K/A601	ALUM	G-4		ALUM	K/A601	G-4				H	
108	ADDRESSING/ Q.A. ASSISTANT	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
110	ACCESSIBLE UNISEX SHOWER/TLT	3'-0"	7'-0"	1 3/4"	3	SCW		19.0	HM	A			J2	H2		
111	UNISEX SHOWER/TOILET	3'-0"	7'-0"	1 3/4"	3	SCW		18.0	HM	A			J2	H2		
112	CORRIDOR	3'-0"	7'-0"	1 3/4"	1	ALUM	G-1	14.0	ALUM	L/A601	G-1		J1	H1	D	
115	SHIFT SUPERVISORS' OFFICE	3'-0"	7'-0"	1 3/4"	1	ALUM	G-1	20.0	ALUM	M/A601	G-1		J1	H1		
116	FILE ROOM	3'-0"	7'-0"	1 3/4"	3	SCW		23.0	HM	A			J2	H2		
117	CORRIDOR	3'-0"	7'-0"	1 3/4"	1	ALUM	G-1	12.0	ALUM	N/A601	G-1		J1	H1	D	
118A	911 DISP. TRAINING ROOM	3'-0"	7'-0"	1 3/4"	3	SCW		5.0	HM	A			J2	H2	A,D	
118B	911 DISP. TRAINING ROOM	3'-0"	7'-0"	1 3/4"	1	ALUM	G-1	27.0	ALUM	O/A601	G-1		J1	H1		
119	PRIVATE ROOM	3'-0"	7'-0"	1 3/4"	3	SCW		22.0	HM	A			J2	H2		
120	BACK-UP MANAGER'S OFFICE	3'-0"	7'-0"	1 3/4"	3	SCW		20.0	HM	A			J2	H2		
121	JANITOR/STORAGE	3'-0"	7'-0"	1 3/4"	3	SCW		30.0	HM	A			J2	H2		
122	BUNK ROOM A	3'-0"	7'-0"	1 3/4"	3	SCW		16.0	HM	A			J2	H2		1/3 HR
123	BUNK ROOM B	3'-0"	7'-0"	1 3/4"	3	SCW		16.0	HM	A			J2	H2		1/3 HR
124	BREAK ROOM	3'-0"	7'-0"	1 3/4"	4	SCW	G-1	22.0	HM	A			J2	H2		
125	CORRIDOR	3'-6"	7'-0"	1 3/4"	3	SCW		5.0	HM	A			J2	H2	A,D	
126	SECURE VESTIBULE	3'-8"	7'-0"	1 3/4"	2	IHM		3.0	HM	B		YES	J5	H5	A,B,D	1 HR
127	ELECTRICAL ROOM	2'-8", 3'-0"	7'-0"	1 3/4"	2	IHM		33.1	HM	E		YES	J6	H6	A,B,F,G	1 HR
128	GENERAL STORAGE	3'-6"	7'-0"	1 3/4"	2	SCW		30.0	HM	A			J2	H2		
129	MECHANICAL ROOM	3'-8"	7'-0"	1 3/4"	2	IHM		28.1	HM	B		YES	J6	H6	B,G	1 HR
130	IT/DEMARK ROOM	3'-6"	7'-0"	1 3/4"	2	HM		13.0	HM	A			J2	H2	E	1 1/2 HR
134	FIRE PROTECTION ROOM	3'-0"	7'-0"	1 3/4"	2	IHM		28.1	HM	B		YES	J5	H5	B,G	1 HR
201A	APPARATUS ROOM A	14'-0"	14'-0"	-	5	ALUM/GL	G-3	34.0	STEEL	-			3/A151	2/A411		
201B	APPARATUS ROOM A	14'-0"	14'-0"	-	5	ALUM/GL	G-3	34.0	STEEL	-			3/A151	2/A411		
201C	APPARATUS ROOM A	14'-0"	14'-0"	-	5	ALUM/GL	G-3	34.0	STEEL	-			3/A151	2/A411		
201D	APPARATUS ROOM A	3'-0"	7'-0"	1 3/4"	2	IHM		3.0	HM	B		YES	J5 SIM	H5 SIM	A,B,D	
201E	APPARATUS ROOM A	14'-0"	14'-0"	-	5	ALUM/GL	G-3	34.0	STEEL	-			3/A151	2/A411		
201F	APPARATUS ROOM A	14'-0"	14'-0"	-	5	ALUM/GL	G-3	34.0	STEEL	-			3/A151	2/A411		
201G	APPARATUS ROOM A	14'-0"	14'-0"	-	5	ALUM/GL	G-3	34.0	STEEL	-			3/A151	2/A411		
201H	APPARATUS ROOM A	3'-0"	7'-0"	1 3/4"	2	IHM		3.0	HM	B		YES	J5 SIM	H5 SIM	A,B,D	
202	WASH STORAGE	3'-0"	7'-0"	1 3/4"	2	HM		30.0	HM	B			J7 SIM	H7 SIM		
203	DECONTAMINATION ROOM	3'-0"	7'-0"	1 3/4"	2	IHM		28.0	HM	B		YES	J7	H7	B	
204	DECONTAMINATION BATHROOM	3'-0"	7'-0"	1 3/4"	2	HM		17.0	HM	B			J8	H8		
205A	READY STORAGE	3'-0"	7'-0"	1 3/4"	2	HM		12.1	HM	B			J8	H8	D	
205B	READY STORAGE	3'-0"	7'-0"	1 3/4"	2	HM		12.0	HM	B			J8	H8	D	
206A	E.M.S. WAREHOUSE	3'-0"	7'-0"	1 3/4"	2	HM		12.1	HM	B			J8	H8	D	
206B	E.M.S. WAREHOUSE	8'-0"	8'-0"	-	6	ISTL		34.0	STEEL	-			J9	H9	G	
207A	COVERED RESTOCKING BAYS	3'-0"	7'-0"	1 3/4"	2	IHM		3.0	HM	B		YES	J5 SIM	H5 SIM	A,B,D	
207B	COVERED RESTOCKING BAYS	3'-0"	7'-0"	1 3/4"	2	IHM		3.0	HM	B		YES	J5 SIM	H5 SIM	A,B,D	
208A	CORRIDOR	PR 3'-0"	7'-0"	1 3/4"	2	IHM		7.0	HM	E		YES	J7	H7	A,B	
208B	CORRIDOR	PR 3'-0"	7'-0"	1 3/4"	2	IHM		7.0	HM	E		YES	J7	H7	A,B	
209A	APPARATUS ROOM B	14'-0"	14'-0"	-	5	ALUM/GL	G-3	34.0	STEEL	-			3/A151	2/A411		
209B	APPARATUS ROOM B	14'-0"	14'-0"	-	5	ALUM/GL	G-3	34.0	STEEL	-			3/A151	2/A411		
209C	APPARATUS ROOM B	14'-0"	14'-0"	-	5	ALUM/GL	G-3	34.0	STEEL	-			3/A151	2/A411		
209D	APPARATUS ROOM B	3'-0"	7'-0"	1 3/4"	2	IHM		3.0	HM	B		YES	J5 SIM	H5 SIM	A,B,D	
209F	APPARATUS ROOM B	14'-0"	14'-0"	-	5	ALUM/GL	G-3	34.0	STEEL	-			3/A151	2/A411		
209G	APPARATUS ROOM B	14'-0"	14'-0"	-	5	ALUM/GL	G-3	34.0	STEEL	-			3/A151	2/A411		
209H	APPARATUS ROOM B	14'-0"	14'-0"	-	5	ALUM/GL	G-3	34.0	STEEL	-			3/A151	2/A411		
209I	APPARATUS ROOM B	3'-0"	7'-0"	1 3/4"	2	IHM		3.0	HM	B		YES	J5 SIM	H5 SIM	A,B,D	
301A	DUMPSTER ENCLOSURE	PR 5'-0"	8'-0"	-	7	STL		34.0	STL	-						
301B	DUMPSTER ENCLOSURE	PR 5'-0"	8'-0"	-	7	STL		34.0	STL	-						
401A	MECHANICAL YARD	4'-0"	7'-0"			CHAIN LINK									J	
401B	MECHANICAL YARD	4'-0"	7'-0"			CHAIN LINK									J	

REV 5

DOOR, FRAME, AND HARDWARE SCHEDULE

SCALE: NTS 1

adwarchitects
environmentsforlife
architecture planning interiors

six coliseum centre
2815 coliseum centre drive, suite 500
charlotte, north carolina 28217
t| 704 379 1919
f| 704 379 1920
www.adwarchitects.com

SAMPSON COUNTY, N.C. EST. 1784 MANUFACTURING FORK AGRICULTURE

SAMPSON COUNTY 911 & ES FACILITIES

CLINTON, NORTH CAROLINA

CONSTRUCTION DOCUMENTS

DOOR, FRAME, AND HARDWARE SCHEDULES & DETAILS

DATE	12.04.2020
PROJECT NO	20003

REVISIONS

NUM.	DATE	DESCRIPTION:
REV2	01/09/21	REV2/ADD1
REV5	01/22/21	REV5/ADD4

REV 2 GENERAL COORDINATION

THIS DRAWING IS THE PROPERTY OF ADW ARCHITECTS, P.A. AND SHALL NOT BE REPRODUCED OR COPIED IN WHOLE OR IN PART. IT SHALL NOT BE USED ON ANY OTHER PROJECT OR GIVEN TO ANY OTHER COMPANY OR AGENCY WITHOUT THE CONSENT OF ADW ARCHITECTS, P.A.

1-22-21

SEAL

SHEET NUMBER A600