



THIS DRAWING IS THE PROPERTY OF SCHNEIDER ELECTRIC AND SUBJECT TO RETURN UPON REQUEST. IT IS NOT TO BE COPIED OR REPRODUCED, NOR IS IT TO BE USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT WAS FURNISHED, WITHOUT THE WRITTEN CONSENT OF SCHNEIDER ELECTRIC.



- DEMOLITION NOTES**
- D1 REMOVE HORIZONTAL, CEILING MOUNTED CLASSROOM VENTILATOR COMPLETE INCLUDING CHILLED WATER AND HOT WATER RUNOUTS, POWER (SEE ELECTRICAL) TEMPERATURE CONTROLS AND HANGER SUPPORTS. REMOVE AND STORE BI-POLAR IONIZATION KITS, AND RE-USE IN NEW UNIT VENTILATORS. REMOVE CONDENSATE PIPING COMPLETE INCLUDING INLET PIPING AND POWER (SEE ELECTRICAL). REPAIR OR REPLACE MOUNTING AS REQUIRED.
  - D2 REMOVE OUTSIDE AIR SUPPLY DUCT INDICATED BY HATCHING COMPLETE INCLUDING ASSOCIATED HANGER SUPPORTS.
  - D3 REMOVE INLINE OUTSIDE AIR SUPPLY FAN COMPLETE INCLUDING SUPPLY AIR DUCT NECESSARY FOR INSTALLATION OF NEW DOAS UNIT, POWER (SEE ELECTRICAL) CONTROLS AND HANGER SUPPORTS.
  - D4 REMOVE CH6, CHR, HUS, AND HUR PIPING ABOVE CEILING AS NECESSARY TO REPLACE WITH NEW CH6, CHR, HUS, AND HUR PIPING WITH SIZES AS NOTED. INSULATE NEW CH6, CHR, HUS, AND HUR PIPES AND REPAIR ALL DAMAGED INSULATION ON EXISTING PIPES AT
  - D5 REMOVE TRUNK DUCT INDICATED BY HATCHING AS REQUIRED FOR INSTALLATION OF NEW DOAS UNIT. REMOVAL SHALL INCLUDE DUCT HANGERS AND SUPPORTS.




**SECTION THRU MAIN CORRIDOR / CLASSROOM**  
SCALE: 1/4" = 1'-0" APPLIES TO SHEETS M101 AND M102

**FIRE & SMOKE WALL INDICATIONS**

- EXISTING ONE HOUR WALL
- EXISTING SMOKE PARTITION SEALED TO DECK

**NOTES:**

- 1 FIELD VERIFY RATED FLOOR AND WALL ASSEMBLY TYPES AND LOCATIONS.
- 2 SEAL ALL DUCT AND PIPE PENETRATIONS THROUGH SMOKE RATED WALL ASSEMBLIES WITH ANGLE AND CAULK.
- 3 PROVIDE UL RATED ASSEMBLIES ON ALL DUCT AND PIPE PENETRATIONS THROUGH RATED WALL ASSEMBLIES.



**KEY PLAN**  
NO SCALE

**HVAC RENOVATION FLOOR PLAN - AREA 'A'**  
SCALE: 1/8" = 1'-0"

**SCHNEIDER ELECTRIC ENERGY SERVICES PROJECT**  
**FOR**  
**BRUNSWICK COUNTY SCHOOL DISTRICT**  
**SOUTH BRUNSWICK HIGH SCHOOL**  
**280 COUGAR ROAD**  
**SOUTHPORT, NC 28461**

**SHEET TITLE**  
**PARTIAL HVAC FLOOR PLAN**  
**AREA 'A' - ECM-3-1A**

		DESCRIPTION	
		SUBMISSION / REVISION	
		DATE	
		MARK	
DRAWN BY: DJ		CHECKED BY: CDW	
DESIGNED BY: DJ		APPROVED BY: CDW	
DATE: 03-23-22		PROJECT: PC21P0006	
SHEET NUMBER			
M101			
SHT. OF			

**Schneider Electric**  
Tel: +1 972 223 1111  
Fax: +1 972 223 1112  
www.schneider-electric.com  
Schneider Electric  
13998  
03-23-22  
ENGINEER  
DRAWN BY: WJL

SHEET TITLE

PARTIAL HVAC FLOOR PLAN  
AREA 'B' - ECM-3-1A

[illegible]


SHT. OF

- 21 REMOVE HORIZONTAL, CEILING MOUNTED CLASSROOM VENTILATOR COMPLETE INCLUDING CHILLED WATER AND HOT WATER RUNOUTS, FOUER (SEE ELECTRICAL), TEMPERATURE CONTROLS AND HANGER SUPPORTS. REMOVE REFRIGERANT FROM INSULATION OF NEW DOWS UNIT, RE-USE IN NEW UNIT VENTILATORS. REMOVE CONDENSATE PUMPS COMPLETE INCLUDING INLET PIPING AND FOUER (SEE ELECTRICAL). REPAIR OR REPLACE MOUNTING AS REQUIRED.
- 22 REMOVE OUTSIDE AIR SUPPLY DUCT INDICATED BY HATCHING COMPLETE INCLUDING DISCONNECTS, HANGERS AND SUPPORTS.
- 23 REMOVE INLINE OUTSIDE AIR SUPPLY FAN COMPLETE INCLUDING SUPPORTS, HANGERS AND INSULATION. REPAIR OR REPLACE NEW DOWS UNIT, FOUER (SEE ELECTRICAL), CONTROLS AND HANGER SUPPORTS.
- 24 REMOVE CHS, CHR, HUS, AND HUR PIPING ABOVE CEILING AS NECESSARY TO REPLACE WITH NEW CHS, CHR, HUS, AND HUR PIPING WITH SIZES AS NOTED. INSULATE NEW CHS, CHR, HUS, AND HUR PIPES AND REPAIR ALL DAMAGED INSULATION ON EXISTING PIPES AT
- 25 REMOVE TRUNK DUCT INDICATED BY HATCHING AS REQUIRED FOR EXISTING TRUNK DUCT UNIT. REMOVAL SHALL INCLUDE DUCT HANGERS AND SUPPORTS.

EXISTING ONE HOUR WALL

EXISTING SMOKE PARTITION  
SEALED TO DECK


- ① FIELD VERIFY RATED FLOOR AND WALL ASSEMBLY TYPES AND LOCATIONS.
- ② SEAL ALL DUCT AND PIPE PENETRATIONS THROUGH SMOKE RATED WALL ASSEMBLIES WITH ANGLE AND CAULK.
- ③ PROVIDE UL RATED ASSEMBLIES ON ALL DUCT AND PIPE PENETRATIONS THROUGH RATED WALL ASSEMBLIES.



KEY PLAN

---

NO SCALE



CEILING NOTE:  
CONTRACTOR SHALL ASSUME NEW UNIT VENTILATORS ARE SMALLER THAN  
REMOVED UNIT VENTILATORS. PROVIDE FILLER GRID AND TILE AROUND  
NEW UNITS AS REQUIRED. TYPICAL FOR ALL NEW UNIT VENTILATORS

 HYAC RENOVATION FLOOR PLAN - AREA 'B'  
SCALE: 1/8" = 1'-0"

THIS DRAWING IS THE PROPERTY OF SCHNEIDER ELECTRIC AND SUBJECT TO RETURN UPON REQUEST. IT IS NOT TO BE COPIED OR REPRODUCED, NOR IS IT TO BE USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT WAS FURNISHED, WITHOUT THE WRITTEN CONSENT OF SCHNEIDER ELECTRIC




THIS DRAWING IS THE PROPERTY OF SCHNEIDER ELECTRIC AND SUBJECT TO RETURN UPON REQUEST. IT IS NOT TO BE COPIED OR REPRODUCED, NOR IS IT TO BE USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT WAS FURNISHED, WITHOUT THE WRITTEN CONSENT OF SCHNEIDER ELECTRIC.

DEDICATED OUTSIDE AIR HANDLING UNIT SCHEDULE ① ②

MARK	AACH MODEL ①	MAXIMUM DIMENSIONS			SUPPLY FAN ③			EXHAUST FAN ③			ENTHALPY WHEEL, SUMMER										ENTHALPY WHEEL, WINTER										HOT WATER HEAT COIL ④								
											SUPPLY					EXHAUST					DEHUMIDIFICATION COIL ④																		
		LENGTH	WIDTH	HEIGHT	CFM	E.S.P.	FAN HP	CFM	E.S.P.	FAN HP	ENT. AIR (A) FDB FUB	LVG. AIR (B) FDB FUB	ENT. AIR (F) FDB FUB	LVG. AIR (G) FDB FUB	TOTAL MBH	SENS. MBH	ENT. AIR (B) FDB FUB	LVG. AIR (C) FDB FUB	EUT °F	LUT °F	GPM	WATER P.D.	ENT. AIR (A) FDB	LVG. AIR (E) FDB	ENT. AIR (F) FDB	LVG. AIR (G) FDB	MBH	ENT. AIR (E) FDB	LVG. AIR (D) FDB	EUT °F	LUT °F	GPM	WATER P.D.						
DOAS-A-1 ⑤	H3-BRB-3-0-26HA	142"	44"	23"	1175	1.0"	2.3 ④	1000	1.0"	11 ④	93.5	11.9	80.1	67.9	75	62	89.1	74.8	50.5	33.5	80.1	67.9	54.5	54.3	45	55.5	7.5	5.4 FT	24.1	54.1	70	33.1	58.1	54.1	100	100	16.4	7.6	11 FT.
DOAS-B-2 ⑤	H3-CRB-3-0-26HC	172"	62"	21"	1350	1.0"	2.3 ④	1800	1.0"	23.4 ④	93.5	11.9	80.3	67.5	75	62	89.0	74.2	79.3	54.2	80.3	67.5	54.1	54.6	45	55	8.5	5.4 FT	24.1	55.8	70	35.5	79.9	55.8	101	100	15.5	8.0	11 FT.
DOAS-B-3 ⑤	H3-CRB-3-0-26HC	172"	62"	21"	2050	1.0"	2.3 ④	1800	1.0"	23.4 ④	93.5	11.9	80.8	68.0	75	62	89.1	74.3	83.4	58.3	80.8	68.0	54.6	54.5	45	55	11.1	3.1 FT	24.1	54.5	70	35.3	79.9	54.5	95.7	100	15.5	8.0	10 FT.

- ① OR EQUAL BY VALENT, SEMCO OR APPROVED EQUAL. FLAT FILTER SECTION W/ 2" MERV 8 FLEAT THROUGHWAY FILTERS, ENTHALPY WHEEL, CHILLED WATER DEHUMIDIFICATION COIL, AND HOT WATER HEAT COIL AND ACCESS SECTIONS. PROVIDE UNIT WITH INTERVAL VIBRATION ISOLATORS. ② ④ ⑤ ⑥ ① ⑧
- ② UNITS TO MATCH AVAILABLE ELECTRICAL SERVICE, SEE ELECTRICAL.
- ③ MAX. FACE VELOCITY FOR ALL COILS SHALL BE 500 FPM MAX. ALL COILS SHALL HAVE EQUAL FACE AREAS. ALL COIL SECTIONS SHALL HAVE REMOVABLE ACCESS PANELS. ALL COIL SECTIONS SHALL HAVE REMOVABLE ACCESS PANELS.
- ④ ALL FANS SHALL HAVE ECM MOTORS.
- ⑤ UNIT SHALL BE LOW PROFILE, CONCEALED ABOVE THE CEILING. MAXIMUM DIMENSIONS SHALL BE EXCEED THOSE LISTED.
- ⑥ UNIT SHALL BE HORIZONTAL FLOOR MOUNTED WITH VERTICAL R.A. INLET AND VERTICAL S.A. OUTLET.
- ⑦ PROVIDE DOAS UNITS WITH CONTROLS TERMINAL STRIP. SCHEIDER ELECTRIC TO TAKE FULL CONTROL OF DOAS UNITS AND COMMUNICATION WITH BAS.
- ⑧ ALL COOLING COILS SHALL HAVE 2-WAY PRESS. INDEPENDENT CONTROL VALVES WITH UNIONS, 2-WAY CONTROL VALVES WITH AUTO-FLOW CONTROL VALVES FOR HEATING COILS, STAINLESS STEEL DRAIN PANS, AND UNION CONNECTIONS TO COILS. SEE WATER PIPING DIAGRAM ON P102. SCHEIDER ELECTRIC TO FURNISH CONTROL VALVES, THIS CONTRACTOR SHALL INSTALL THEM IN PIPING RUNOUTS.



GRILLE AND DIFFUSER SCHEDULE

MARK	SERVICE	NECK SIZE	MAX CFM	RUNOUT SIZE	REMARKS
②	SUPPLY	8" DIA.	230	8" DIA.	W/ BUTTERFLY DAMPER
⑧	RET./EXH.	8"x8"	230	8"x8"	W/ OFF. BLADE DAMPER **
⑩	RET./EXH.	10"x10"	350	10"x8"	W/ OFF. BLADE DAMPER **
⑫	RET./EXH.	12"x12"	500	12"x10"	W/ OFF. BLADE DAMPER **
⑬	RET./EXH.	16"x16"	700	16"x10"	W/ OFF. BLADE DAMPER **
⑫	RET./EXH.	22"x22"	1500	22"x16"	W/ OFF. BLADE DAMPER **
⑬	EXISTING GRILLE OR DIFFUSER, BALANCE TO CFM NOTED				
GRILLE/ DIFFUSER	CEILING TYPE	MANUF.	MODEL	MATERIAL	
SQUARE SUPPLY	LAY-IN	PRICE #	ASPD-31 (T-BAR)	STEEL	
SQUARE SUPPLY	GYP. BD.	PRICE #	ASPD-31 (SURFACE MOUNT)	STEEL	
SQUARE RET./EXH.	LAY-IN	PRICE #	8IDAL (1/2"x1/2"x1") T-BAR	ALUMINUM	
SQUARE RET./EXH.	GYP. BD.	PRICE #	8IDAL (1/2"x1/2"x1") ALUM. FR.	ALUMINUM	
* OR EQUAL BY CARNES, METALAIR, NAILOR, KREUGER OR APPROVED EQUAL ** OFF. BLADE DAMPERS MAY BE OMITTED FOR TRANSFER AIR GRILLES.					
NOTES: 1. GRILLE AND DIFFUSER LOCATIONS SHOWN ON FLOOR PLANS ARE APPROXIMATE, SEE EXISTING CONDITIONS FOR EXACT LOCATION.					
2. GRILLES AND DIFFUSERS SHALL MATCH CEILING TYPE, VERIFY CEILING TYPE IN FIELD.					
3. GRILLE AND DIFFUSER COLORS SHALL BE SELECTED PROJECT MANAGER.					
4. LAY-IN EGGRATE SHALL HAVE FULL FACE (24"x24") AND FULL SIZE STEEL BACK PLATE WITH DUCT CONNECTION COLLAR. INTERIOR OF GRILLES SHALL BE FLAT BLACK.					
5. PROVIDE 2" THICK BACK PAN INSULATION, 36"x36" FOR ALL SUPPLY AIR DIFFUSERS.					

UNIT VENTILATOR SCHEDULE ② ④ ⑤ ⑥ ① ⑧

MARK	TRANE MODEL ①	CFM	FAN ③ WATTS	COOLING COIL							HEATING COIL								
				TOTAL MBH	SENS. MBH	ENT. AIR	EWT °F	LWT °F	GPM	WATER P.D. (FT)	RUNOUT SIZE	CAPACITY	ENT. AIR	LVG. AIR	EWT °F	LWT °F	GPM	WATER P.D. (FT)	RUNOUT SIZE
AREA 'A'																			
UV-106-25	HUVC1000	805	180	19.5	16.6	75/63	45	51	3.3	2.0	--	35.1	68	103	180	160	3.6	2.0	--
UV-108-25	HUVC1000	805	180	19.5	16.6	75/63	45	51	3.3	2.0	--	35.1	68	103	180	160	3.6	2.0	--
UV-110-25	HUVC1000	805	180	19.5	16.6	75/63	45	51	3.3	2.0	--	35.1	68	103	180	160	3.6	2.0	--
UV-112-25	HUVC1000	805	180	19.5	16.6	75/63	45	51	3.3	2.0	--	35.1	68	103	180	160	3.6	2.0	--
UV-114-25	HUVC1000	805	180	19.5	16.6	75/63	45	51	3.3	2.0	--	35.1	68	103	180	160	3.6	2.0	--
AREA 'B'																			
UV-149-25	HUVC1000	805	180	19.5	16.6	75/63	45	51	3.3	2.0	--	35.1	68	103	180	160	3.6	2.0	--
UV-163-25	HUVC1000	805	180	19.5	16.6	75/63	45	51	3.3	2.0	--	35.1	68	103	180	160	3.6	2.0	--
UV-161-25	HUVC1000	805	180	19.5	16.6	75/63	45	51	3.3	2.0	--	35.1	68	103	180	160	3.6	2.0	--
UV-165-25	HUVC1000	805	180	19.5	16.6	75/63	45	51	3.3	2.0	--	35.1	68	103	180	160	3.6	2.0	--
UV-170-25	HUVC1000	805	180	19.5	16.6	75/63	45	51	3.3	2.0	--	35.1	68	103	180	160	3.6	2.0	--
UV-171-3	HUVC1500	1300	221	29.1	26.0	75/63	45	51	4.93	2.0	--	64.4	68	107	180	160	6.4	4.0	--
UV-175-25	HUVC1000	805	180	19.5	16.6	75/63	45	51	3.3	2.0	--	35.1	68	103	180	160	3.6	2.0	--
UV-132-3	HUVC1500	1300	221	29.1	26.0	75/63	45	51	4.93	2.0	--	64.4	68	107	180	160	6.4	4.0	--
UV-130-3	HUVC1500	1300	221	29.1	26.0	75/63	45	51	4.93	2.0	--	64.4	68	107	180	160	6.4	4.0	--
UV-124B-3	HUVC1500	1300	221	29.1	26.0	75/63	45	51	4.93	2.0	--	64.4	68	107	180	160	6.4	4.0	--
UV-124A-3	HUVC1500	1300	221	29.1	26.0	75/63	45	51	4.93	2.0	--	64.4	68	107	180	160	6.4	4.0	--
UV-155-25	HUVC1000	805	180	19.5	16.6	75/63	45	51	3.3	2.0	--	35.1	68	103	180	160	3.6	2.0	--
UV-159-2	HUVA750	720	135	14.1	13.8	75/63	45	51	2.5	2.0	--	29.0	68	104	180	160	2.9	4.8	--

- ① OR APPROVED EQUAL. HORIZONTAL EXPOSED (AT THE CEILING) WITH FRONT BAR GRILLE DISCHARGE, BAR GRILLE BOTTOM RETURN AIR GRILLE, NO O.A. OPENING, FILTER RACKS AND 2" MERV 8 FLEAT THROUGHWAY TYPE FILTERS, BOTTOM ACCESS PANEL, NON-FUSED DISCONNECT SWITCHES.
- ② CONTRACTOR SHALL ENSURE ANY UNIT VENTILATOR SUBSTITUTED FOR THOSE SPECIFIED SHALL BE COORDINATED WITH ELECTRICAL AND PHYSICAL DIFFERENCES.
- ③ ECM MOTORS, VOLTAGE SHALL MATCH AVAILABLE ELECTRICAL SERVICE, SEE ELECTRICAL.
- ④ PROVIDE MERV 8 THROUGHWAY FILTERS TO MAINTAIN A CLEAN SYSTEM DURING TEMPORARY SERVICE.
- ⑤ ALL COOLING COILS SHALL HAVE 2-WAY PRESS. INDEPENDENT CONTROL VALVES WITH UNIONS, 2-WAY CONTROL VALVES WITH AUTO-FLOW CONTROL VALVES FOR HEATING COILS, STAINLESS STEEL DRAIN PANS, AND UNION CONNECTIONS TO COILS. SEE WATER PIPING DIAGRAM ON P102. SCHEIDER ELECTRIC TO FURNISH CONTROL VALVES, THIS CONTRACTOR SHALL INSTALL THEM IN PIPING RUNOUTS.
- ⑥ RE-USE EXISTING BI-POLAR IONIZATION KITS FROM REMOVED UNIT VENTILATORS.
- ⑦ PROVIDE NEW CONDENSATE PUMPS EQUAL TO LITTLE GIANT VCM-15, 0.5 GALLON TANK, 50 GPH (0.83 GPM) AT 5 FT. HEAD, 115 VOLT / 10 AMP, BUILT-IN CHECK VALVE, AND 3/8" BARBED DISCHARGE. PRIOR TO ORDERING PUMPS, VERIFY INSIDE DIMENSIONS OF EXISTING WALL MOUNTED PUMP ENCLOSURES AND VERIFY PUMP WILL FIT INSIDE ENCLOSURE. REPORT ANY PROBLEMS TO ENGINEER OR PROJECT MANAGER FOR SUBSTITUTION.
- ⑧ PROVIDE UNIT VENTILATORS WITH CONTROLS TERMINAL STRIP. SCHEIDER ELECTRIC TO TAKE FULL CONTROL OF UNIT VENTILATORS AND COMMUNICATION WITH BAS.

4-PIPE FAN COIL UNIT SCHEDULE ② ④ ⑤ ⑥ ① ⑧

MARK	TRANE MODEL ①	CFM	FAN ③ MOTOR	COOLING COIL							HEATING COIL								
				TOTAL MBH	SENS. MBH	ENT. AIR	EWT °F	LWT °F	GPM	WATER P.D. (FT)	RUNOUT SIZE	CAPACITY	ENT. AIR	LVG. AIR	EWT °F	LWT °F	GPM	WATER P.D. (FT)	RUNOUT SIZE
AREA 'A'																			
FCU-151-15	FCDB060	570	125 W	11.5	11.2	75/63	45	55	2.3	2.3	3/4"	17.5	68	95	180	160	1.8	1.0	3/4"
FCU-153-15	FCDB060	570	125 W	11.5	11.2	75/63	45	55	2.3	2.3	3/4"	17.5	68	95	180	160	1.8	1.0	3/4"
FCU-157-15	FCDB060	570	125 W	11.5	11.2	75/63	45	55	2.3	2.3	3/4"	17.5	68	95	180	160	1.8	1.0	3/4"

- ① OR APPROVED EQUAL. HORIZONTAL EXPOSED (AT THE CEILING) WITH FRONT QUAD GRILLE DISCHARGE, STAMPED BOTTOM RETURN AIR GRILLE, NO O.A. OPENING, FILTER RACKS AND 1" MERV 8 FLEAT THROUGHWAY TYPE FILTERS, BOTTOM ACCESS PANEL, NON-FUSED DISCONNECT SWITCHES.
- ② CONTRACTOR SHALL ENSURE ANY UNIT VENTILATOR SUBSTITUTED FOR THOSE SPECIFIED SHALL BE COORDINATED WITH ELECTRICAL AND PHYSICAL DIFFERENCES.
- ③ ECM MOTORS, VOLTAGE SHALL MATCH AVAILABLE ELECTRICAL SERVICE, SEE ELECTRICAL.
- ④ PROVIDE MERV 8 THROUGHWAY FILTERS TO MAINTAIN A CLEAN SYSTEM DURING TEMPORARY SERVICE.
- ⑤ ALL COOLING COILS SHALL HAVE 2-WAY PRESS. INDEPENDENT CONTROL VALVES WITH UNIONS, 2-WAY CONTROL VALVES WITH AUTO-FLOW CONTROL VALVES FOR HEATING COILS, STAINLESS STEEL DRAIN PANS, AND UNION CONNECTIONS TO COILS.
- ⑥ RE-USE EXISTING BI-POLAR IONIZATION KITS FROM REMOVED UNIT VENTILATORS.
- ⑦ PROVIDE NEW CONDENSATE PUMPS EQUAL TO LITTLE GIANT VCM-15, 0.5 GALLON TANK, 50 GPH (0.83 GPM) AT 5 FT. HEAD, 115 VOLT / 10 AMP, BUILT-IN CHECK VALVE, AND 3/8" BARBED DISCHARGE. PRIOR TO ORDERING PUMPS, VERIFY INSIDE DIMENSIONS OF EXISTING WALL MOUNTED PUMP ENCLOSURES AND VERIFY PUMP WILL FIT INSIDE ENCLOSURE. REPORT ANY PROBLEMS TO ENGINEER OR PROJECT MANAGER FOR SUBSTITUTION.
- ⑧ PROVIDE FAN COIL UNITS WITH CONTROLS TERMINAL STRIP. SCHEIDER ELECTRIC TO TAKE FULL CONTROL OF FAN COIL UNITS AND COMMUNICATION WITH BAS.


ROOF VENT SCHEDULE

MARK	GREENHECK ①	SERVICE	CFM	S.P.	THROAT AREA	REMARKS
RAV-DOAS-A1	RGR-16x16	EXHAUST	1175	0.06"	1.78 SQFT.	PRE-FAB CURB # BIRD SCREEN
RAV-DOAS-B2	RGR-20x20	EXHAUST	1355	0.07"	2.78 SQFT.	PRE-FAB CURB # BIRD SCREEN
RAV-DOAS-B3	RGR-18x18	EXHAUST	1150	0.08"	2.25 SQFT.	PRE-FAB CURB # BIRD SCREEN

- ① OR EQUAL BY COOK, ACHE, BREIDERT, CARNES OR APPROVED EQUAL.

**Schneider Electric**

Schneider Electric  
13000 North Loop East  
Carrollton, TX 75006 USA  
Tel. 1-877-333-1111  
www.schneider-electric.com



SCHNEIDER ELECTRIC ENERGY SERVICES PROJECT

FOR

BRUNSWICK COUNTY SCHOOL DISTRICT

SOUTH BRUNSWICK HIGH SCHOOL

280 COUGAR ROAD

SOUTHPORT, NC 28461

SHEET TITLE

HVAC SCHEDULES AND DETAILS

ECM-3A

MARK	DATE	DESCRIPTION
		SUBMISSION / REVISION

DRAWN BY: DJ	CHECKED BY: CDW
DESIGNED BY: DJ	APPROVED BY: CDW
DATE: 03-23-22	PROJECT: PC21P0006

SHEET NUMBER

M201

SHT. OF





## MECHANICAL SPECIFICATIONS

- GENERAL
- 1.1 All material and work shall comply with the National Fire Codes of the NFPA, National and local codes and the 2018 North Carolina State Building Code, ASHRAE Standard 90.1 – 2018 and 2017 American National Standards Institute Code.
- 1.2 Drawings for work under Division 23 are diagrammatic and generally, indicate reasonable arrangements. Work under Division 23 includes all necessary to make HVAC systems complete and fully operational.
- 1.3 MATERIAL AND EQUIPMENT SUBMITTALS: Submit for review detailed drawings of all equipment and all material listed in this section. All material submittals shall be submitted in hardback binders. Partial submittals will not be reviewed by the Engineer. Furnish six (6) copies of equipment submittals. Review rendered on equipment submittals shall not be construed as approval of the materials of building conditions. WHERE DRAWINGS ARE REVIEWED, SAID REVIEW SHALL BE LIMITED TO THE MATERIALS AND EQUIPMENT SUBMITTED. REVIEW DOES NOT IN ANY WAY RELIEVE THE CONTRACTOR FROM ANY RESPONSIBILITY OR OBLIGATION TO FURNISH THE BEST QUALITY PERFORMANCE AS REQUIRED BY THE CONTRACT DOCUMENTS. Submit the following materials and equipment for review by the Engineer:
1. Unit Ventilators
  2. Duct and Pipe Insulation
  3. Roof Air Vents (see schedule)
  4. Coils and Diffusers (see schedule)
  5. Pressure Gauges and Pipe Thermometers
  6. Piping and Valves
  7. Dedicated Outside Air Systems (DOAS)
  8. Seismic Submittals
- 1.4 WORKMANSHIP: Work that is not of good quality will require removal and reinstallation.
- 1.5 COORDINATION: No work shall be performed on this project before coordinating with the existing building. The Contractor shall coordinate with the building owner, and control components with all trades concerned and existing conditions. Temperature and equipment control wiring is included under Division 23.
- 1.6 The responsibility for obtaining, cutting, and patching for work under Division 23 of the specifications is included Division 23.
- 1.7 DAMAGES DURING CONSTRUCTION: Contractor shall be responsible for any costs of repairing any damages caused by this contractor, to the building contents, and site during construction and warranty period.
- 1.8 WARRANTY: Warranty all contract components, piping and any other materials specified under Division 23. Warranty all equipment, piping and any other materials specified under Division 23 for a period of one (1) year from the date of project acceptance, unless otherwise indicated. Upon failure of any part(s) of the system during the warranty period, the affected portion(s) shall be repaired or replaced promptly by and at the expense of the Contractor.
- 1.9 IDENTIFICATION: Identify each piece control component. Items shall be identified by name and number. Nameplates shall be 1/16" thick plates with 1/2" high white letters on black background. Nameplates shall be attached to the component, not glued.
- 1.10 RECORD DRAWINGS: Provide record drawings for all work included under Division 23. Mark on the job site one complete set of drawings for this project. All changes authorized by the Engineer and/or Architect shall be listed on the drawings. Submit all drawings and drawings or other material shall be indicated in red ink on the drawings as work progresses. Before Final Completion, Contractor shall submit the latest set of drawings to the Structural Engineer which shall include the information outlined above. AutoCAD drawings (electronic), calculations, design details shall be corrected to depict all substituted materials and equipment.
- 2.0 SEISMIC REQUIREMENTS: All contractors shall comply with the 2018 International Building Code (IBC) for seismic requirements.
- 2.1 Provide seismic submittals including calculations to determine restraint loads resulting from seismic forces presented in IBC. Seismic calculations shall be certified by a Professional Structural Engineer in the employ of the seismic equipment manufacturer with a minimum of 5 years experience, and licensed in the project's jurisdiction.
- 2.2 Provide seismic calculations and submittals for all new roof mounted equipment.
- 2.3 Manufacturers of seismic restraints must be a member of the Vibration Isolation and Seismic Control Manufacturers Association (VISCMA).
- 2.4 Provide Letter of Acceptance from the manufacturer's agent for project closure indicating manufacturer's review of installed seismic restraints for new equipment throughout project.
- 3.0 TESTING, ADJUSTING, AND BALANCING
- 3.1 Work under this section includes the testing, adjusting and balancing of all new heating, ventilation, air conditioning and refrigeration systems. The results of all tests, adjustments and balancing shall be submitted to the Engineer for approval.
- 3.2 Instruments used shall be of high quality and as recommended by the manufacturer for the project. Instruments shall be properly calibrated and certified within the last six months.
- 3.3 The balancing firm shall warrant, solely that the system will be set to within 10% of the values as established by the drawings specifying conditions and design intent for the balancing areas. The testing, balancing and adjusting shall be performed as many times as required to prove project requirements have been met. As requested by the Engineer, tests shall be performed in his presence.
- 3.4 Any changes that are required for the final balancing results as determined by the balancing firm shall be provided under this section. The specifications shall not be changed, but not limited to, changing of pulleys, belts, dampers or adding dampers or access panels.
- 3.5 Prior to acceptance of the systems by the Owner, submit the following for review:
1. Final balancing report, in triplicate, contained in a hard-bound book
  2. All reports on the project
  3. All calculations
- These reports shall be prepared in accordance with the standards of ASHRAE or NEBB.

- 4.01 INSULATION
- 4.2 Insulation all on chilled water pipes shall be 1" thick and 1-1/2" thick on hot water pipes. Fiberglass pipe insulation shall be equal to Owens Corning Fiberglas 1000 or equivalent. All HVAC work, including insulation shall have a conductivity not to exceed 0.029. Insulation shall be applied in a single layer, coated with two coats of vapor sealing mastic applied over the staples.
- 4.2 New supply, return, exhaust and outside air supply ducts shall be insulated with 2" thick duct wrap equal to Mansville Microcrete 1000, "Gras-T", or equivalent. All ductwork shall have a vapor barrier. Addres to clean sheet metal ducts with bonding adhesive. Secure on ducts over 24" wide with weld pins and clip washers. Seal all seams and joints with mastic. Seal all seals with glass fabric and coat with flame retardant mastic.
- 5.0 DUCTWORK
- 5.2 Coordinate routing of new ducts with existing conditions and other trades in the field. Provide offsets and vary sizes as required to avoid existing structural and any other interferences. Do not construct any ductwork in the space reserved for other trades. Be thoroughly coordinated with all other trades and existing conditions.
- 5.2 New supply, return, exhaust and outside air supply ducts shall be constructed in strict accordance with SMACNA Low Pressure Duct Standards. A copy of the SMACNA Low Pressure Duct Standards shall be kept on the job site. All new ducts shall be galvanized sheet metal, 26 gauge minimum.
- 5.3 New flexible supply air ducts to ceiling diffusers shall be minimum 18" x 18" (181 CUs per Hour). Each section shall have locking sheet metal end rings for connection to take-off fittings and dampers. Maximum run of flexible ducts shall be six feet (6').
- 5.4 Supply air duct take-offs from sheet metal trunks shall be a factory fabricated fitting with an adhesive bonded collar and screw holes at each quadrant, air scoop, and balancing damper with a mechanical seal. All take-offs shall be made with sheet metal with sheet metal screws and coated with duct sealant.
- 5.5 Support ducts from the building structure with 1" wide galvanized sheet metal hangers on eight foot (8') centers and at each duct bend, transition, and location of a damper. Maximum duct spacing (3') centers. Crimping or sagging of flexible ducts will not be accepted.
- 6.0 PIPING
- 6.1 Piping shall comply with best trade practice. Provide clearance between pipe and building structure so pipes can expand without damage to building structure. All piping shall be installed in accordance with codes and comply with the 2018 North Carolina State Building Code. Pipe and equipment locations shall be determined in field. Exact location of equipment and pipes shall be determined in field.
- 6.2 Condensate drain piping shall be type L copper with soldered fittings. Provide P-traps at all condensate drain connections to floor mounted drain traps. Drain traps shall be twice the total size the pressure regulated by the cooling equipment fan. Slope condensate drain pipes minimum 1/4" per foot in direction of flow and connect to existing drain pipe.
- 6.3 Chilled water and hot water piping inside the building 2" and smaller shall be type L copper with sweat fitting.
- 6.4 Connection hoses for new unit ventilators shall be UL 94, flame retardant, steel braided flexible hose rated for 300 psi working pressure and 212°F temperature. Fittings shall be metal NPT with sweat NPTSS thread. The inner core shall be EPDM (Ethylene Propylene Diene) Hose. Hose shall be 3/4" ID.
- 6.5 Stop valves for chilled water and hot water piping shall be brass body ball valves designed for 125 psi working pressure. Ball valves shall be Federal Spec WW-V-35, type I, Class A, 150 lb. pressure rating. Short Handles shall zinc-chromate plate. Steel valves coated.
- 6.7 Strainers shall Y-type, 20 mesh type 304 stainless steel screens 125 psi working pressure with blow-down valves and removable strainers.
- 6.8 Flow control valves (globe valves) shall be complete with in-line strainers. Flow control valves shall be 50 cfm capacity rated for 150 psi working pressure. Valves shall include pressure/temperature port with a cap and union.
- 6.9 Motor control valves shall be 2-way, equal percentage bronze ball valves rated for 125 psi working pressure. Provide control valve with strainers. Motor control valves shall meet class 150 requirements and have 1% resolution. Actuators shall have a 5-year warranty. Valves shall fall open to the close.
- 6.10 Pipe thermometers for chilled water and hot coils in DOAS units shall be 1/2" NPT, 1/2" scale, accuracy ± 0.5°C. Accuracy shall be free, sealed in a vialox case, and glass lens. Accuracy shall be 1/4" of full scale. Water range shall be 32°F to 240°F. Hot water range shall be 32°F to 240°F.
- 6.11 Water pressure gauges for chilled water and hot coils in DOAS units shall be 4-1/2" dia, dial, flangeless cast aluminum with 1/2" NPT, 1/2" scale, accuracy ± 0.5°C. Accuracy shall be free, sealed in a vialox case, and glass lens. Accuracy shall be 1/4" of full scale. Water range shall be 32°F to 240°F. Hot water range shall be 32°F to 240°F.
- 7.0 UNIT VENTILATORS
- 7.1 Provide horizontal exposed unit ventilators, UL listed, NFPA-90A compliant certified or rated in accordance with AHRI-840 and AHRI-350.
- 7.2 Exterior cabinets shall be heavy-gauge metal. All interior shall be galv. sheet metal. Bottom shall removable be 2-panel design with accessible compartment with removable 2-panel design. Provide access to supply air outlet and return air inlet. Units shall include access to access for inspection of drain pan, coils and fan sections. Final finish shall be powder coated and painted. Provide electric power supply system with 1.5 min. duration thickness.
- 7.4 Cabinet insulation shall be 1 1/2" thick, dual density bonded glass fiber, suitable for 4,500 fpm or lower. Insulation shall meet Fire Hazard

END OF DIVISION 23

- 7.2** Piping and control end pockets shall be minimum 12" wide.
- 7.6** Hydraulic coils shall be plate-fin, mechanically bonded to tubes, tested to 350-350 psi, and rated in accordance with AHRI-440 or 220. Coils shall have threaded drain pipe and manual air valve. Heating coils shall be in the re-heat position.
- 7.8** Fans shall be double width, double inlet forward curved centrifugal. Wheels shall be galvanized metal, dynamically balanced with direct drive EC motors. Fan and coils shall be blow-thru design. Motors shall have internal thermal overload protection, permanently lubricated. Motors shall be capable of starting at 90% of rated voltage. Motors shall be able to operate at up to 100% over load.
- 7.8** Drain pan shall of a corrosion resistant design for quick removal of condensate. Pan shall be insulated on the bottom, and be removable for cleaning.
- 7.9** Provide units with filter rack for #1 MERV 13 filter based on ASHRAE Standard 52.2 atmospheric dust spot method.
- 7.10** Piping package shall include union, strainer, P/T port, and ball valve in the chilled water and hot water supply runout piping. Chilled water and hot water return piping shall include union, 2-way 2-position control valve, auto-flow balance device, P/T port, and ball valve.
- 8.1** FAN COIL UNITS:
- 8.3** Exterior cabinets shall be heavy-gauge metal. All interior shall be galv. sheet metal. Bottom shall removable be 2-panel design with accessible access doors. Units shall be suitable for ceiling mount. See schedule for supply air outlet and return air inlet. Units shall include access to areas for inspection of drain pan, coils, and fan sections. Final finish shall be powdercoated. Units shall be compatible with electric heating system with 1.5 min minimum thickness, meeting ASTM B117 salt spray test.
- 8.4** Cabinet insulation shall be 1/2" thick closed-cell insulation. Insulation shall be fire hazard resistant.
- 8.5** Piping and control end pockets shall be minimum 8" wide.
- 8.6** Hydraulic coils shall be plate-fin, mechanically bonded to tubes, tested to 350-350 psi, and rated in accordance with AHRI-440 or 220. Coils shall include threaded drain pipe and manual air valve. Heating coils shall be in the re-heat position.
- 8.8** Fans shall be double width, double inlet forward curved centrifugal. Wheels shall be galvanized metal, dynamically balanced with direct drive ECM motors. Fan and coils shall be blow-thru design. Motors shall have internal thermal overload protection, permanently lubricated. Motors shall be capable of starting at 90% of rated voltage. Motors operating at 90% of rated voltage. Motors shall be able to operate at up to 100% over load.
- 8.8** Drain pan shall of a corrosion resistant design for quick removal of condensate. Pan shall be insulated on the bottom, and be removable for cleaning. Pan shall be reversible after either side pipe connection.
- 8.9** Provide units with filter rack for #1 MERV 13 filter based on ASHRAE Standard 52.2 atmospheric dust spot method.
- 8.10** Piping package shall include union, strainer, P/T port, and ball valve in the chilled water and hot water supply runout piping. Chilled water and hot water return piping package shall include union, 2-way 2-position control valve, auto-flow balance device, P/T port, and ball valve.
- 9.1** DEDICATED OUTSIDE AIR UNIT (DOAS):
- 9.2** Provide low profile horizontal DOAS unit above the existing ceiling as shown and scheduled on the drawings. The units shall be chilled water cooled and have electric heat. Units shall have hot water heating.
- 9.3** Due to confined space above the existing ceiling, units with dimensions larger than those listed in the schedule will not be accepted.
- 9.4** Units shall be double wall construction injected panel construction with thermal breaks.
- 9.5** Chilled water dehumidification coil shall be sized to provide moisture removal and leaving air dewpoint temperature scheduled. Coils shall be made of copper tubing. Enter and hot water supply runout piping, chilled water and hot water return piping package shall include union, 2-way 2-position control valve, auto-flow balance device, P/T port, and ball valve.
- 9.6** Hot water heating coil shall be sized to deliver the leaving air temperature scheduled. Coils shall be copper tubes mechanically bonded to aluminum fins. Coil must be tested and rated for 150 psi. Coils shall have union connections.
- 9.7** Unit pans shall be stainless steel, double sloped to prevent standing water and microbial growth.
- 9.8** Energy recovery wheels shall be total enthalpy type with high airflow (cfm) capacity. Wheel cabinet shall include return air / exhaust air and outside air / intake air coils. Enter and hot water supply runout piping, chilled water and hot wet bulb temperatures listed in the schedule based on outdoor air bulb and wet bulb temperatures listed in the schedule.
- 9.9** Supply air blower shall be backward curved plenum fan with EC motor. Return air / exhaust air blower shall be backward curved plenum fan with EC Motor. Fans shall perform as listed in the schedule.
- 10.0** Units shall include filter rack on the outside air supply for 2" pleated media #13. Filter rack shall be located upstream of the energy recovery wheel for 2" pleated media MERV 8.
- 10.1** Piping package shall include union, strainer, P/T port, and ball valve in the chilled water and hot water supply runout piping, chilled water and hot water return piping package shall include union, 2-way 2-position control valve, auto-flow balance device, P/T port, and ball valve.





THIS DRAWING IS THE PROPERTY OF SCHNEIDER ELECTRIC AND IS SUBJECT TO RETURN UPON REQUEST. IT IS NOT TO BE COPIED OR REPRODUCED, NOR IS IT TO BE USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT WAS FURNISHED, WITHOUT THE WRITTEN CONSENT OF SCHNEIDER ELECTRIC.

## RACEWAY MATERIAL USE TABLE

APPLICATION	EMT	IMC	GRS	RAC	ENT	SCH 40 PVC	HDPE	AC/MC CABLE	MFD. WIRING
CONTRACTOR MAY USE ANY MATERIAL MARKED (C) FOR APPLICATION LISTED. IF MATERIAL IS NOT MARKED FOR AN APPLICATION, IT SHALL NOT BE USED FOR THAT APPLICATION.									
BRANCH CIRCUITS									
CONCEALED ABOVE CEILING	●	●	●	●					
CONCEALED IN WALLS	●	●	●	●					
EXPOSED FROM FLOOR TO 7'-0" A.F.F. (INTERIOR)	●	●	●	●					
EXPOSED FROM 7'-0" A.F.F. AND ABOVE (INTERIOR)	●	(1)	(1)		NOT PERMITTED			NOT PERMITTED	NOT PERMITTED
IN OR UNDER CONCRETE FLOORS		(1)	(1)		NOT PERMITTED			NOT PERMITTED	NOT PERMITTED
OUTDOORS - BELOW GRADE	●	●	●	●					
OUTDOORS - EXPOSED	●	●	●	●					
STUB-UPS BELOW PANELS & ENCLOSURES	●	●	●	●					
FEEDER CONDUITS						(2)			
SERVICE ENTRANCE						(2)			

- (1) WITH BITUMINOUS COATING. SEE SPEC. (3) WITH PANEL "SKIRT" ONLY.  
(2) OUTDOORS - BELOW GRADE.



## GROUNDING OF CONDUITS 1" C. AND LARGER

1. SIZE - EQUIPMENT BONDING JUMPER ON SUPPLY SIDE OF SERVICE: THE BONDING JUMPER SHALL NOT BE SMALLER THAN THE SIZES SHOWN IN TABLE 250.66 FOR GROUNDING ELECTRODE CONDUCTORS.
2. SIZE - EQUIPMENT BONDING JUMPER ON LOAD SIDE OF SERVICE: THE BONDING JUMPER SHALL NOT BE SMALLER THAN THE SIZES SHOWN IN TABLE 250.122 FOR EQUIPMENT GROUNDING CONDUCTORS.
3. FOR MORE THAN ONE RACEWAY IN ENCLOSURE, BOND ALL LUGS TOGETHER BEFORE TYING BONDING JUMPER TO ENCLOSURE.
4. BOND BOTH ENDS OF EACH CONDUIT 1" C. AND LARGER.
5. EXTEND BONDING JUMPER TO EACH PANEL INCLUDING TWO-SECTION PANELS WITH FEED-THRU JUMPLERS.

## ABBREVIATIONS

THE FOLLOWING STANDARD ABBREVIATIONS ARE USED IN THESE PLANS AND SPECIFICATIONS. CONTRACTOR IS CAUTIONED THAT ALL ABBREVIATIONS LISTED MAY NOT BE USED; CONSULT PLANS AND SPECIFICATIONS FOR ABBREVIATIONS APPLICABLE TO THIS PROJECT.

A.F.F.	ABOVE FINISHED FLOOR
B.F.F.	BELOW FINISHED FLOOR
A.F.G.	ABOVE FINISHED GRADE
B.F.G.	BELOW FINISHED GRADE
U.N.O.	UNLESS NOTED OTHERWISE
CKT.	CIRCUIT
C.	CONDUIT
E.C.	EMPTY CONDUIT
FLX.	FLEXIBLE CONDUIT
WFLX	WEATHERPROOF FLEXIBLE CONDUIT
EHWH	ELECTRIC WATER HEATER
VE	VENTILATING FAN
CEF	VENTILATING FAN (CEILING EXHAUST FAN)
AHU	AIR HANDLING UNIT
FCU	FAN COIL UNIT
CU	CONDENSING UNIT
RTU	ROOF TOP HEATING/COOLING UNIT
P	PUMP
EDH	ELECTRIC DUCT HEATER
RAC	ROOM AIR CONDITIONING/HEATING UNIT
CHLR	CHILLER
HP	HEAT PUMP OR HORSEPOWER

## BRANCH CIRCUIT WIRING -

### HASH-MARK CODE

BRANCH CIRCUITS SHOWN ON THESE DRAWINGS MAY INCLUDE HASHMARKS WHICH INDICATE THE NUMBER OF WIRES TO BE PROVIDED IN A CONDUIT RUN BETWEEN OUTLETS OR JUNCTION BOXES. WIRE SIZES SHALL BE AS TABULATED IN PANELBOARD SCHEDULES UNLESS OTHERWISE INDICATED ON PLAN. SEE SYMBOL SCHEDULE FOR CONDUIT ROUTING NOTATION. HASHMARK CODE IS AS FOLLOWS:

EACH PHASE AND NEUTRAL WIRE IN A CONDUIT RUN IS REPRESENTED BY A HASHMARK. FOR EXAMPLE -

- TWO WIRES (NO HASHMARKS)  
— THREE WIRES (3 HASHMARKS)  
— FOUR WIRES (4 HASHMARKS)  
— FIVE WIRES (5 HASHMARKS)  
... AND SO FORTH.


NOTE: GROUND WIRES ARE NOT GENERALLY SHOWN. EXAMINE SPECIFICATIONS AND GENERAL NOTES TO DETERMINE REQUIREMENTS FOR GROUND WIRES AND WHERE SPECIFIED, PROVIDE IN ADDITION TO THE NUMBER OF WIRES INDICATED BY HASHMARK CODE.

NOTE: CONTRACTOR IS CAUTIONED THAT MULTI-WIRE (LINE-TO-NEUTRAL) BRANCH CIRCUITS DO NOT INDICATE ALL REQUIRED NEUTRAL CONDUCTORS. PROVIDE SEPARATE NEUTRAL CONDUCTORS (WITH COLORED STRIPE TO MATCH PHASE CONDUCTOR) FOR EACH PHASE CONDUCTOR.

EMPTY CONDUITS ARE NOTED BY "EC" WITH TRADE SIZE.

## GENERAL NOTES


- DO NOT SCALE DRAWINGS UNLESS DIMENSIONS ARE SHOWN. LOCATE OUTLETS AND EQUIPMENT AS OBVIOUSLY INDICATED AND COORDINATE WITH OTHER TRADES TO AVOID CONFLICTS.
- MINIMUM SIZE CONDUCTOR FOR POWER SHALL BE NO. 12 AWG.
- ALL FUSES SHALL BE DUAL-ELEMENT TYPE, "FUSETRON" BY BUSSMAN, OR "TECON" BY ECONOMY.
- BRANCH CIRCUIT SIZES ARE AWG 12-1/2" C. UNLESS OTHERWISE NOTED IN PANELBOARD SCHEDULES.
- ALL BRANCH CIRCUIT LOADS SHALL BE BALANCED ACROSS PANELBOARD BUSES TO OBTAIN MINIMUM NEUTRAL CURRENT.
- ALL FLEXIBLE CONDUIT SHALL CONTAIN A GREEN WIRE BONDED TO RIGID RACEWAY, BOX OR FIXTURE AT EACH END OF FLEX. SIZE GROUND WIRE PER N.E.C. TABLE 250-122.
- ALL ELECTRICAL WORK ABOVE CEILINGS UTILIZED AS RETURN AIR PLENUMS SHALL COMPLY WITH N.E.C. AND LOCAL CODES FOR WIRING USED IN ENVIRONMENTAL AIR.
- CONTRACTOR SHALL MINIMIZE REMOVAL OF STRUCTURAL STEEL FIREPROOFING FOR INSTALLATION OF CONDUIT AND EQUIPMENT HANGERS. OBTAIN APPROVAL OF GENERAL CONTRACTOR PRIOR TO REMOVAL.
- COORDINATE WITH OTHER TRADES TO CONCEAL ELECTRICAL WORK AND PROVIDE OUTLETS IN CORRECT LOCATIONS FOR EACH PIECE OF MECHANICAL OR ELECTRICAL EQUIPMENT CONNECTED.
- COORDINATE DEVICE REQUIREMENTS AND MOUNTING HEIGHTS FOR THRU-WALL UNITS AND THE LIKE WITH EQUIPMENT FURNISHED.
- ALL PENETRATIONS THRU WALLS, FLOORS, BARRIERS, PARTITIONS AND THE LIKE SHALL BE SEALED TIGHT. SEAL ALL PENETRATIONS THRU SMOKE TIGHT PARTITIONS WITH U.L. LISTED ASSEMBLIES OR METHODS. SEE ARCHITECTURAL DRAWINGS FOR LOCATIONS OF SMOKE PARTITIONS.
- FIRESTOP ALL RACEWAYS PASSING THRU FIRE-RATED WALLS, FLOORS OR PARTITIONS. USE U.L. LISTED THROUGH-PENETRATION FIRESTOP SYSTEMS APPROPRIATE FOR CONSTRUCTION AND WITH RATING EQUAL TO THAT BEING PENETRATED. SUBMIT SHOP DRAWINGS FOR SYSTEM(S) PROPOSED. SEE ARCHITECTURAL DRAWINGS FOR LOCATIONS AND RATINGS.
- OPENINGS GREATER THAN SIXTEEN(16) SQUARE INCHES IN FIRE-RATED WALLS AND PARTITIONS SHALL BE PROTECTED WITH U.L. LISTED SYSTEMS, COMPONENTS AND METHODS AS REQUIRED TO MAINTAIN RATING. PROVIDE PUDDY PADS, LIGHT COVERS, INSERTS, WRAPS, COLLARS AND THE LIKE AS REQUIRED.
- ALL TYPEWRITTEN PANELBOARD DIRECTORIES, FIRE ALARM PROGRAMMING, LIGHTING CONTROL PROGRAMMING, LABELING AND THE LIKE SHALL UTILIZE FINAL OPERATIONAL ROOM NAMING SYSTEM AND SHALL REFLECT FINAL ROOM DESIGNATIONS. COORDINATE WITH ARCHITECT AND OWNER FOR FINAL NAMING.



## COMPRESSION TYPE CONDUIT FITTING

Copyright © 1999 by WEA & Associates, Inc. NO SCALE

## SYSTEM NO. W-L-1001



- WALL ASSEMBLY - THE 1, 2, 3 OR 4 HR FIRE RATED GYPSUM WALLBOARD/STUD WALL ASSEMBLY SHALL BE CONSTRUCTED OF THE MATERIALS AND IN THE MANNER DESCRIBED IN THE INDIVIDUAL U300 OR U400 SERIES WALL OR PARTITION DESIGNS IN THE UL FIRE RESISTANCE DIRECTORY AND SHALL INCLUDE THE FOLLOWING CONSTRUCTION FEATURES:
  - STUDS - WALL FRAMING MAY CONSIST OF EITHER WOOD STUDS (MAX 2 H FIRE RATED ASSEMBLIES FOR STEEL CHANNEL STUDS. WOOD STUDS TO CONSIST OF NOM. 2 BY 4 IN. LUMBER SPACED 16" OC WITH NOM. 2 BY 4 IN. LUMBER END PLATES AND CROSS BRACES. STEEL STUDS TO BE MIN. 3-5/8 IN. WIDE BY 1-3/8 IN. DEEP CHANNELS SPACED MAX. 24 IN. OC.
  - WALLBOARD GYPSUM - NOM. 1/2 OR 5/8 IN. THICK, 4 FT. WIDE WITH SQUARE OR TAPERED EDGES. THE GYPSUM WALLBOARD TYPE, THICKNESS, NUMBER OF LAYERS, FASTENER TYPES AND SHEET ORIENTATION SHALL BE AS SPECIFIED IN THE INDIVIDUAL U300 OR U400 SERIES DESIGN IN THE UL FIRE RESISTANCE DIRECTORY. MAX. DIAM. OF OPENING IS 13-1/2 IN.
- PIPE OR CONDUIT - NOM. 12 IN. DIAM. (OR SMALLER) SCHEDULE 10 (OR HEAVIER) STEEL PIPE, NOM. 12 IN. DIAM. (OR SMALLER) SERVICE WEIGHT (OR HEAVIER) CAST IRON SOIL PIPE, NOM. 12 IN. DIAM. (OR SMALLER) CLASS 50 (OR HEAVIER) DUCTILE IRON PRESSURE PIPE, NOM. 6 IN. DIAM. (OR SMALLER) STEEL CONDUIT, NOM. 4 IN. DIAM. (OR SMALLER) STEEL ELECTRICAL METALLIC TUBING, NOM. 6 IN. DIAM. (OR SMALLER) TYPE L (OR HEAVIER) COPPER TUBING OR NOM. 1 IN. DIAM. (OR SMALLER) FLEXIBLE STEEL CONDUIT. WHEN COPPER PIPE IS USED, MAX. F RATING OF FIRESTOP SYSTEM (ITEM 3) IS 2 H. STEEL PIPES OR CONDUITS LARGER THAN NOM. 4 IN. DIAM. MAY ONLY BE USED IN WALLS CONSTRUCTED USING STEEL CHANNEL STUDS. A MAX. OF ONE PIPE OR CONDUIT IS PERMITTED IN THE FIRESTOP SYSTEM. PIPE OR CONDUIT TO BE INSTALLED NEAR CENTER OF STUD CAVITY WIDTH AND TO BE RIGIDLY SUPPORTED ON BOTH SIDES OF WALL ASSEMBLY.
- FILL VOID OR CAVITY MATERIAL\* - CAULK - CAULK FILL MATERIAL INSTALLED TO COMPLETELY FILL ANNULAR SPACE BETWEEN PIPE OR CONDUIT AND GYPSUM WALLBOARD AND WITH A MIN. 1/4 IN. DIAM. BEAD OF CAULK APPLIED TO PERIMETER OF PIPE OR CONDUIT AT ITS EGRESS FROM THE WALL. CAULK INSTALLED SYMMETRICALLY ON BOTH SIDES OF WALL ASSEMBLY. THE HOURLY F RATING OF THE FIRESTOP SYSTEM IS DEPENDENT UPON THE HOURLY F RATING OF THE WALL ASSEMBLY IN WHICH IT IS INSTALLED, AS SHOWN IN THE FOLLOWING TABLE. THE HOURLY F RATING OF THE FIRESTOP SYSTEM IS DEPENDENT UPON THE TYPE OR SIZE OF THE PIPE OR CONDUIT AND THE HOURLY F RATING OF THE WALL ASSEMBLY IN WHICH IT IS INSTALLED, AS TABULATED BELOW:

MAX. PIPE OR CONDUIT DIAM., IN.	ANNULAR SPACE IN.	F RATING HR	T RATING HR
1	0 TO 3/16	1 OR 2	0+ 1 OR 2
1	1/4 TO 1/2	3 OR 4	3 OR 4
4	0 TO 1/4	1 OR 2	0
4	0 TO 1-1/2	1 OR 2	0
6	1/4 TO 1/2	3 OR 4	0
12	3/16 TO 3/8	1 OR 2	0

\* WHEN COPPER PIPE IS USED, T RATING IS 0 H.  
# 0 TO 1-1/2 IN. ANNULAR SPACE APPLIES ONLY WHEN TYPE CP-25 WB - CAULK IS USED AND ONLY WHEN THE MIN. THICKNESS OF THE GYPSUM WALLBOARD IS 5/8 IN. FOR 1 HR RATED WALLS AND 1-1/4 IN. FOR 2 HR RATED WALLS.  
CAULK-K-3M COMPANY-TYPE CP 25WB+ OR FB-3000WT  
\* BEARING THE UL CLASSIFICATION MARKING.

## ELECTRICAL SYMBOLS

	TRANSFORMER		CONNECTION TO EXISTING CIRCUIT
	PANELBOARD		BRANCH CIRCUIT RACEWAY - CONCEALED IN WALL OR CEILING
	SAFETY SWITCH		BRANCH CIRCUIT RACEWAY - CONCEALED IN FLOOR OR UNDERGROUND
	ENCLOSED, MOLDED CASE CIRCUIT BREAKER		BRANCH CIRCUIT RACEWAY - EXPOSED
	MOTOR CONTROLLER OR CONTACTOR		EXISTING; TO REMAIN
	FLUSH JUNCTION BOX CEILING (Q=WALL)		EXISTING; BEING RELOCATED
	FULL BOX OR JUNCTION BOX IN FLOOR		EXISTING; NEW LOCATION
	TRANSIENT VOLTAGE SURGE SUPPRESSOR(TVSS)		
	ELECTRIC MOTOR		TYPICAL: SYMBOLS DENOTE EXISTING. REMOVE COMPLETE. TYPICAL: "X" ON PLAN SYMBOLS DENOTES EXISTING. REMOVE COMPLETE.
	CONDUIT STUB		
	MOTOR RATED SWITCH		


NOTE: ALL DEVICES SHOWN ON THIS SCHEDULE ARE SYMBOLIC ONLY. SEE ELECTRICAL SPECIFICATIONS FOR EXACT DEVICE REQUIREMENTS AND PERFORMANCE CHARACTERISTICS.

## NOTES TO THROUGH PENETRATION FIRESTOPPING

- WHERE RACEWAYS PASS THRU FIRE-RATED WALLS, FLOORS OR OTHER PARTITIONS, PROVIDE A UL-LISTED THROUGH PENETRATION SYSTEM WITH RATING EQUAL TO THAT OF CONSTRUCTION BEING PENETRATED.
- EACH ASSEMBLY SHALL BE SPECIFIC TO THE PENETRATING DEVICE (E.G., SINGLE CONDUIT, MULTIPLE CONDUITS, CABLE TRAY, ETC.) AND SHALL BE A UL LISTED SYSTEM AS PUBLISHED IN THE UL FIRE RESISTANCE DIRECTORY, LATEST EDITION.
- FIRESTOP SYSTEMS SHALL MEET REQUIREMENTS OF ASTM E-814/UL 1749 TESTED ASSEMBLIES THAT PROVIDE A FIRE RATING EQUAL TO THAT OF CONSTRUCTION BEING PENETRATED.
- FOR THOSE FIRESTOP APPLICATIONS THAT EXIST FOR WHICH NO UL TESTED SYSTEM IS AVAILABLE THROUGH THE MANUFACTURER, A MANUFACTURER'S ENGINEERING JUDGEMENT DERIVED FROM SIMILAR UL SYSTEM DESIGNS OR OTHER TESTS SHALL BE SUBMITTED TO LOCAL AUTHORITY HAVING JURISDICTION FOR THEIR APPROVAL PRIOR TO INSTALLATION. ENGINEERING JUDGEMENT DRAWINGS SHALL FOLLOW REQUIREMENTS SET FORTH BY THE INTERNATIONAL FIRESTOP COUNCIL.
- INSTALLATION SHALL BE IN COMPLIANCE WITH MANUFACTURER'S INSTRUCTION AND IN ACCORDANCE WITH UL FIRE RESISTANCE DIRECTORY FOR EACH SYSTEM UTILIZED.
- FIRESTOP MATERIALS SHALL BE BY 3M COMPANY, ILTI USA, SPECIFIED TECHNOLOGIES INC (STI), METACALK, TREMCO OR APPROVED EQUAL.
- SUBMIT UL SYSTEM DETAIL AND PRODUCT DATA FOR EACH FIRE STOP COMPONENT UTILIZED, INCLUDING DETAILED DRAWINGS, INSTALLATION INSTRUCTIONS, ASSEMBLY LISTING NUMBER, CERTIFICATED OF CONFORMANCE AND MATERIAL SAFETY DATA SHEETS. MAINTAIN A COPY OF APPROVED SHOP DRAWINGS ON SITE FOR REVIEW BY ENGINEER, THIRD PARTY INSPECTOR AND AHJ.
- COORDINATE WITH OTHER TRADES AND CONTRACT REQUIREMENTS FOR ADDITIONAL FIRESTOPPING REQUIREMENTS. WHERE REQUIRED, ALL FIRESTOP MATERIAL SHALL BE BY SAME MANUFACTURER AND/OR SAME FIRESTOPPING SUB-CONTRACTOR.

## SYSTEM NO. WL1014 (FORMERLY SYSTEM NO. 259)

F RATING - 2 HR  
T RATING - 3/4 HR



## SECTION A-A

- WALL ASSEMBLY - THE FIRE RATED GYPSUM WALLBOARD/STUD WALL ASSEMBLY SHALL BE CONSTRUCTED OF THE MATERIALS AND IN THE MANNER SPECIFIED IN THE INDIVIDUAL U300 OR U400 SERIES WALL AND PARTITION DESIGNS IN THE UL FIRE RESISTANCE DIRECTORY AND SHALL INCLUDE THE FOLLOWING CONSTRUCTION:
  - STUDS - WALL FRAMING MAY CONSIST OF EITHER WOOD STUDS OR STEEL CHANNEL STUDS. WOOD STUDS TO CONSIST OF NOM. 2 BY 4 IN. LUMBER SPACED 16 IN. OC. STEEL STUDS TO BE MIN. 2-1/2 IN. WIDE AND SPACED MAX 24 IN. OC.
  - WALLBOARD GYPSUM - TWO LAYERS OF NOM. 5/8 IN. THICK GYPSUM WALLBOARD, AS SPECIFIED IN THE INDIVIDUAL WALL AND PARTITION DESIGN. MAX. AREA OF OPENING IS 78 SQ. IN. WITH MAX. DIMENSION OF 12 IN.
- METALLIC PIPE - NOM. 3-1/2 IN. DIAM. (OR SMALLER) SCHEDULE 5 (OR HEAVIER) STEEL PIPE, CONDUIT OR STEEL ELECTRICAL METALLIC TUBING. THE SPACE BETWEEN PIPES, CONDUITS, OR TUBING SHALL MIN. BE 1 IN. TO MAX. 2-5/8" THE SPACE BETWEEN PIPES, CONDUITS OR TUBING AND PERIPHERY OF OPENING SHALL BE MIN. 1 IN. TO MAX. 2-5/8". PIPE, CONDUIT OR TUBING TO BE RIGIDLY SUPPORTED ON BOTH SIDES OF FLOOR OR WALL ASSEMBLY.
- FIRESTOP SYSTEM - THE FIRESTOP SYSTEM SHALL CONSIST OF THE FOLLOWING:
  - STEEL WIRE MESH - NO. 8 STEEL WIRE MESH HAVING A MIN. 1 IN. LAP ALONG THE LONGITUDINAL SEAM. LENGTH OF STEEL WIRE MESH TO BE 4 IN., CENTERED AND FORMED TO FIT PERIPHERY OF THROUGH OPENING.
  - FILL, VOID OR CAVITY MATERIAL\* - PILLOW-LIKE MATERIAL TIGHTLY PACKED INTO THE ANNULAR SPACE BETWEEN THE PIPES AND PERIMETER OF THROUGH OPENING. PRIOR TO INSTALLATION, THE PILLOW-LIKE MATERIAL SHALL BE PATTED DOWN BY HAND OR WITH A FLAT BOARD TO EVENLY DISTRIBUTE CONTENTS. THE PILLOW-LIKE MATERIAL SHALL BE INSTALLED HORIZONTALLY SUCH THAT IT IS FLUSH WITH THE SURFACES OF THE WALL. METALINES, INC. - METACALK 910 RETROFIT BAGS. RECTORSAL CORP. - METACALK 910 RETROFIT BAGS.
  - FILL, VOID OR CAVITY MATERIAL\* - CAULK - APPLIED TO ALL RETROFIT BAG JOINTS, VOIDS, PERIMETER OF PIPES, AND PERIMETER OF THROUGH OPENING TO A MIN. DEPTH OF 1/8 IN. THE RECTORSAL CORP. - METACALK 950.

\* BEARING THE UL CLASSIFICATION MARKING.

## DEMOLITION NOTES

- BIDDERS SHALL VISIT THE SITE OF WORK PRIOR TO BIDDING AND SHALL INCLUDE IN BID ALL WORK REQUIRED TO PROVIDE NEW WORK AND TO MODIFY EXISTING WORK AS REQUIRED TO CONTINUE IN OPERATION.
- DEMOLITION WORK SHALL COMPLY WITH ANSI 10.6, NFPA 241, OSHA, AHERA AND ALL OTHER APPLICABLE LOCAL, STATE AND FEDERAL STANDARDS, CODES AND GUIDELINES.
- CONTRACTOR IS CAUTIONED THAT DEMOLITION PLANS ARE BASED ON RECORD DRAWINGS AND VISUAL FIELD OBSERVATION AND ARE INTENDED TO COMMUNICATE INTENT OF DEMOLITION AND DO NOT INDICATE EVERY COMPONENT OF ELECTRICAL SYSTEMS.
- OWNER SHALL RETAIN FIRST RIGHT OF REFUSAL ON ELECTRICAL EQUIPMENT BEING DEMOLISHED. PRIOR TO BEGINNING DEMOLITION WORK, CONTRACTOR SHALL WALL DEMOLITION AREA WITH OWNER REPRESENTATIVE AND IDENTIFY ITEMS TO BE REMOVED AND TURNED OVER TO OWNER. ALL SUCH ITEMS SHALL BE CAREFULLY REMOVED, PROTECTED AND DELIVERED TO OWNER.
- EXISTING RACEWAY AND WIRING SYSTEMS REUSED AS PART OF THIS CONTRACT SHALL BE REWORKED AS REQUIRED TO COMPLY WITH REQUIREMENTS FOR NEW WORK AND CURRENT CODES AND STANDARDS.
- CONTRACTOR SHALL EXAMINE DEMOLITION AND NEW WORK PLANS FOR ALL TRADES AND INCLUDE IN BID ALL REQUIRED REWORK AND/OR RELOCATION OF EXISTING RACEWAY, JUNCTION BOXES, DEVICES, WIRING SYSTEMS AND THE LIKE AS REQUIRED TO ACCOMMODATE NEW CONSTRUCTION.
- SEE MECHANICAL DRAWINGS FOR EXTENT OF DEMOLITION WORK REQUIRED. REMOVE ELECTRICAL WORK COMPLETE FOR MECHANICAL SYSTEMS BEING REMOVED BY OTHERS. CONTRACTOR IS CAUTIONED THAT THIS EQUIPMENT MAY BE LOCATED OUTSIDE OF GENERAL DEMOLITION AREA (SUCH AS IN MECHANICAL ROOMS, MEZZANINES, ROOFTOP OR SIMILAR LOCATIONS).
- INCLUDE IN BID ALL WORK REQUIRED FOR TEMPORARY WIRING AND ASSOCIATED ELECTRICAL WORK REQUIRED TO MAINTAIN EXISTING SYSTEMS IN SERVICE DURING DEMOLITION PHASE. INTERRUPTIONS IN ANY ELECTRICAL SERVICE OR SYSTEM (POWER, LIGHTING, COMMUNICATION, FIRE ALARM, ETC.) SHALL BE COORDINATED WITH AND APPROVED BY OWNER A MINIMUM OF 48 HOURS PRIOR TO PERFORMING WORK U.N.O.
- ELECTRICAL DEMOLITION GENERALLY INCLUDES REMOVAL OF EXISTING OUTLETS, DEVICES, AND OTHER ELECTRICAL COMPONENTS. WHERE ALL CIRCUIT LOADS ARE REMOVED, DEMOLISH CIRCUITS BACK TO PANELBOARD(S). WHERE ONLY PORTIONS OF CIRCUIT LOADS ARE REMOVED, REWORK CIRCUITS BY EXTENSION AND RECONNECTION TO CONTINUE REMAINING LOADS IN SERVICE BEYOND THE DEMOLITION AREA.
- WIRING SYSTEMS SHALL BE REMOVED BACK TO THE SOURCE OF SUPPLY UNLESS NOTED OTHERWISE. CIRCUIT BREAKERS, FUSIBLE SWITCHES, ETC. SUPPLYING LOADS DEMOLISHED AS PART OF THIS CONTRACT SHALL BE LABELED AS SPARE AND SET TO THE QEE POSITION.
- PROVIDE REVISED CIRCUIT DIRECTORIES IN ALL PANELBOARDS AFFECTED BY NEW OR DEMOLITION WORK. INDICATE ALL LOADS, NEW, SPARE OR MODIFIED.
- FOR ALL LIGHTING BEING RELOCATED OR NOTED AS EXISTING TO REMAIN, REMOVE, CLEAN, RE-LAMP AND REINSTALL COMPLETE IN LOCATIONS AS INDICATED ON NEW WORK PLANS. PROVIDE NEW CONTROL AS INDICATED.
- ALL ELECTRICAL COMPONENTS AND DEVICES INDICATED AS TO REMAIN OR TO BE RELOCATED SHALL BE PROTECTED AGAINST DAMAGE DURING DEMOLITION PROCESS AND CLEANED PRIOR TO BEING RESTORED INTO SERVICE.
- REMOVE ALL EXISTING, ABANDONED WIRING SYSTEMS IN CEILING SPACE, EQUIPMENT ROOMS, SHAFTS, CRAWL SPACES AND SIMILAR CAVITIES OF THE WORK AREA, INCLUDING WIRING, RACEWAYS, BOXES AND SUPPORTS.
- EXISTING CEILING SYSTEMS ARE BEING REMOVED AND REPLACED IN SOME AREAS UNDER THIS CONTRACT. INCLUDE IN BID ALL WORK AS REQUIRED FOR RELOCATION OF ALL EXISTING CEILING MOUNTED ELECTRICAL DEVICES (FIRE ALARM, SENSORS, CAMERAS, CLOCKS, SPEAKERS, ETC.) TO NEW CEILING SYSTEM. PROVIDE REMOVAL, PROTECTION OF, TEMPORARY SUPPORT AND REINSTALLATION COMPLETE.
- COORDINATE WITH PRIME CONTRACTOR FOR ALL PATCHING AND PAINTING AS REQUIRED DUE TO DEMOLITION WORK. NEW FINISHES SHALL MATCH ADJACENT SURFACES.

## SCHNEIDER ELECTRIC ENERGY SERVICES PROJECT

## FOR BRUNSWICK COUNTY SCHOOL DISTRICT

SOUTH BRUNSWICK HIGH SCHOOL  
280 COUGAR ROAD  
SOUTHPORT, NC 28461

## ELECTRICAL SYMBOLS, SCHEDULES AND DETAILS

SHEET TITLE

DATE	DESCRIPTION	REVISION
03-23-22	PROJECT: PC21PD006	
03-23-22	DESIGNED BY: CJA	
03-23-22	CHECKED BY: SDO	
03-23-22	DRAWN BY: CJA	

SHEET NUMBER

E001

SHT. 1 OF 5

ALL RIGHTS RESERVED. THIS DRAWING AND THE DESIGN THEREON IS COPYRIGHTED AND PROTECTED BY THE LAWS OF THE UNITED STATES. NO PART OF THIS DRAWING OR DESIGN MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT THE WRITTEN PERMISSION OF GWA, INC. THIS DRAWING IS NOT TO BE USED FOR ANY OTHER PROJECT WITHOUT THE WRITTEN PERMISSION OF GWA, INC. THIS DRAWING IS NOT TO BE USED FOR ANY OTHER PROJECT WITHOUT THE WRITTEN PERMISSION OF GWA, INC.

GWA, INC. Electrical Engineers

168 Laurelhurst Avenue  
Columbia, SC 29210  
(803)252-6919  
Fax (803)799-5494  
gwa@gwa-inc.net  
http://www.gwa-inc.net



THIS DRAWING IS THE PROPERTY OF SCHNEIDER ELECTRIC AND SUBJECT TO RETURN UPON REQUEST. IT IS NOT TO BE COPIED OR REPRODUCED. NOR IS IT TO BE USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT WAS FURNISHED. WITHOUT THE WRITTEN CONSENT OF SCHNEIDER ELECTRIC.

**ELECTRICAL PLAN - PART "A" - DEMOLITION**  
SCALE: 1/8" = 1'-0"

**ELECTRICAL PLAN - PART "A" - NEW WORK**  
SCALE: 1/8" = 1'-0"



GWA: 21-3670

**GWA**  
inc.  
Electrical Engineers

168 Laurelhurst Avenue  
Columbia, SC 29210  
(803)252-6919  
Fax (803)799-5494  
gwa@gwainc.net  
http://www.gwainc.net

ALL RIGHTS RESERVED. THIS DRAWING AND THE DESIGN THEREON IS CONSIDERED AS PROVIDED BY THE USER OF THE UNITED STATES.  
NONE OF THE INFORMATION ON THIS DRAWING OR ANY INFORMATION HEREON SHALL BE USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT WAS FURNISHED.  
THE DESIGN THEREON WITHOUT THE EXPRESSED WRITTEN PERMISSION OF GWA, INC. SHALL BE SUBJECT TO LEGAL ACTION.

SHEET TITLE  
ELECTRICAL PLAN - DEMO AND  
NEW WORK - AREA A

DRAWN BY: CJA	CHECKED BY: SDO
DESIGNED BY: CJA	APPROVED BY: SDO
DATE: 03-23-22	PROJECT: PC21P0006


SHEET NUMBER

E101

SHT. 2 OF 5

SCHNEIDER ELECTRIC ENERGY SERVICES PROJECT  
FOR  
BRUNSWICK COUNTY SCHOOL DISTRICT  
SOUTH BRUNSWICK HIGH SCHOOL  
280 COUGAR ROAD  
SOUTHPORT, NC 28461

3/23/2022



**Schneider Electric**  
Schneider Electric  
1650 West Croyley Road  
Carrollton, TX 75006 USA  
Tel: +1 972 329 1111  
Fax: +1 972 329 5488  
www.schneider-electric.com

**Schneider Electric**  
1650 West Crosby Road  
Carrollton, TX 75006 USA  
Tel. +1 972 323 1111  
Fax +1 972 323 5498  
[www.schneider-electric.com](http://www.schneider-electric.com)

3/23/2022

SHEET TITLE

ELECTRICAL PLAN - DEMO AND  
NEW WORK - AREA B

**SHEET NUMBER**

SHT. 3 OF 5



- NOTES TO ELECTRICAL WORK - THIS SHEET
1. CIRCUITS INDICATED ON EXISTING EQUIPMENT ARE BASED ON VISUAL OBSERVATION - CONTRACTOR SHALL VERIFY AND NOTIFY ENGINEER OF ANY DISCREPANCIES PRIOR TO NEW WORK BEING COMPLETED.
  2. PROVIDE FUSING IN SAFETY SWITCHES (FUSED DISCONNECTS) TO SUIT NAMEPLATE OF EQUIPMENT CONNECTED. FUSE RATING SHALL NOT EXCEED MOC/MFS RATING OF MECHANICAL EQUIPMENT SERVED.
  3. PROVIDE UPDATED PANELBOARD DIRECTORIES FOR ALL CIRCUITS AFFECTED BY THIS WORK. SEE DEMOLITION NOTES AND SPECIFICATIONS.



ALL RIGHTS RESERVED. THIS DRAWING AND THE DESIGN THEREON IS COPYRIGHTED AS PRESCRIBED BY THE LAWS OF THE UNITED STATES AND IS THE PROPERTY OF CORA, INC. ANY REPRODUCTION, DISTRIBUTION OR CAUTION TO BE DISTRIBUTED THEREON SHALL BE A PART OF THIS DOCUMENT.



THIS DRAWING IS THE PROPERTY OF SCHNEIDER ELECTRIC AND SUBJECT TO RETURN UPON REQUEST. IT IS NOT TO BE COPIED OR REPRODUCED, NOR IS IT TO BE USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT WAS FURNISHED, WITHOUT THE WRITTEN CONSENT OF SCHNEIDER ELECTRIC.

SECTION 26 05 00 – ELECTRICAL, GENERAL

PART 1 – GENERAL

1.1 FEES

A. FEES FOR PERMITS [AND INSPECTIONS] ARE INCLUDED. DELIVER PERMITS [AND CERTIFICATES] TO THE ARCHITECT.

1.2 SITE VISIT

A. PRIOR TO BIDDING, THIS CONTRACTOR SHALL VISIT THE JOB SITE AND SHALL FAMILIARIZE HIMSELF WITH ALL CONDITIONS UNDER WHICH WORK IS TO BE PERFORMED AND SHALL INCLUDE IN HIS BID ALL LABOR, MATERIAL, AND OPERATIONS REQUIRED FOR A COMPLETE JOB.

1.3 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS DO NOT INDICATE ALL HARDWARE AND FITTINGS. EXAMINE ALL PLANS AND SPECIFICATIONS FOR THE PROJECT AND CONDITIONS AT SITE AND ARRANGE WORK ACCORDINGLY. FURNISHING REQUIRED FITTINGS AND HARDWARE WITHOUT EXTRA CHARGE. IF A CONFLICT EXISTS, THE GREATER QUANTITY OR BETTER QUALITY, IN THE OPINION OF THE ENGINEER, GOVERNS.

B. DRAWINGS AND SPECIFICATIONS ARE COMPLEMENTARY; WORK CALLED FOR IN EITHER SHALL BE PROVIDED AS IF CALLED FOR BY BOTH.

1.4 CODES AND STANDARDS

A. MATERIALS, EQUIPMENT AND INSTALLATION SHALL CONFORM TO THE REQUIREMENTS OF THE CODES AND STANDARDS (LATEST EDITIONS) LISTED BELOW. IN ADDITION, ALL MATERIALS, EQUIPMENT, AND DEVICES SHALL MEET THE REQUIREMENTS OF THE UNDERWRITERS' LABORATORIES, INC. THE LABEL OF, OR LISTING BY, THE UNDERWRITERS' LABORATORIES, INC. WILL BE ACCEPTED AS CONFORMING WITH THIS REQUIREMENT. IN LIEU OF THE LABEL OR LISTING, THE CONTRACTOR MAY SUBMIT INDEPENDENT PROOF SATISFACTORY TO THE ENGINEER THAT THE MATERIALS, EQUIPMENT OR DEVICES CONFORM TO THE PUBLISHED STANDARDS, INCLUDING METHODS OF TESTS, OF THE UNDERWRITERS' LABORATORIES, INC. (UL), NATIONAL ELECTRICAL CODE (NEC), NATIONAL ELECTRICAL SAFETY CODE, AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI), AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM), INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE), NATIONAL ELECTRICAL MANUFACTURING ASSOCIATION (NEMA), ILLUMINATING ENGINEERING SOCIETY (IES), NATIONAL FIRE PROTECTION ASSOCIATION (NFPA), NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION STANDARD PRACTICES FOR GOOD WORKMANSHIP IN ELECTRICAL CONTRACTING (NECA 1), INTERNATIONAL BUILDING CODE (IBC) WITH NORTH CAROLINA MODIFICATIONS, AND AMERICANS WITH DISABILITIES ACT (ADA).

1.5 BASIC MATERIALS AND METHODS

A. ALL MATERIALS INSTALLED SHALL BE NEW, CLEAN, IN GOOD CONDITION AND SHALL MEET APPLICABLE PROVISIONS OF CODES AND STANDARDS LISTED ABOVE.

B. WORKMANSHIP SHALL BE IN ACCORDANCE WITH BEST PRACTICE. COMPLY WITH NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION STANDARD PRACTICES FOR GOOD WORKMANSHIP IN ELECTRICAL CONTRACTING (NECA 1).

C. ALL MATERIALS AND EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER GUIDELINES AND INSTALLATION INSTRUCTIONS.

1.6 SCOPE

A. PROVIDE ALL LABOR, EQUIPMENT, MATERIAL, AND OPERATIONS REQUIRED FOR COMPLETE, SAFE AND QUIETLY-OPERATING ELECTRICAL SYSTEMS IN ACCORDANCE WITH SPECIFICATIONS AND DRAWINGS AND SUBJECT TO TERMS AND CONDITIONS OF THE CONTRACT.

B. THE WORK INCLUDES:

1. GROUNDING IN ACCORDANCE WITH SPECIFICATIONS, DRAWINGS AND CODES;

2. COMPLETE DISTRIBUTION SYSTEM FOR POWER INCLUDING PANELBOARDS, SAFETY SWITCHES, FEEDERS, BRANCH CIRCUITS, AND CONNECTIONS TO OUTLETS AND DEVICES FOR POWER UTILIZATION;

3. FIRE ALARM SYSTEM EXTENSION;

4. POWER SUPPLY CONNECTIONS TO MECHANICAL EQUIPMENT;

5. CUTTING, PATCHING, TRENCHING, AND BACKFILLING AS REQUIRED FOR PROVISION OF THE WORK;

6. FIREPROOFING AND CAULKING AS REQUIRED;

7. SEISMIC RESTRAINT FOR ELECTRICAL SYSTEM COMPONENTS;

8. PARTIAL DEMOLITION OF EXISTING ELECTRICAL SYSTEM.

1.7 CUTTING AND PATCHING

A. PROVIDE UNDER THIS CONTRACT ALL CUTTING AND PATCHING OF WALLS, FLOORS, PARTITIONS, CEILING, ETC. REQUIRED FOR PROPER INSTALLATION OF THE NEW SYSTEM.

B. PROVIDE PATCHING TO MATCH EXISTING ADJACENT FINISHES. PAINT TYPE, BRAND AND COLOR SHALL BE IN ACCORDANCE WITH OWNER'S PAINTING STANDARDS.

C. DO NOT CUT JOISTS, BEAMS, GIRDERS, COLUMNS, OR OTHER STRUCTURAL MEMBERS WITHOUT WRITTEN PERMISSION FROM OWNER.

D. RELOCATION OF EXISTING CONDUIT, EQUIPMENT, WIRING, ETC. AS REQUIRED FOR INSTALLATION OF NEW SYSTEM IS INCLUDED IN THIS WORK. PERFORM ALL WORK IN ACCORDANCE WITH SPECIFICATIONS FOR NEW WORK OF THE PARTICULAR TYPE INVOLVED.

1.8 EXCAVATING AND BACKFILLING

A. PROVIDE UNDER THIS CONTRACT ALL EXCAVATING, AND BACKFILLING REQUIRED FOR THE INSTALLATION OF ELECTRICAL WORK.

B. CONTRACTOR SHALL NOTIFY ENGINEER PRIOR TO BACKFILLING, DO NOT BEGIN BACKFILLING UNTIL OWNER'S REPRESENTATIVE HAS OBSERVED THE WORK. EXCAVATIONS SHALL BE FILLED AS SOON AS POSSIBLE AND NOT LEFT OPEN FOR PROLONGED PERIODS.

C. PROVIDE SAFETY (WARNING) BARRICADES AROUND ALL OPEN TRENCHES AND HOLES BEFORE LEAVING UNATTENDED. DO NOT LEAVE EXPOSED WIRING IN A TRENCH UNATTENDED.

D. BACKFILLED SHALL BE DONE IN LAYERS OF 6 INCHES FILL, WETTED DOWN AND TAMPED FOR EACH CONSECUTIVE LAYER UP TO GRADE TO A COMPLETION OF AT LEAST 95 PERCENT OF AASHTO T-99-49 PROCTOR CURVE.

E. WHENEVER TRENCHES HAVE NOT BEEN PROPERLY FILLED, OR IF SETTLEMENT OCCURS, THEY SHALL BE REFILLED, SMOOTHED OFF AND FINALLY MADE TO CONFORM TO THE SURFACE OF THE GROUND. BACKFILLING SHALL BE CAREFULLY PERFORMED AND THE ORIGINAL SURFACE RESTORED TO ORIGINAL CONDITIONS TO THE FULL SATISFACTION OF THE ENGINEER.

1.9 ROOF PENETRATIONS

A. CONTRACTOR SHALL COORDINATE ROOF PENETRATIONS WITH OTHER TRADES AND SHALL PROVIDE ALL WORK REQUIRED FOR COMPLETE RACEWAYS AND RACEWAY SUPPORTS FOR ELECTRICAL WORK FOR ROOF-MOUNTED EQUIPMENT AND DEVICES.

B. PROVIDE FLASHING DEVICES NOT INCLUDED UNDER OTHER DIVISIONS OF THESE SPECIFICATIONS. ALL WORK SHALL COMPLY WITH REQUIREMENTS FOR ROOF CONSTRUCTION AND SHALL IN NO WAY ALTER ANY SPECIFIED ROOF PERFORMANCE OR WARRANTIES.

C. WHERE SEVERAL SERVICES (E.G., ELECTRICAL AND REFRIGERATION) ARE CONNECTED TO A SINGLE EQUIPMENT, COORDINATE WITH OTHER TRADES INVOLVED TO MINIMIZE ROOF PENETRATIONS AND TO PERFORM WORK IN A WORKMANLIKE MANNER.

D. LAY OUT WORK IN ADVANCE AND LOCATE RACEWAY PENETRATIONS AS NEAR EQUIPMENT CONNECTION POINTS AS POSSIBLE. WHERE MORE THAN ONE RACEWAY SERVES EQUIPMENT, EXTEND ALL RACEWAYS THROUGH A COMMON FLASHING DEVICE WITH ONE ROOF PENETRATION AND LEAVE SUFFICIENT SPACE BETWEEN RACEWAYS TO AFFECT A LEAKPROOF SEAL.

E. CONTRACTOR SHALL EXAMINE OTHER DIVISIONS OF THESE SPECIFICATIONS AND SHALL COMPLY WITH ALL REQUIREMENTS FOR A COMPLETE PROJECT.

1.10 PENETRATIONS AND FIRESTOPPING

A. ALL PENETRATIONS THROUGH WALLS, FLOORS, PARTITIONS AND THE LIKE SHALL BE SEALED TIGHT.

B. WHERE CONDUITS PASS THROUGH FIRE-RATED WALLS, FLOORS OR OTHER PARTITIONS, PROVIDE A UL-LISTED THROUGH-PENETRATION ASSEMBLY WITH FIRE RATING EQUAL TO CONSTRUCTION BEING PENETRATED. EACH ASSEMBLY SHALL BE SPECIFIC TO THE PENETRATING MEDIA, SINGLE CONDUIT, MULTIPLE CONDUITS, CABLE TRAY, BUDWY, ETC. AND SHALL BE SPECIFIC TO THE CONSTRUCTION PENETRATED, I.E., CONCRETE, GYPSUM BOARD ON WALL STUDS, ETC. INSTALL ASSEMBLIES IN ACCORDANCE WITH MATERIAL MANUFACTURER'S INSTRUCTIONS AND UL BUILDING MATERIALS DIRECTORY, LATEST EDITION.

C. FIRESTOP SYSTEMS SHALL MEET REQUIREMENTS OF ASTM E-814/UL 1749 TESTED ASSEMBLIES THAT PROVIDE A FIRE RATING EQUAL TO THAT OF CONSTRUCTION BEING PENETRATED.

D. FOR THOSE FIRESTOP APPLICATIONS THAT EXIST FOR WHICH NO UL TESTED SYSTEM IS AVAILABLE THROUGH THE MANUFACTURER, A MANUFACTURER'S ENGINEERING JUDGEMENT DERIVED FROM SIMILAR UL SYSTEM DESIGNS OR OTHER TESTS SHALL BE SUBMITTED TO LOCAL AUTHORITY HAVING JURISDICTION FOR THEIR APPROVAL PRIOR TO INSTALLATION. ENGINEERING JUDGEMENT DRAWINGS SHALL FOLLOW REQUIREMENTS SET FORTH BY THE INTERNATIONAL FIRESTOP COUNCIL.

E. FIRESTOP MATERIALS SHALL BE BY 3M COMPANY, HILTI USA, SPECIFIED TECHNOLOGIES INC (STI), METACALK, TREMCO OR APPROVED EQUAL.

F. SUBMIT UL SYSTEM DETAIL AND PRODUCT DATA FOR EACH FIRE STOP COMPONENT UTILIZED, INCLUDING DETAILED DRAWINGS, INSTALLATION INSTRUCTIONS, ASSEMBLY LISTING NUMBER, CERTIFICATE OF CONFORMANCE AND MATERIAL SAFETY DATA SHEETS.

G. MAINTAIN A COPY OF APPROVED FIRESTOP SYSTEM DETAILS AND PRODUCT DATA ON SITE FOR REVIEW BY ENGINEER, THIRD PARTY INSPECTOR AND AIA.

H. COORDINATE WITH OTHER TRADES AND CONTRACT REQUIREMENTS FOR ADDITIONAL FIRESTOPPING REQUIREMENTS. WHERE REQUIRED, ALL FIRESTOP MATERIAL SHALL BE BY SAME MANUFACTURER AND/OR SAME FIRESTOPPING SUB-CONTRACTOR.

1.11 SEISMIC RESTRAINTS

A. PROVIDE SEISMIC RESTRAINT OF NEW ELECTRICAL SYSTEMS AND EQUIPMENT AS REQUIRED BY APPLICABLE VERSIONS OF INTERNATIONAL BUILDING CODE (IBC) AND ASCE 7. SEISMIC RESTRAINT PRODUCTS SHALL BE BY MASON INDUSTRIES, TOLCO, UNISTRUT CORPORATION, GRINNELL CORPORATION, AMBER BOOTH, PEABODY OR APPROVED EQUAL.

B. FIRE ALARM NAC PANELS, AND RACEWAYS SHALL WITHSTAND THE EFFECTS OF EARTHQUAKE MOTIONS DETERMINED ACCORDING TO ASCE/SEI 7.

1.12 DAMAGES

A. COST OF REPAIRING DAMAGE TO BUILDING, BUILDING CONTENTS, AND SITE DURING CONSTRUCTION AND GUARANTEE PERIOD RESULTING FROM THIS WORK IS A PART OF THIS CONTRACT.

1.13 MATERIAL AND EQUIPMENT

A. NEW AND AS SPECIFIED OR APPROVED EQUAL.

B. WHERE SEVERAL UNITS OF ONE TYPE OF EQUIPMENT ARE USED, ALL UNITS SHALL BE PRODUCTS OF THE SAME MANUFACTURER.

C. ANY INCREASE IN THE COST OF THIS WORK, RESULTING FROM SUBSTITUTION OF ANY PRODUCT OR PRODUCTS FOR THOSE SPECIFIED IS PART OF THIS CONTRACT. SUCH WORK SHALL BE ACCOMPLISHED IN AN APPROVED MANNER AT NO EXTRA COST TO THE OWNER.

1.14 OPERATING INSTRUCTIONS, PANELBOARD DIRECTORIES AND NAMEPLATES

A. INSTRUCT OWNER IN OPERATION OF ALL SYSTEMS.

B. INSTALL IN EACH PANELBOARD A SINGLE-SIDED PLASTIC-COVERED, TYPEWRITTEN CIRCUIT DIRECTORY IN METAL FRAME. INDICATE NAME, ADDRESS AND SERVICE TELEPHONE NUMBER OF INSTALLER. DIRECTORY SHALL LIST THE LOAD SERVED AND THE LOCATION OF THE LOAD FOR EACH BREAKER.

C. NAMEPLATES PROVIDED BY CONTRACTOR: ON ALL PANELBOARDS, DISCONNECT SWITCHES, TRANSFORMERS AND ENCLOSURES, PROVIDE ENGRAVED PLASTIC LAMINATE NAMEPLATES. UNLESS OTHERWISE NOTED, NAMEPLATES TO BE 1/16" THICK PLASTIC WITH 1/4" HIGH WHITE LETTERS ON BLACK BACKGROUND. ATTACH NAMEPLATES WITH EPOXY GROUT OR SCREWS ON MAIN SWITCHBOARD/PANELBOARD AND FEEDER DISTRIBUTION PANELBOARDS, PROVIDE NAMEPLATE FOR EACH CIRCUIT BREAKER.

D. NAMEPLATES PROVIDED BY EQUIPMENT MANUFACTURERS: ALL SWITCHBOARDS, PANELBOARDS, TRANSFORMERS, SAFETY SWITCHES AND THE LIKE SHALL BE PROVIDED WITH ENGRAVED METAL NAMEPLATES WHICH STATE ALL INDUSTRY-STANDARD REQUIRED DATA ABOUT THE LABELED EQUIPMENT. NAMEPLATES SHALL BE AFFIXED WITH SCREWS OR RIVETS. THE USE OF PAPER NAMEPLATES ONLY WILL NOT BE ACCEPTED.

1.15 SHOP DRAWINGS

A. THE ENGINEER WILL REVIEW AND TAKE APPROPRIATE ACTION ON SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND OTHER SUBMITTALS REQUIRED BY THE CONTRACT DOCUMENTS. SUCH REVIEW SHALL BE ONLY FOR GENERAL COMPLIANCE WITH THE DESIGN AND WITH THE INFORMATION GIVEN IN THE CONTRACT DOCUMENTS. IT SHALL NOT INCLUDE REVIEW OF QUANTITIES, DIMENSIONS, WEIGHTS, FABRICATION PROCESSES, CONSTRUCTION METHODS, COORDINATION WITH THE WORK OF OTHER TRADES, OR CONSTRUCTION SAFETY PRECAUTIONS, ALL OF WHICH ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. ENGINEER'S REVIEW SHALL BE CONDUCTED WITH REASONABLE PROMPTNESS CONSISTENT WITH SOUND PROFESSIONAL PRACTICE. REVIEW OF A SPECIFIC ITEM SHALL NOT INDICATE ACCEPTANCE OF AN ASSEMBLY OF WHICH THE ITEM IS A COMPONENT. THE ENGINEER SHALL NOT BE REQUIRED TO REVIEW AND SHALL NOT BE RESPONSIBLE FOR ANY DEVIATIONS FROM THE CONTRACT DOCUMENTS NOT CLEARLY NOTED BY THE CONTRACTOR. NOR SHALL THE ENGINEER BE REQUIRED TO REVIEW PARTIAL SUBMISSIONS OR THOSE FOR WHICH SUBMISSIONS FOR CORRELATED ITEMS HAVE NOT BEEN MADE.

B. PRIOR TO SUBMITTAL OF SHOP DRAWINGS TO THE ENGINEER, THE CONTRACTOR SHALL REVIEW AND APPROVE SHOP DRAWINGS. SHOP DRAWINGS WHICH HAVE NOT BEEN REVIEWED AND APPROVED IN WRITING BY THE ELECTRICAL SUBCONTRACTOR WILL NOT BE REVIEWED BY THE ENGINEER. ELECTRICAL SUBCONTRACTOR SHALL STATE IN WRITING ON SHOP DRAWINGS ANY PROPOSED DEVIATIONS FROM CONTRACT DOCUMENTS. SUCH DEVIATIONS, IF NOT STATED IN SHOP DRAWINGS SUBMITTAL, SHALL BE THE SOLE RESPONSIBILITY OF THE ELECTRICAL SUBCONTRACTOR.

NOTE: IN ADDITION TO THE GENERAL CONTRACTOR'S APPROVAL AND STAMP, THE FIRST PAGE OF EACH SHOP DRAWING SUBMITTAL SHALL CONTAIN THE WORDS "APPROVED BY" AND "APPROVED AS NOTED", AND SHALL BE SIGNED, AND DATED BY THE ELECTRICAL SUBCONTRACTOR BEFORE THE ENGINEER WILL REVIEW THEM.

C. ELECTRICAL SUBCONTRACTOR SHALL SUBMIT FOR REVIEW BY THE ENGINEER DETAILED SHOP DRAWINGS OF ALL EQUIPMENT AND ALL MATERIAL LISTED BELOW. ALL SUBMITTAL DATA SHALL BE SUBMITTED AT ONE TIME – PARTIAL SUBMITTALS WILL NOT BE REVIEWED BY THE ENGINEER. NO MATERIAL OR EQUIPMENT FOR WHICH ENGINEER'S REVIEW IS REQUIRED SHALL BE DELIVERED TO THE JOB SITE OR INSTALLED UNTIL THE CONTRACTOR HAS IN HIS POSSESSION THE REVIEWED SHOP DRAWINGS FOR THE PARTICULAR MATERIAL OR EQUIPMENT. THE SHOP DRAWINGS SHALL BE COMPLETE AS DESCRIBED HEREIN. THIS CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AS DIRECTED BY ARCHITECT OR, IF NO PROCEDURE IS SPECIFIED BY THE ARCHITECT, SUBMIT ONE ELECTRONIC .PDF COPY TO ENGINEER VIA EMAIL: GWAINC@GMAIL.COM.

D. SHOP DRAWINGS SUBMITTED FOR REVIEW SHALL BE DETAILED, DIMENSIONED DRAWINGS OR CATALOG PAGES SHOWING CONSTRUCTION, SIZE, ARRANGEMENT, OPERATING CLEARANCES, PERFORMANCE CHARACTERISTICS AND CAPACITY.

E. SAMPLES, DRAWINGS, SPECIFICATIONS, CATALOGS, SUBMITTED FOR REVIEW SHALL BE PROPERLY LABELED INDICATING SPECIFIC SERVICE FOR WHICH MATERIAL OR EQUIPMENT IS TO BE USED, SECTION AND ARTICLE NUMBER OF SPECIFICATIONS GOVERNING, CONTRACTOR'S NAME, AND PROJECT NAME.

F. CATALOGS, PAMPHLETS, OR OTHER DOCUMENTS SUBMITTED TO DESCRIBE ITEMS ON WHICH REVIEW IS BEING REQUESTED, SHALL BE SPECIFIC AND IDENTIFICATION IN CATALOGS, PAMPHLET, ETC. OF ITEM SUBMITTED SHALL BE CLEARLY MADE IN INK. DATA OF A GENERAL NATURE WILL NOT BE ACCEPTED.

G. REVIEW RENDERED ON SHOP DRAWINGS SHALL NOT BE CONSIDERED AS A GUARANTEE OF MEASUREMENTS OF BUILDING CONDITIONS. WHERE DRAWINGS ARE REVIEWED, SAID REVIEW DOES NOT MEAN THAT DRAWINGS HAVE BEEN CHECKED IN DETAIL. SAID REVIEW DOES NOT MEAN THAT THIS CONTRACTOR TAKES ANY RESPONSIBILITY OR NECESSITY OF FURNISHING MATERIAL OR PERFORMING WORK AS REQUIRED BY THE CONTRACT DRAWINGS AND SPECIFICATIONS.

H. FAILURE OF CONTRACTOR TO SUBMIT SHOP DRAWINGS IN TIME FOR REVIEW BY ENGINEER WITH REASONABLE PROMPTNESS CONSISTENT WITH SOUND PROFESSIONAL PRACTICE SHALL NOT ENTITLE HIM TO AN EXTENSION OF CONTRACT TIME, AND NO CLAIM FOR EXTENSION BY REASON OF SUCH DELAY WILL BE ALLOWED.

I. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR THE FOLLOWING MATERIALS AND EQUIPMENT FOR REVIEW BY ENGINEER: "SEE NOTE" IN PARAGRAPH B, ABOVE.

1. FIRE ALARM SYSTEM EXTENSION INCLUDING BATTERY CALCULATIONS

2. PANELBOARDS

3. CIRCUIT BREAKERS

4. SAFETY SWITCHES

5. BASIC MATERIALS: WIRE, CONDUIT, FITTINGS, CONNECTORS

1.16 RECORD DATA

A. PRESERVE ONE SET OF APPROVED SHOP DRAWINGS AND DELIVER TO OWNER PRIOR TO SUBSTANTIAL COMPLETION OF THE WORK. OWNER'S SHOP DRAWINGS SHALL BE BOUND IN A 3-RING BINDER OF GOOD QUALITY, WITH STIFF VINYL OR CLOTH FRONT AND BACK. NUMBER OF COPIES SHALL BE AS DIRECTED BY ARCHITECT. IN ADDITION, PROVIDE ONE ELECTRONIC COPY (.PDF FORMAT) TO OWNER.

1.17 RECORD DRAWINGS

A. CONTRACTOR SHALL MAINTAIN ON THE JOB SITE ONE COMPLETE SET OF DRAWINGS FOR THIS PROJECT. ALL CHANGES AUTHORIZED BY THE ENGINEERS AND/OR THE OWNER AS TO THE LOCATIONS, SIZES, ETC. OF EQUIPMENT, CONDUIT, FITTINGS, AND/OR OTHER MATERIAL, AND EQUIPMENT SHALL BE INDICATED IN RED PENCIL ON THE DRAWINGS AS THE WORK PROGRESSES. AT THE COMPLETION OF THE PROJECT, THE CONTRACTOR SHALL OBTAIN A COMPLETE SET OF REPRODUCEABLES OF THE DRAWINGS, AND SHALL TRANSFER ALL CHANGES TO THESE REPRODUCEABLES. THE NUMBER OF RECORD PRINTS SPECIFIED BY THE ARCHITECT SHALL BE DELIVERED TO THE ARCHITECT. IN ADDITION, PROVIDE ONE ELECTRONIC COPY (.PDF FORMAT) TO OWNER.

1.18 COORDINATION WITH OTHER TRADES

A. COORDINATE WITH OTHER TRADES TO CONCEAL ELECTRICAL WORK AND PROVIDE ELECTRICAL WORK IN CORRECT LOCATIONS FOR EACH PIECE OF MECHANICAL OR ELECTRICAL EQUIPMENT CONNECTED.

B. CONCEAL OUTLETS FOR ALL MECHANICAL EQUIPMENT, ETC., IN FINISHED AREAS. OBTAIN ROUGHING DIAGRAMS FOR ALL DEVICES AND INSTALL ELECTRICAL WORK ACCORDING TO DIAGRAMS.

C. LOCATE ALL OUTLETS AT UNIFORM HEIGHTS TO SUIT BLOCK COURSING. HEIGHTS SHOWN IN DRAWINGS MAY BE VARIED TO SUIT COURSING, BUT SHALL IN ALL CASES COMPLY WITH CODES.

1.19 ELECTRICAL WORK FOR MECHANICAL SYSTEMS

A. PROVIDE COMPLETE POWER WIRING AND CONNECTIONS FOR MECHANICAL SYSTEMS SPECIFIED UNDER DIVISION 23. THIS WORK INCLUDES ALL RACEWAYS, CONDUCTORS, OUTLET AND PULL BOXES, LINE VOLTAGE ON-OFF SWITCHES WHERE INDICATED AND DISCONNECTING MEANS AS INDICATED AND REQUIRED BY APPLICABLE CODES. WHERE MAGNETIC MOTOR STARTERS, VARIABLE FREQUENCY DRIVES OR OTHER CONTROLS ARE FURNISHED BY OTHERS, WIRE COMPLETE. WHERE CONTROLLERS ARE PROVIDED ALREADY MOUNTED ON EQUIPMENT, WIRE COMPLETE. IN ALL CASES PROVIDE POWER WIRING THROUGHOUT CONDUIT. WIRING AND CONNECTIONS SHALL BE MADE IN ACCORDANCE WITH THE REQUIREMENTS OF THESE SPECIFICATIONS. SAFETY SWITCH ENCLOSURES SHALL BE NEMA TYPE 3R OUTDOORS AND IN WET LOCATIONS; NEMA TYPE 4X IN CORROSIVE ENVIRONMENTS. DO NOT INCLUDE IN THIS DIVISION IS TEMPERATURE CONTROLS, WIRING, EQUIPMENT, CONTROL, WIRING, AND INTERLOCK WIRING REQUIRED TO OPERATE THE MECHANICAL SYSTEM, EXCEPT AS SPECIFIED BELOW FOR WATER HEATERS. REFER TO DIVISION 23 FOR EQUIPMENT PROVIDED UNDER THAT DIVISION.

B. COORDINATE LOCATIONS FOR STARTERS, DRIVES AND OTHER CONTROLS WITH MECHANICAL AND OTHER TRADES AND INSTALL SO THAT ADEQUATE WORKSPACE AND CLEARANCE IS PROVIDED TO ALLOW FOR SAFE OPERATION. COMPLY WITH NEC REQUIREMENTS.

C. SAFETY SWITCHES, ENCLOSED CIRCUIT BREAKERS, MOTOR-RATED TOGGLE SWITCHES AND SIMILAR DISCONNECTING MEANS SHALL BE LOCATED WITHIN LINE OF SIGHT OF EQUIPMENT AND INSTALLED AS REQUIRED TO PROVIDE ADEQUATE WORKSPACE AND CLEARANCES IN ACCORDANCE WITH NEC REQUIREMENTS. COORDINATE LOCATIONS WITH MECHANICAL CONTRACTOR AND OTHER TRADES PRIOR TO ROUGHING.

D. WHERE WATER HEATERS ARE EQUIPPED WITH CIRCULATING PUMPS, AQUASTATS AND OTHER FIELD-INSTALLED CONTROL OR SAFETY DEVICES, WIRE COMPLETE INCLUDING POWER AND CONTROLS.

1.20 EQUIPMENT FOUNDATIONS AND MOUNTING

A. PROVIDE ALL REQUIRED MOUNTING DEVICES, HARDWARE, SUPPLEMENTARY STEEL AND OTHER MATERIALS TO MOUNT EQUIPMENT AND RACEWAYS. ALL MOUNTING SHALL BE SECURED TO STRUCTURAL MEMBERS OR PERSONALLY BRACED COMPLY WITH CODES. WHERE ADDITIONAL STRUCTURAL MEMBERS SUCH AS COLUMNS, BEAMS, AND THE LIKE ARE REQUIRED TO MOUNT EQUIPMENT, THEY SHALL BE PROVIDED AT NO ADDITIONAL COST TO THE OWNER.

1.21 TESTS, PERFORMANCE

A. UPON COMPLETION OF WORK, THE SYSTEM SHALL BE FREE OF FAULTS, INCLUDING SHORT CIRCUITS, GROUNDS AND OPEN CIRCUITS AND LOADS SHALL BE BALANCED ACROSS PHASES TO OBTAIN MINIMUM NEUTRAL CURRENT IN ALL FEEDERS AND BRANCH CIRCUITS. TEST SYSTEMS AS REQUIRED IN THE PRESENCE OF THE ENGINEER OR HIS REPRESENTATIVE, AND OPERATE TO COMPLY WITH APPLICABLE CODES AND CONTRACT DOCUMENTS.

B. FOR ALL FIRE SAFETY SYSTEMS, TEST SYSTEMS COMPLETELY AND EXERCISE ALL USER STATIONS, INITIATION/ACTIVATION STATIONS AND WARNING/ALARM DEVICES PRIOR TO SUBSTANTIAL COMPLETION OF THE WORK. ENGINEER FURNISH CERTIFICATE TO ENGINEER STATING THAT SYSTEMS ARE COMPLETE AND OPERATIONAL AND HAVE BEEN OPERATED BY THE CONTRACTOR AS SPECIFIED ABOVE.

C. ALL COSTS ASSOCIATED WITH CORRECTION OF DEFICIENCIES IN THE WORK SHALL BE BORNE BY THE CONTRACTOR. DEFECTIVE MATERIAL AND EQUIPMENT SHALL BE REPLACED AT NO REPAIR.

D. ALL DEVICES WHICH MUST BE ADJUSTED OR SET TO OPERATE ON A SCHEDULE (TIME CLOCKS, PROGRAM MECHANISMS, ETC.) SHALL BE SET PRIOR TO SUBSTANTIAL COMPLETION TO OPERATE ON SCHEDULES DIRECTED BY THE OWNER.

E. ALL ADJUSTABLE BREAKERS SHALL BE ADJUSTED IN FIELD TO SETTINGS DETERMINED BY AN ENGINEERING COORDINATION STUDY AS REQUIRED TO DETERMINE APPROPRIATE SETTINGS FOR OPTIMAL POWER DISTRIBUTION COORDINATION. INCLUDE IN BID ALL REQUIRED WORK AND ENGINEERING SERVICES AS REQUIRED FOR THIS STUDY AND ADJUSTMENT.

1.22 DEMONSTRATION

A. INSTRUCT OWNER IN OPERATION OF ALL SYSTEMS. TRAIN OWNER'S MAINTENANCE PERSONNEL TO ADJUST, OPERATE, AND MAINTAIN EQUIPMENT.

1.23 WARRANTIES

A. THE CONTRACTOR AGREES:

1. TO CORRECT DEFECTS IN WORKMANSHIP, MATERIALS, EQUIPMENT, AND OPERATION OF ALL SYSTEMS FOR A PERIOD OF ONE YEAR FROM THE DATE OF SUBSTANTIAL COMPLETION.

2. TO REMOVE ANY ITEM NOT SPECIFIED OR GIVEN WRITTEN APPROVAL AND REPLACE IT WITH AN APPROVED ITEM.

3. THAT ALL SYSTEMS PROVIDED WILL SAFELY, QUIETLY, AND EFFICIENTLY OPERATE IN ACCORDANCE WITH THE DESIGN.

B. THIS DOES NOT SUPERSEDE MANUFACTURER'S WARRANTIES WHICH MAY EXTEND BEYOND ONE YEAR.

1.24 CONSTRUCTION SEQUENCE

A. THE CONTRACTOR IS CAUTIONED THAT THE PROJECT MAY BE CONSTRUCTED IN STAGES TO ACCOMMODATE THE OWNER'S USE OF THE BUILDING. THIS CONTRACTOR SHALL VERIFY REQUIREMENTS PRIOR TO BIDDING AND SHALL COOPERATE IN ALL RESPECTS WITH OTHER CONTRACTORS AND TRADES ON THE JOB TO CARRY OUT THE WORK WITH MINIMUM DISRUPTION OF BOTH THE OWNER'S REQUIREMENTS AND CONSTRUCTION OF THE PROJECT.

1.25 DETAILS

A. THE DETAILS AND SKETCHES IN THE DRAWINGS ARE CONSTRUCTION STANDARDS APPLICABLE TO THIS PROJECT.

B. THE CONTRACTOR SHALL COMPLY WITH DETAILS AS APPLICABLE TO THE WORK INDICATED AND SHALL RETAIN ON THE JOB SITE AT ALL TIMES, A COMPLETE SET OF DRAWINGS AND SPECIFICATIONS.

1.26 DEFINITIONS

A. IN THIS DIVISION OF THE SPECIFICATIONS AND ACCOMPANYING DRAWINGS, THE FOLLOWING DEFINITIONS APPLY:

1. PROVIDE: TO PURCHASE, PAY FOR, TRANSPORT TO THE JOB SITE, UNPACK, INSTALL AND CONNECT COMPLETE AND READY FOR OPERATION; TO INCLUDE ALL PERMITS, INSPECTIONS, EQUIPMENT, MATERIAL, LABOR, HARDWARE AND OPERATIONS REQUIRED FOR COMPLETION.

2. INSTALL: TO RECEIVE FROM ANOTHER CONTRACTOR, THE OWNER OR ANOTHER ENTITY AND INSTALL COMPLETE AND READY FOR OPERATION, UNLESS OTHERWISE INDICATED. RECEIPT IS ASSUMED TO BE AT THE JOB SITE.

3. FURNISH: TO PURCHASE, PAY FOR AND DELIVER TO THE JOB SITE FOR INSTALLATION BY OTHERS.

4. THE CONTRACTOR IS CAUTIONED THAT "FURNISH" AND "INSTALL" REQUIRE COORDINATION WITH OTHERS. SUCH COORDINATION SHALL BE ACCOMPLISHED PRIOR TO BIDDING AND BID AMOUNTS SHALL INCLUDE ALL REQUIRED LABOR, MATERIAL AND OPERATIONS FOR COMPLETION OF ALL ITEMS AND SYSTEMS SPECIFIED AND INDICATED.

5. AS INDICATED: AS SHOWN IN DRAWINGS.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION (NOT USED)

END OF SECTION 26 05 00

SECTION 26 05 10 – ELECTRICAL, DEMOLITION

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. THE FOLLOWING APPLY TO THE WORK UNDER THIS SECTION:

1. SECTION 26 05 00, ELECTRICAL, GENERAL.

2. SECTION 26 20 00, INTERIOR WIRING SYSTEMS.

1.2 SCOPE

A. PROVIDE ALL LABOR, MATERIAL AND OPERATION REQUIRED FOR REMOVAL OF EXISTING ELECTRICAL SYSTEMS AS INDICATED.

B. BIDDERS SHALL VISIT THE SITE OF THE WORK PRIOR TO BIDDING AND SHALL INCLUDE IN BID ALL WORK REQUIRED TO PROVIDE NEW WORK AND TO MODIFY EXISTING WORK AS REQUIRED TO CONTINUE IN OPERATION.

C. CONTRACTOR SHALL EXAMINE DEMOLITION AND NEW WORK PLANS FOR ALL TRADES AND INCLUDE IN BID ALL NEWWORK AND/OR RELOCATION OF EXISTING RACEWAY, JUNCTION BOXES, PANELBOARDS, SAFETY SWITCHES, DEVICES, WIRING SYSTEMS AND ALL OTHER RELATED ELECTRICAL EQUIPMENT AS REQUIRED TO ACCOMMODATE NEW CONSTRUCTION.

D. ELECTRICAL DEMOLITION WORK GENERALLY INCLUDES:

1. EXISTING CIRCUIT BREAKERS, SAFETY SWITCHES AND OTHER ELECTRICAL EQUIPMENT AS INDICATED;

2. EXISTING FIRE ALARM DEVICES AS REQUIRED. EXISTING FIRE ALARM SYSTEM SHALL REMAIN IN OPERATION DURING CONSTRUCTION;

3. EXPOSED CONDUITS, SURFACE METAL RACEWAYS AND EXPOSED OUTLET BOXES AND DEVICES AS INDICATED;

4. CONDUCTORS EXPOSED AND CONCEALED AS INDICATED;

5. EXISTING WIRING DEVICES AS INDICATED, WHERE NEW WIRING DEVICES ARE SHOWN IN EXISTING LOCATIONS, THE CONTRACTOR MAY RE-USE EXISTING DEVICES AND OUTLET BOX FOR NEW DEVICES;

6. EXISTING ELECTRICAL WORK FOR MECHANICAL EQUIPMENT BEING REMOVED BY OTHERS;

7. WHERE INDICATED ON DRAWINGS, EXISTING RACEWAYS MAY BE REUSED FOR NEW CIRCUITS. CONTRACTOR SHALL MANDEREL BRUSH AND SWAB EXISTING FEEDER CONDUITS PRIOR TO PULLING NEW CONDUCTORS.

E. INCLUDE IN BID ALL WORK REQUIRED FOR TEMPORARY WIRING AND ASSOCIATED ELECTRICAL WORK REQUIRED TO MAINTAIN EXISTING SYSTEMS IN SERVICE DURING DEMOLITION PHASE.

F. ALL INTERRUPTIONS IN ELECTRICAL SYSTEMS (POWER, LIGHTING, COMMUNICATION, FIRE ALARM AND OTHER SYSTEMS) AS REQUIRED FOR THIS WORK SHALL BE COORDINATED WITH AND APPROVED BY OWNER PRIOR TO PERFORMING WORK. NOTICE SHALL BE PROVIDED TO OWNER IN WRITING A MINIMUM OF 48 HOURS IN ADVANCE, BUT NOT LESS THAN THE TIME SPECIFIED IN OTHER PORTIONS OF CONTRACT DOCUMENTS.

G. THE INTENT OF THIS SPECIFICATION IS TO OBTAIN REMOVAL OF THE EXISTING ELECTRICAL SYSTEM TO THE EXTENT REQUIRED TO ENABLE THE OWNER TO IDENTIFY, SERVICE, REPAIR OR MODIFY THE NEW WIRING SYSTEM EFFICIENTLY AND SAFELY.

1.3 STANDARDS

A. DEMOLITION WORK SHALL COMPLY WITH ANSI A106, NFPA 241, OSHA, AHERA AND ALL APPLICABLE LOCAL, STATE AND FEDERAL STANDARDS AND GUIDELINES.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 EXAMINATION

A. VERIFY THAT UTILITIES IN WORK AREA HAVE BEEN DISCONNECTED AND CAPPED AS REQUIRED.

B. SURVEY EXISTING CONDITIONS AND CORRELATE WITH DEMOLITION AND NEW WORK INDICATED IN CONTRACT DOCUMENTS TO DETERMINE EXTENT OF DEMOLITION REQUIRED.

C. WHEN UNANTICIPATED MECHANICAL, ELECTRICAL, ENVIRONMENTAL OR STRUCTURAL ELEMENTS THAT CONFLICT WITH INTENDED FUNCTION OR DESIGN ARE ENCOUNTERED, INVESTIGATE AND MEASURE THE NATURE AND EXTENT OF CONFLICT. PROVIDE PROMPT WRITTEN NOTICE TO ENGINEER OF ANY CONFLICTS.

3.2 DEMOLITION

A. OWNER SHALL RETAIN FIRST RIGHT OF REFUSAL ON ALL ELECTRICAL EQUIPMENT BEING DEMOLISHED. PRIOR TO BEGINNING DEMOLITION WORK, CONTRACTOR SHALL WALK THROUGH DEMOLITION AREA WITH OWNER'S REPRESENTATIVE, AND IDENTIFY ITEMS TO BE REMOVED. DEMOLITION WORK SHALL BE TURNED OVER TO OWNER AND DELIVER TO OWNER AT LOCATION ON SITE AS DIRECTED BY OWNER.

B. MAINTAIN SERVICES AND SYSTEMS INDICATED TO REMAIN AND PROTECT THEM AGAINST DAMAGE DURING DEMOLITION PROCESS.

C. ALL DEVICES INDICATED AS TO REMAIN OR TO BE RELOCATED SHALL BE PROTECTED AGAINST DAMAGE DURING DEMOLITION PROCESS AND CLEANED PRIOR TO BEING RESTORED INTO SERVICE.

D. CONTRACTOR SHALL PATCH AND RESTORE FINISH TO MATCH ADJACENT SURFACE AT ALL LOCATIONS RESULTING FROM DEMOLITION AT WHICH NEW WORK IS NOT INSTALLED, AS REQUIRED UNDER SECTION 26 05 00, ELECTRICAL, GENERAL.

E. PROVIDE TEMPORARY BARRICADES, DUST BARRIERS AND OTHER PROTECTION REQUIRED TO PREVENT INJURY TO PEOPLE AND DAMAGE TO BUILDING CONTENTS, ADJACENT AREA OF BUILDING AND FACILITIES TO REMAIN.

F. MAINTAIN PROTECTED EGRESS AND ACCESS AT ALL TIMES. DO NOT CLOSE OR OBSTRUCT ROADWAYS OR SIDEWALKS WITHOUT PERMISSION FROM OWNER.

G. CONDUCT DEMOLITION TO MINIMIZE INTERFERENCE WITH OWNER'S USE OF SITE.

H. CONDUCT OPERATIONS WITH MINIMUM INTERFERENCE TO PUBLIC OR PRIVATE ACCESS.

3.3 DISPOSAL OF DEMOLISHED MATERIALS

A. DEMOLISHED MATERIAL SHALL BE PROMPTLY REMOVED FROM SITE.

B. REMOVE AND TRANSPORT MATERIALS IN A MANNER THAT WILL PREVENT CONTAMINATION OR DAMAGE TO ADJACENT SURFACES AND AREAS.

C. BURNING OF DEMOLISHED MATERIALS WILL NOT BE PERMITTED ON SITE.

D. ALL MATERIALS SHALL BE PROPERLY AND LEGALLY DISPOSED OF. CONTRACTOR IS RESPONSIBLE FOR ALL HANDLING, STORAGE, TRANSPORTATION AND DISPOSAL FEES.

3.4 CLEANING

A. CLEAN ADJACENT STRUCTURES AND IMPROVEMENTS OF DUST, DIRT AND DEBRIS CAUSED BY DEMOLITION OPERATIONS.

B. RETURN ADJACENT AREAS TO CONDITION EXISTING BEFORE DEMOLITION OPERATIONS BEGAN.

END OF SECTION 26 05 10

SECTION 26 20 00 – INTERIOR WIRING SYSTEMS

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. SECTION 26 05 00, ELECTRICAL, GENERAL, APPLIES TO THE WORK UNDER THIS SECTION.

1.2 SCOPE

A. PROVIDE INTERIOR WIRING SYSTEMS COMPLETE AND READY FOR OPERATION, AS INDICATED, SPECIFIED HEREIN AND IN COMPLIANCE WITH APPLICABLE CODES AND STANDARDS.

PART 2 – PRODUCTS

2.1 MANUFACTURERS

A. MATERIALS OF LIKE TYPE SHALL BE MANUFACTURED BY THE SAME COMPANY.

B. PANELBOARDS, CIRCUIT BREAKERS, SAFETY SWITCHES, MOTOR STARTERS, CONTACTORS AND THE LIKE: GE/ABB, SIEMENS-ITE, SQUARE D, Eaton, OR APPROVED EQUAL.

C. FITTINGS, CONDUITS, BOXES AND THE LIKE: STEEL CITY, THOMAS AND BETTS, O-Z ELECTRICAL MANUFACTURING COMPANY, APPLETON, EFCO, CROUSE-HINDS, GAYN INDUSTRIES, OR APPROVED EQUAL.

D. CONDUCTORS AND CABLES: ALPHA WIRE COMPANY, BELDEN, CERRO WIRE, SOUTHWIRE COMPANY, GENERAL CABLE OR APPROVED EQUAL.

E. CABLE MARKERS: 3M COMPANY, E-Z CODE, BRADY, OR APPROVED EQUAL.

F. CONNECTORS, LUGS AND TERMINALS AND THE LIKE: 3M COMPANY, IDEAL, THOMAS AND BETTS, O-Z ELECTRICAL MANUFACTURING COMPANY, OR APPROVED EQUAL.

G. WIRING DEVICES AND THE LIKE: BEST SPECIFICATION GRADE: ARROW HART/COOPER, HUBBELL, LEGRAND/P&S, LEVITON, OR APPROVED EQUAL.

H. FUSES: DUAL-ELEMENT TYPE, "FUSETRON" BY BUSSMAN OR "ECON" BY ECONOMY OR APPROVED EQUAL.

I. GROUNDING DEVICES, AND THE LIKE: CADWELD, THOMAS AND BETTS, APPLETON, EICO, O-Z ELECTRICAL MANUFACTURING COMPANY, OR APPROVED EQUAL.

2.2 CONDUIT AND FITTINGS

A. RIGID STEEL CONDUIT (ZINC-COATED): ANSI C80.1.

B. RIGID NONMETALLIC CONDUIT: PVC TYPE EPC-40 IN ACCORDANCE WITH NEMA TC2.

C. INTERMEDIATE METAL CONDUIT (IMC): UL 1242, ZINC-COATED STEEL ONLY.

D. ELECTRICAL METALLIC TUBING (EMT): ANSI C80.3.

E. FLEXIBLE METAL CONDUIT: UL 1.

F. LIQUID-TIGHT FLEXIBLE METAL CONDUIT (STEEL): UL 360.

G. FITTINGS FOR METAL CONDUIT, ELECTRICAL METALLIC TUBING, AND FLEXIBLE METAL CONDUIT: UL 514. ALL FERROUS FITTINGS SHALL BE CADMIUM- OR ZINC-COATED IN ACCORDANCE WITH UL 514.

I. FITTINGS FOR RIGID METAL CONDUIT AND IMC SHALL BE THREADED TYPE. SPLIT COUPLINGS ARE NOT ACCEPTABLE.

J. FITTINGS FOR ELECTRICAL METALLIC TUBING (EMT) SHALL BE THE COMPRESSION TYPE.

K. FITTINGS FOR RIGID NONMETALLIC CONDUIT: NEMA TC3.

2.3 OUTLET BOXES AND COVERS

A. UL 514, CADMIUM- OR ZINC-COATED IF OF FERROUS METAL.

B. PROVIDE OUTLET BOXES OF SIZE AND TYPE SPECIFIED BY NEC, AND IN NO CASE SMALLER THAN THE FOLLOWING:

1. BOXES FOR SWITCHES AND RECEPTABLES: 3" x 2" x 2-3/4" OR 4" x 4" x 1-1/2" WITH PLASTER RIM TO SUIT CONSTRUCTION

C. PROVIDE SUITABLE EXTENSIONS, RINGS OR SUBCOVERS SET TO COME FLUSH WITH THE FINISHED SURFACE IN WHICH BOXES ARE MOUNTED.

D. BOXES FOR EXPOSED RACEWAY SHALL BE THREADED-HUB CAST METAL, SIZES AS SPECIFIED ABOVE.

2.4 CABINETS, JUNCTION BOXES, AND PULL BOXES

A. UL 50, HOT-DIP ZINC-COATED, CODE GAUGE SHEET STEEL, SCREW COVER UNLESS INDICATED OTHERWISE.

2.5 WIRES AND CABLES

A. WIRES AND CABLES SHALL MEET THE APPLICABLE REQUIREMENTS OF NFPA 70 AND UL FOR THE TYPE OF INSULATION, JACKET, AND CONDUCTOR SPECIFIED OR INDICATED. ALL WIRE AND CABLE SHALL BE NEW, WITH SIZE, GRADE OF INSULATION, VOLTAGE, AND MANUFACTURER'S NAME PERMANENTLY IMPRINTED ON OUTER COVERING AT REGULAR INTERVALS AND DELIVERED TO THE JOB SITE IN COMPLETE COILS AND REELS.

B. CONDUCTORS: CONDUCTORS NO. 10 AWG AND SMALLER SHALL BE SOLID, AND THOSE NO. 8 AWG AND LARGER SHALL BE STRANDED, UNLESS INDICATED OTHERWISE. CONDUCTOR SIZES SHOWN ARE BASED ON COPPER. ALL CONDUCTORS SHALL BE COPPER.

C. MINIMUM CONDUCTOR SIZES: MINIMUM SIZE FOR BRANCH CIRCUITS SHALL BE NO. 12 AWG; FOR CLASS 1 REMOTE-CONTROL AND SIGNAL CIRCUITS, NO. 14 AWG; AND FOR CLASS 2 LOW-ENERGY REMOTE-CONTROL AND SIGNAL CIRCUITS, NO. 18 AWG. ALL 120 V, BRANCH CIRCUITS EXCEEDING 100' IN LENGTH AND ALL 277 V, BRANCH CIRCUITS EXCEEDING 250' IN LENGTH SHALL BE NO. 10 AWG, MINIMUM.

D. COLOR CODING: PROVIDE FOR ALL SERVICE, FEEDER, BRANCH, CONTROL, AND SIGNALING CIRCUIT CONDUCTORS. COLOR SHALL BE GREEN FOR GROUNDING CONDUCTORS, AND WHITE FOR NEUTRALS, EXCEPT WHERE NEUTRALS OF MORE THAN ONE SYSTEM ARE INSTALLED IN SAME RACEWAY OR BOX. THE NEUTRAL OF THE HIGHER-VOLTAGE SYSTEM AND WHITE OF THE LOWER-VOLTAGE SYSTEM OR SHALL BE GRAY. THE COLOR OF THE UNGROUNDING CONDUCTORS IN DIFFERENT VOLTAGE SYSTEMS SHALL MATCH EXISTING.

E. COLOR CODING FOR FIRE ALARM CONDUCTORS SHALL BE THE MANUFACTURER'S STANDARD AND SHALL BE CONSISTENT THROUGHOUT THE SYSTEM. INCLUDE COLOR CODING KEY WITH RECORD DATA.

F. INSULATION: UNLESS SPECIFIED OR INDICATED OTHERWISE, OR REQUIRED TO BE OTHERWISE BY NFPA 70, ALL POWER AND LIGHTING WIRES SHALL BE 90C-VOLT, TYPE THHN, THHW, OR XHHW. REMOTE-CONTROL AND SIGNAL CIRCUITS SHALL BE TYPE TW, THHN, TH, THWN OR XHHW.

G. BONDING CONDUCTORS: ASTM B 1, SOLID BARE COPPER WIRE FOR SIZES NO. 8 AWG AND SMALLER; ASTM B 8, CLASS B, STRANDED BARE COPPER WIRE FOR SIZES NO. 6 AWG AND LARGER.

H. NONMETALLIC-SHEATHED CABLE: NOT PERMITTED.

2.6 ELECTRICAL CONNECTIONS

A. COMPLY WITH NEC ARTICLE 110-14.

B. ALL TERMINATION DEVICES, SUCH AS CONNECTORS, SPLICING DEVICES, EQUIPMENT TERMINALS, DEVICE TERMINALS AND THE LIKE SHALL BE RATED AND LISTED FOR OPERATION AT 75 DEGREES C.

2.7 SPLICES AND TERMINATION COMPONENTS

A. UL 486A AND UL 486B, AS APPLICABLE FOR WIRE CONNECTORS, AND UL 510 FOR INSULATING TAPES, CONNECTORS FOR WIRES NO. 10 AND SMALLER AND SHOWN IN RECORD DATA. PROVIDE WIRE CONNECTORS WITH 486A OR UL 486B (TWIST-ON SPLICING CONNECTOR). PROVIDE SOLDERLESS TERMINAL LUGS ON STRANDED CONDUCTORS.

B. SPLICES AND/OR TAPS FOR #6 AND LARGER CONDUCTORS SHALL BE CRIMP TYPE BY TABB, BURNDY, OZ, OR APPROVED EQUAL; OR ILSCO KUP-L-TAP; CLEARAP, OR APPROVED EQUAL.

2.8 DEVICE PLATES

A. PROVIDE UL LISTED, ONE-PIECE DEVICE PLATES FOR OUTLETS AND FITTINGS TO SUIT THE DEVICES INSTALLED. PLATES ON UNFINISHED WALLS AND ON FITTINGS SHALL BE OF ZINC-COATED SHEET STEEL, OR CAST METAL HAVING ROUND OR BEVELED EDGES. PLATES ON FINISHED WALLS SHALL BE OF ALUMINUM. MINIMUM 0.10 INCH WALL THICKNESS, AND SHALL BE THE SAME COLOR AS THE RECEPTACLE OR TOGGLE SWITCH WITH WHICH IT IS MOUNTED, OR SHALL BE SATIN FINISH STAINLESS STEEL OR BRUSHED-FINISH ALUMINUM, MINIMUM 1/8 INCH THICK. ALL DEVICES SHALL BE MOUNTED ON DEVICES SHALL BE MACHINE TYPE WITH COUNTERSUNK HEADS IN A COLOR TO MATCH THE FINISH OF THE PLATE. THE USE OF SECTIONAL TYPE DEVICE PLATES WILL NOT BE PERMITTED. PLATES INSTALLED IN WET LOCATIONS SHALL BE GASKETED. ALL PLATES SHALL BE OVERSIZE TYPE.

2.9 SWITCHES

A. TOGGLE SWITCHES: FED. SPEC. W-S-896, TOTALLY ENCLOSED WITH BODIES OF THERMOSETTING PLASTIC AND A MOUNTING STRAP. HANDLES SHALL BE WHITE, GRAY, BROWN OR IVORY. WIRING TERMINALS SHALL BE OF THE SCREW TYPE, SIZE WREDS. SWITCHES SHALL BE RATED QUIET-TYPE AC ONLY, 120/277 VOLTS, WITH THE CURRENT RATING AND NUMBER OF POLES INDICATED. COLORS SHALL BE AS DIRECTED BY ARCHITECT.

B. DISCONNECT SWITCHES: NEMA KS1. PROVIDE HEAVY DUTY, FUSIBLE TYPE. GENERAL DUTY AND NON-FUSIBLE SWITCHES ARE NOT PERMITTED.

1. OPERATING MECHANISMS SHALL BE OF THE QUICK-MAKE, QUICK-BREAK TYPE, WITH ARC-SUPPRESSING CHARACTERISTICS.

2. ENCLOSURES SHALL BE NEMA 1 INDOORS AND NEMA 3R OUTDOORS AND IN WET LOCATIONS UNLESS OTHERWISE INDICATED. EQUIPPED WITH CROUCH INTERLOCK AND PROVISIONS FOR PADLOCKING OPERATING HANDLE IN OFF POSITION. SHALL CAREFULLY SHIELD BREAKERS FROM VIEW OF OPERATOR AS PANELBOARDS AS PANELBOARDS.

3. SAFETY SWITCHES USED AS MOTOR DISCONNECT MEANS AND LOCATED ON LOAD SIDE OF VARIABLE FREQUENCY DRIVES (VFDs) SHALL BE PROVIDED WITH FACTORY MOUNTED AUXILIARY CONTACTS TO ALLOW COMMUNICATION OF SWITCH POSITION TO VFD.

2.10 RECEPTABLES

A. NEMA WD1, HEAVY-DUTY, GROUNDING TYPE. RATINGS AND CONFIGURATIONS SHALL BE AS INDICATED. BODIES SHALL BE OF WHITE, GRAY, BROWN OR IVORY THERMOSETTING PLASTIC SUPPORTED ON A METAL MOUNTING STRAP. WIRING TERMINALS SHALL BE OF THE SCREW TYPE, SIZE WREDS. CONNECT GROUNDING POLE TO THE MOUNTING STRAP. COLORS SHALL MATCH EXISTING.

B. WEATHERPROOF RECEPTABLES: IN ALL DAMP OR WET LOCATIONS, PROVIDE IN A CAST METAL BOX WITH A GASKETED, WEATHERPROOF, CAST-METAL COVER PLATE AND A GASKETED CAP OVER EACH RECEPTACLE. OPENING THE CAP(S) SHALL BE PROVIDED WITH A SPRING-HINGED FLAP. COVER SHALL BE IN USE TYPE WHERE REQUIRED BY LOCAL CODES. RECEPTACLE SHALL BE LISTED FOR USE IN DAMP LOCATION OR WET LOCATION OR SUIT INSTALLATION LOCATION.

C. GROUND FAULT CIRCUIT INTERRUPTER RECEPTABLES: UL 943, AND SHALL BE DUPLEX TYPE FOR MOUNTING IN A STANDARD OUTLET BOX. THE DEVICE SHALL BE CAPABLE OF DETECTING A CURRENT LEAK OF 5 MILLIAMPERES.

D. RECEPTABLES SHALL BE BY SAME MANUFACTURER AS TOGGLE SWITCHES, AS SPECIFIED ABOVE.

E. INSTALL GROUNDING TYPE RECEPTABLES WITH THE GROUNDING TERMINAL AT THE TOP.

2.11 PANELBOARDS

A. UL 67 AND UL 50, PANELBOARDS FOR USE AS SERVICE DISCONNECTING MEANS SHALL ADDITIONALLY CONFORM TO UL 869. PANELBOARD BUSES SHALL BE PROVIDED WITH BREAKER EQUIPPED UNLESS OTHERWISE INDICATED. DESIGN SHALL BE SUCH THAT ANY INDIVIDUAL BREAKER CAN BE REMOVED WITHOUT DISTURBING ADJACENT UNITS OR WITHOUT LOOSENING OR REMOVING SUPPLEMENTAL INSULATION SUPPLIES. CLEARANCES AND WORKSPACE SHALL BE OBTAINED AS INDICATED. DIRECTORIES SHALL BE INDICATED, MAKE PROVISIONS FOR THE FUTURE INSTALLATION OF A BREAKER LARGER AS INDICATED. DIRECTORIES SHALL BE TYPED TO INDICATE LOAD SERVED BY EACH CIRCUIT AND MOUNTED IN A HOLDER BEHIND TRANSPARENT PROTECTIVE COVERING. DIRECTORY LISTING FOR EACH BREAKER SHALL LIST THE LOAD SERVED (LIGHTING, RECEPTABLES, ETC.) AND LOCATION OF LOAD (ROOM NAME, ROOM NUMBER, ETC.).

B. PANELBOARD BUSES: SUPPORT BUS BARS ON BASES INDEPENDENTLY OF THE CIRCUIT BREAKERS. MAIN BUSES AND BACK PANS SHALL BE DESIGNED SO THAT BREAKERS MAY BE CHANGED WITHOUT MACHINING, DRILLING, OR TAPPING. PROVIDE AN ISOLATED NEUTRAL BUS IN EACH PANEL FOR CONNECTION OF CIRCUIT NEUTRAL CONDUCTORS. PROVIDE A SEPARATE GROUND BUS MARKED WITH A GREEN STRIPE ALONG ITS FRONT AND BONDED TO THE STEEL CABINET FOR CONNECTING GROUNDING CONDUCTORS.

C. CIRCUIT BREAKERS: FED. SPEC. W-C-375 THERMAL, MAGNETIC TYPE WITH INTERRUPTING CAPACITY AS INDICATED OR TO MATCH EXISTING. BREAKER TERMINALS SHALL BE UL LISTED AS SUITABLE FOR THE TYPE OF CONDUCTOR PROVIDED. PLUG-IN CIRCUIT BREAKERS SHALL BE PROVIDED ONLY WHERE INDICATED IN DRAWINGS.

1. MULTI-POLE BREAKERS: PROVIDE COMMON-Trip TYPE WITH A SINGLE OPERATING HANDLE. BREAKER DESIGN SHALL BE SUCH THAT AN OVERLOAD IN ONE POLE AUTOMATICALLY CAUSES ALL POLES TO OPEN. MAINTAIN PHASE SEQUENCE THROUGHOUT EACH PANEL SO THAT ANY THREE ADJACENT BREAKER POLES ARE CONNECTED TO PHASES A, B, AND C, RESPECTIVELY.

2. CIRCUIT BREAKER WITH GROUND-FAULT CIRCUIT INTERRUPTER: UL 1053 AND NFPA 70. PROVIDE WITH "PUSH-TO-TEST" BUTTON, VISIBLE INDICATION OF TRIPPED CONDITION, AND ABILITY TO DETECT A CURRENT IMBALANCE OF APPROXIMATELY 5 MILLIAMPERES.

3. CIRCUIT BREAKER FOR ARC-FAULT CIRCUIT INTERRUPTER: UL 1699 AND NFPA 70. PROVIDE "PUSH-TO-TEST" BUTTON AND VISUAL INDICATION OF TRIPPED CONDITION.

4. BREAKERS USED TO SERVE REFRIGERATION AND AIR CONDITIONING COMPRESSORS SHALL BE TYPE HACR.

5. CIRCUIT BREAKER USED TO SERVE FIRE ALARM COMPONENTS SHALL BE PROVIDED WITH RED, LOCKING HARDWARE AS WELL AS RED ENGRAVED NAMEPLATE MOUNTED IMMEDIATELY ADJACENT TO BREAKER.

D. CONSTRUCTION:

1. ALL PANELBOARDS SHALL HAVE HINGED, LOCKABLE FRONT COVERS. ALL PANELBOARD LOCKS INCLUDED IN THE PROJECT SHALL BE KEYPED ALIKE AND EACH SHALL BE PROVIDED WITH TWO (2) KEYS.

2. FOR SURFACE-MOUNT FRONTS, MATCH BOX DIMENSIONS; FOR FLUSH-MOUNTED FRONTS, PROVIDE COVER WITH OVERLAP TRIM. TRIMS SHALL COVER ALL LIVE PARTS AND SHALL HAVE NO EXPOSED HARDWARE.

E. PANELBOARDS SHALL BE RATED FOR ENVIRONMENTAL CONDITIONS AT LOCATION WHERE INSTALLED:

1. INDOORS, DRY AND CLEAN CONDITIONS: NEMA 250, TYPE 1.

2. OUTDOORS, NEMA 250, TYPE 3R

3. KITCHEN OR WASH-DOWN AREAS: NEMA 250, TYPE 4X

4. OTHER WET OR DAMP INDOOR LOCATIONS: NEMA 250, TYPE 4

5. INDOOR LOCATIONS SUBJECT TO DUST, FALLING DIRT AND DRIPPING NONCORROSIVE LIQUIDS: NEMA 250, TYPE 5

6. PUMP STATIONS, LIFT STATIONS, VICINITY OF WASTEWATER, POOL EQUIPMENT OR SIMILAR CORROSIVE ENVIRONMENTS: NEMA 250, TYPE 4X, STAINLESS STEEL.

2.12 FUSES

A. PROVIDE A COMPLETE SET OF FUSES FOR EACH FUSIBLE DEVICE PROVIDED. TIME-CURRENT CHARACTER



- A. PROVIDE GROUNDING SYSTEM TO COMPLY WITH NEC, AS SHOWN ON DRAWINGS AND AS SPECIFIED.
- B. ALL GROUND SYSTEM COMPONENTS AND FITTINGS USED SHALL BE FREE FROM PAINT, GREASE, AND OTHER POORLY CONDUCTING MATERIAL, AND CONTACT SURFACES SHALL BE CLEANED THOROUGHLY TO ENSURE GOOD METAL-TO-METAL CONTACT.
- C. INSTALL GROUNDING JUMPERS BETWEEN ALL PANELBOARDS AND FEEDER RACEWAYS CONNECTED THERETO; ACROSS PULL BOXES AND RACEWAY EXPANSION JOINTS AND ACROSS WATER METERS LOCATED WITHIN BUILDINGS.
- D. PROVIDE A GROUND WIRE IN ALL GROUITS SIZED PER NEC TABLE 250-122 AS APPLICABLE.
- E. PROVIDE IN ALL RUNS OF FLEXIBLE CONDUIT A SEPARATE GROUNDING CONDUCTOR SIZED PER NEC TABLE 250-122.

END OF SECTION 28 31 10